

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6713	05-00148-00-PV	TAZEWELL	74	04
STA. 145+50.00		TO STA. 156+60.00		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES				TAZEWELL COUNTY		
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	5000-2A	7071-2A	7031-1F
				ROADWAY	CAMP ST. BRIDGE	TRAFFIC SIGNALS
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2.0	2.0		
63200310	GUARDRAIL REMOVAL	FOOT	71.0	71.0		
* 63301990	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	1.0	1.0		
66400105	CHAIN LINK FENCE, 4'	FOOT	68.0	68.0		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1.0		1.0	
* 66900205	SPECIAL WASTE DISPOSAL	CU YD	5262.0	5262.0		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	22.0	22.0		
67100100	MOBILIZATION	L SUM	1.0	1.0		
701001700	TRAFFIC CONTROL AND PROTECTION	L SUM	1.0	1.0		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	555.0	555.0		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	200.0	200.0		
72000100	SIGN PANEL - TYPE 1	SQ FT	11.3	6.3		5.0
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	9.0	9.0		
72900100	METAL POST - TYPE A	FOOT	58.0	58.0		
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	44.0	44.0		
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	2529.0	2529.0		
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	478.0	478.0		
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	360.0	360.0		
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	293.0	293.0		
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	107.0	107.0		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	7.0	7.0		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1.0	1.0		
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1013.0			1013.0
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	84.0			84.0
* 81100600	CONDUIT ATTACHED TO STRUCTURE 2" DIA, GALVANIZED STEEL	FOOT	402.0			402.0
* 81400115	HANDHOLE TO BE ADJUSTED	EACH	1.0			1.0
* 81400100	HANDHOLE	EACH	4.0			4.0
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLR-TYPE USE) 1/C NO. 6	FOOT	1277.0			1277.0
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1176.0			1176.0
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	2.0			2.0
* 85000300	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	L SUM	1.0			1.0
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1134.0			1134.0
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1		
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	5	5		

△ Revised 2-24-09

SUMMARY OF QUANTITIES				TAZEWELL COUNTY		
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	5000-2A	7071-2A	7031-1F
				ROADWAY	CAMP ST. BRIDGE	TRAFFIC SIGNALS
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	587.0			587.0
* 87501100	TRAFFIC SIGNAL POST, 15 FT.	EACH	1.0			1.0
* 87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	2.0			2.0
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8.0			8.0
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	40.0			40.0
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4.0			4.0
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1.0			1.0
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2.0			2.0
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	1.0			1.0
* 88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	5.0			5.0
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	70.0	70.0		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	51.0	51.0		
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	212.0	212.0		
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	119.0	119.0		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	63.0	63.0		
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	172.0	172.0		
550A0420	STORM SEWERS, CLASS A, TYPE 2 27"	FOOT	166.0	166.0		
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	65.0	65.0		
* X0322765	RELOCATE VIDEO VEHICLE DETECTION SYSTEM	EACH	1.0			1.0
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	41.0		41.0	
X6060015	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24 (VWGF)	FOOT	21.0	21.0		
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	21.0	21.0		
X6064201	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	22.0	22.0		
* X8900030	REMOVE EXISTING TEMPORARY TRAFFIC SIGNAL EQUIPMENT	EACH	1.0			1.0
XX000321	INLET-MANHOLE, TYPE G-1, 5'-DIAMETER, SPECIAL	EACH	2.0	2.0		
* XX002182	STREET NAME SIGN MAST ARM MOUNT	EACH	3.0			3.0
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.0	1.0		
Z0030250	IMPACT ATTENUATOR, TEMPORARY, (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0	2.0		
Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0	2.0		
△ Z0078600	TRAINEES	HOURL	500.0	500.0		

* SPECIALTY ITEMS
△ Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
CAMP STREET CONNECTOR
SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE 12/22/2008

DRAWN BY JLT
CHECKED BY CSA