

SELECT FILL -SOIL MASS SOIL REINFORCEMENT (TYP.) STRUCTURE EXCAVATION (TYP.) -0.70 X "H" MIN.
SEE SUPPLIER SHOP DRAWINGS FOR LENGTH \*LIMITS OF TEMPORARY MSE WALL

- SACRIFICIAL FACE

TEMPORARY MSE WALL DETAIL SCALE: NOT TO SCALE

\* PER IDOT SPECIAL PROVISION "TEMPORARY MECHANICALLY STABILIZED EARTH WALL"

COUNTY TOTAL SHEET SHEETS NO.

6713 06-00139-00-GE TAZEWELL 13 8 TO STA....

PROJECT: HPP 079000130 ILLINOIS CITY OF EAST PEORIA

RTE. SECTION


STA.

-- PERMANENT EMBANKMENT

- LIMIT OF REINFORCED

--- EX. R.O.W.

-EXISTING GRADE



DATE -NAME -SCALE -NAME --

PLOT FILE PLOT USER

TYPICAL PIEZOMETER INSTALLATION DETAIL

SCALE: NOT TO SCALE

## SETTLEMENT PLATFORM NOTES:

SEE PLAN SHEET FOR PIEZOMETER AND SETTLEMENT PLATFORM LOCATIONS

- THE HORIZONTAL AND VERTICAL LOCATION OF INSTALLED SETTLEMENT PLATFORM BASES SHALL BE RECORDED AND SUBMITTED BY THE ENGINEER, PRIOR TO PLACEMENT OF FILL.
- 2. SUGGESTED SETTLEMENT PLATFORM PROCEDURE SUBJECT TO APPROVAL BY THE ENGINEER: CARE SHALL BE TAKEN TO MAINTAIN PIPE VERTICALLY, AND A RECORD OF ADDED PIPE LENGTH SHALL BE MADE AS FILL IS PLACED. AT THE TIME OF BASE PLATE INSTALLATION, AN INITIAL REFERENCE MARK SHALL BE SCRIBED ON THE RISER PIPE AND ITS ELEVATION DETERMINED AND RECORDED. THE PIPE SHALL BE SCRIBED TO AN ACCURACY OF 3 mm (0.01 FT.)
  AT MAXIMUM INTERVALS OF 1.5 M (5 FT.) MEASURED FROM THE
  INITIAL MARK.

IMMEDIATELY AFTER THE PIPE IS SCRIBED, THE GRADUATIONS SHALL BE NUMBERED TO REFLECT THE DISTANCE FROM THE INITIAL SCRIBE. WHEN PIPE LENGTHS ARE ADDED, THE EXTENSIONS SHALL BE SCRIBED IN A SIMILIAR MANNER BY TAPE MEASUREMENT FROM SCRIBES ON THE NEXT LOWER PIPE. AN ADJUSTABLE HOSE CLAMP SHALL BE PLACED AROUND THE PIPE AT THE HIGHEST SCRIBE MARK TO PROVIDE A PLACE TO REST THE SURVEY ROD WHEN DETERMINING THE ELEVATION OF THE SCRIBE MARK. THE CLAMP SHALL BE LOOSENED AND MOVED UP AS FILL IS PLACED.

- THE CONTRACTOR SHALL USE MANUAL METHODS OR SMALL EQUIPMENT (e.g. WALK BEHIND COMPACTORS) TO COMPACT EMBANKMENT WITHIN 1 METER OF PLATFORM RISER.
- 5. TOTAL SETTLEMENT IS ESTIMATED TO BE 8". THIS INCLUDES 5" OF STILL SETTLEMENT IS ESTIMATED TO BE B". THIS INCLUDES 5" OF SETTLEMENT DURING CONSTRUCTION AND 3" OF SETTLEMENT ESTIMATED TO OCCUR DURING THE 3 MONTHS AFTER COMPLETION OF THE FILL.

