

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8894	05-00073-01-PV	MADISON	68	8
STA. N.A.		TO STA. N.A.		
FED. ROAD DIST. NO.		ILLINOIS FEDERAL AID PROJECT		

PCC SIDEWALK SCHEDULE		
LOCATION	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH (SQ FT)	DETECTABLE WARNING (SQ FT)
GERBER ROAD:		
STA. 78+06.00 RT. TO STA. 78+51.43 RT.	490.0	
STA. 78+30.00 RT. (EAST LAKE DRIVE INTERSECTION)		10.0
STA. 79+00.93 RT. TO STA. 81+92.00 RT.	927.1	
STA. 81+08.00 RT. TO STA. 81+69.48 RT.	290.6	
STA. 79+06.03 RT. (EAST LAKE DRIVE INTERSECTION)		10.0
STA. 81+90.76 RT. TO STA. 82+90.95 RT.	506.5	
STA. 81+80.00 LT. TO STA. 84+86.00 LT.	913.4	
STA. 82+83.31 RT. TO STA. 82+87.89 RT.	11.9	
STA. 83+20.03 RT. TO STA. 84+16.16 RT.	480.7	
STA. 84+12.46 RT. (WEST LAKE DRIVE INTERSECTION)		10.0
STA. 84+61.64 RT. TO STA. 86+42.22 RT.	884.9	
STA. 84+65.53 RT. (WEST LAKE DRIVE INTERSECTION)		10.0
STA. 86+59.28 RT. TO STA. 87+66.24 RT.	543.8	
STA. 87+78.24 RT. TO STA. 89+62.51 RT.	928.3	
STA. 89+86.51 RT. TO STA. 90+56.35 RT.	343.0	
STA. 90+69.35 RT. TO STA. 91+98.94 RT.	621.8	
STA. 92+15.06 RT. TO STA. 93+01.27 RT.	421.5	
STA. 93+13.16 RT. TO STA. 95+10.57 RT.	993.3	
STA. 95+25.84 RT. TO STA. 95+75.50 RT.	237.1	
STA. 95+91.50 RT. TO STA. 96+56.98 RT.	315.4	
STA. 96+68.28 RT. TO STA. 97+83.19 RT.	579.1	
STA. 97+95.19 RT. TO STA. 100+74.07 RT.	1401.3	
STA. 98+53.92 LT. TO STA. 98+57.93 LT.	10.3	
STA. 100+97.07 RT. TO STA. 101+54.02 RT.	278.5	
STA. 101+78.02 RT. TO STA. 103+11.32 RT.	647.9	
STA. 102+94.50 LT. TO STA. 103+03.24 LT.	98.3	
STA. 103+06.98 RT. (BRIAR LANE INTERSECTION)		10.0
STA. 102+99.03 LT. (BRIAR LANE INTERSECTION)		10.0
TOTAL	11925	60

TEMPORARY EROSION CONTROL SCHEDULE				
LOCATION	PERIMETER EROSION BARRIER (FOOT)	INLET AND PIPE PROTECTION (EACH)	TEMPORARY EROSION CONTROL SEEDINGS (POUND)	MULCH METHOD 2 (ACRE)
GERBER ROAD:				
STA. 78+30.00 LT. TO STA. 85+63.39 LT.			39	0.39
STA. 78+06.00 RT. TO STA. 78+54.43 RT.			3	0.03
STA. 78+08.00 RT. TO STA. 78+54.00 RT.	90.9			
STA. 78+30.00 LT. TO STA. 78+92.00 LT.	68.0			
STA. 78+89.00 RT. TO STA. 81+70.00 RT.	496.4	4		
STA. 79+03.00 RT. TO STA. 79+84.00 RT.	95.2			
STA. 79+12.00 LT. TO STA. 80+60.00 LT.	287.3	5		
STA. 80+74.00 LT. TO STA. 96+85.00 LT.		23		
STA. 81+89.00 LT. TO STA. 84+85.00 LT.	298.4			
STA. 81+96.00 RT. TO STA. 81+97.00 RT.	31.9			
STA. 82+00.00 RT. TO STA. 84+82.00 RT.		2		
STA. 82+00.00 RT. TO STA. 82+21.00 RT.	23.1			
STA. 82+05.00 RT. TO STA. 84+24.21 RT.			27	0.27
STA. 82+38.00 RT. TO STA. 82+88.00 RT.	76.7			
STA. 84+39.24 RT. TO STA. 103+79.86 RT.			33	0.33
STA. 85+44.00 RT. TO STA. 85+45.00 RT.	94.0			
STA. 85+80.94 LT. TO STA. 97+74.05 LT.			7	0.07
STA. 86+00.00 RT. TO STA. 86+42.00 RT.	43.8			
STA. 86+60.00 RT. TO STA. 87+65.00 RT.	107.8			
STA. 87+79.00 RT. TO STA. 89+59.00 RT.	181.8	1		
STA. 89+87.00 RT. TO STA. 90+50.00 RT.	63.6	1		
STA. 90+75.50 RT. TO STA. 91+99.00 RT.	132.1	2		
STA. 92+10.00 RT.		1		
STA. 92+15.00 RT. TO STA. 93+01.00 RT.	106.7			
STA. 93+13.00 RT. TO STA. 95+07.00 RT.	212.7			
STA. 95+23.00 RT. TO STA. 96+59.00 RT.	145.9			
STA. 96+71.00 RT. TO STA. 97+83.00 RT.	139.0	1		
STA. 97+95.00 RT. TO STA. 100+74.00 RT.	442.8	5		
STA. 98+00.03 LT. TO STA. 102+68.48 LT.			4	0.04
STA. 100+97.00 RT. TO STA. 101+54.00 RT.	67.5	1		
STA. 101+78.00 RT. TO STA. 103+12.00 RT.	129.7			
STA. 102+92.32 LT. TO STA. 103+79.86 LT.			1	0.01
TOTALS	3336	46	115	1.15

UTILITY SCHEDULE						
LOCATION	WATER MAIN 6" (FOOT)	WATER MAIN 8" (FOOT)	PVC FORCE MAIN PIPE, 8" (FOOT)	PVC SANITARY SEWER PIPE, 8" (FOOT)	DUCTILE IRON FITTINGS AND ACCESSORIES (POUND)	TRENCH BACKFILL (CU YD)
GERBER ROAD (WATER MAIN):						
STA 78+42.00 TO STA 85+00.00					490	
STA 78+42.00 RT TO STA 85+00.00 RT		666				174
STA 78+42.00 RT TO STA 85+00.00 RT	82					20
GERBER ROAD (SANITARY SEWER):						
STA 78+94.00 TO STA 85+00.00					555	
STA 78+94.00 LT TO STA 85+00.00 RT			647			237
STA 81+75.00 LT TO STA 84+70.00 RT				301		144
TOTALS	82	666	647	301	1045	575

SEEDING SCHEDULE						
LOCATION	SEEDING CLASS 2 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	AGRICULTURAL GROUND LIMESTONE (TON)	EROSION CONTROL BLANKET (SQ YD)
GERBER ROAD:						
STA. 78+30.00 LT. TO STA. 85+63.39 LT.	0.39	35	35	35	0.78	1885.4
STA. 78+06.00 RT. TO STA. 78+54.43 RT.	0.03	3	3	3	0.07	165.2
STA. 82+05.00 RT. TO STA. 84+24.21 RT.	0.27	25	25	25	0.55	1325.2
STA. 84+39.24 RT. TO STA. 103+79.86 RT.	0.33	30	30	30	0.66	1601.6
STA. 85+80.94 LT. TO STA. 97+74.05 LT.	0.07	6	6	6	0.13	321.2
STA. 98+00.03 LT. TO STA. 102+68.48 LT.	0.04	3	3	3	0.08	182.2
STA. 102+92.32 LT. TO STA. 103+79.86 LT.	0.01	1	1	1	0.02	39.9
TOTALS	1.15	103	103	103	2.3	5521

EARTHWORK SCHEDULE				
LOCATION	EARTH EXCAVATION (CU YD)	EMBANKMENT (CU YD)	* EXCAVATION TO BE USED AS EMBANKMENT (ADJUSTED FOR SHRINKAGE) 25% (CU YD)	** EARTHWORK BALANCE EXCESS (+) SHORTAGE (-) (CU YD)
GERBER ROAD:				
STA. 78+30.00 TO STA. 102+83.90	4378	4478	3284	-1195
TOTALS	4378	4478	3284	-1195

ASSUMED SHRINKAGE FACTOR OF 25%
 * EARTH EXCAVATION TO BE USED AS EMBANKMENT = EARTH EXCAVATION x 0.75
 ** EARTHWORK BALANCE = [EMBANKMENT - (EARTH EXCAVATION x 0.75)]

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 SCALE: VERT. NA
 HORIZ. NA
 DATE
 DRAWN BY AJK, RJM
 CHECKED BY JWB