CONTRACT 97364

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8894	05-00073-01-PV	MADISON	68	36
STA. N.A.		TO STA. N.A.		
FED. ROAD DIST. NO.	ILLINOIS	FEDERAL AID PROJECT		

R

PR PERM EASE

EX ROW

12" CONC

GERBER ROAD

8" PCC SW 4'

PR ROW

PR CONST LIMITS

PR CHAIN LINK FENCE, 4' SPECIAL
PR SEGMENTAL CONCRETE BLOCKWALL
(SEE DETAIL SHEET)

STA 79+98.00
50.00' RT

STA 79+54.32, 39.68' RT
1 EA PRECAST REINF CONC FLARED END SEC, 78"
INV EL = 509.38
1 EA CONC HDW REM PARTIAL
(SEE DETAIL NEXT SHEET)

10 0 10 20 30 40 50
SCALE IN FEET

STA 79+34.19, 39.76' RT
1 EA PRECAST REINF CONC FLARED END SEC, 78"
INV EL = 509.38
1 EA CONC HDW REM PARTIAL
(SEE DETAIL NEXT SHEET)

N

8.5 CU YD CHANNEL EXCAVATION

STA 79+98.00
90.00' RT

STA 80+46.00
60.00' LT

STA 80+32.00
65.00' LT

PR ℄ GERBER ROAD

STA 79+98.00
22.00' RT

80+00

PR CCC&G, TY B-6.24

STA 79+98.00
45.00' RT

STA 79+54.35, 51.37' LT
1 EA PRECAST REINF CONC FLARED END SEC, 78"
INV EL = 509.80
1 EA CONC HDW REM PARTIAL
(SEE DETAIL NEXT SHEET)

STA 80+32.00
25.00' LT

STA 80+16.00
25.00' LT

11' 11'

177.8 SQ YD STONE RIPRAP, CL A5

STA 79+60.00
50.00' LT

STA 79+34.17, 51.31' LT
1 EA PRECAST REINF CONC FLARED END SEC, 78"
INV EL = 509.80
1 EA CONC HDW REM PARTIAL
(SEE DETAIL NEXT SHEET)

STA 79+60.00
25.00' LT

40'

PR PERM EASE

27.8 CU YD
CHANNEL EXC

STA 79+35.00
116.00' LT

73 FT PIPE CULV, TY 2, RCCP, 78"

BOX CULV
8'W×5'H

HDW

73 FT PIPE CULV, TY 2, RCCP, 78"

108.9 CU YD
CHANNEL EXCAVATION

STA 79+50.00
90.00' RT

PR TEMP EASE

STA 79+50.00
160.00' RT

40'

PR CONST LIMITS

EX RIPRAP BETWEEN END SECTION
AND PR RIPRAP TO REMAIN

STA 79+15.16
107.94' LT

STA 79+38.77
57.00' LT

PE
Y +25.18

DENSE VEGETATION

STA 78+86.52
45.00' RT

STA 78+87.46
90.00' RT

STA 79+15.00
195.00' RT

STA 78+89.66
195.00' RT

78.0 CU YD
CHANNEL EXC

PR ROW

EX ROW

LIFT STA

STA 78+92.89
57.00' LT

STA 78+92.89
25.00' LT

90°00'00"

OIL & CHIP PVMT

PR ℄ EAST LAKE DRIVE

EAST LAKE DRIVE

12'

12'

STA 78+68.01

EX ROW LS

LIFT STA

LIFT STA

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

MISCELLANEOUS DETAILS

SCALE: VERT. N/A
HORIZ. 1"=10'
DATE 11/5/03

DRAWN BY AJK, RJM
CHECKED BY JWB

MISCELLANEOUS DETAILS: GERBER ROAD