

**SUMMARY OF QUANTITIES**


**INDEX TO SHEETS**

ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
<b>BASE BID</b>				
AR150510	ENGINEER'S FIELD OFFICE	LS	1	
AR150520	MOBILIZATION	LS	1	
AR152410	UNCLASSIFIED EXCAVATION	CY	4,600	
AR156520	INLET PROTECTION	EACH	3	
AR156531	EROSION CONTROL BLANKET	SY	1,090	
AR201610	BITUMINOUS BASE COURSE	TON	4,810	
AR201630	BITUMINOUS BASE TEST SECTION	EACH	1	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	LF	5,600	
AR208515	POROUS GRANULAR EMBANKMENT	CY	100	
AR209612	CRUSHED AGG. BASE COURSE - 12"	SY	5,630	
AR209614	CRUSHED AGG. BASE COURSE - 14"	SY	2,350	
AR401610	BITUMINOUS SURFACE COURSE	TON	2,620	
AR401630	BITUMINOUS SURFACE TEST SECTION	EACH	1	
AR401650	BITUMINOUS PAVEMENT MILLING	SY	11,700	
AR401655	BUTT JOINT CONSTRUCTION	SY	1,950	
AR401915	REM & REP BIT PAVEMENT - TYPE A	SY	50	
AR401916	REM & REP BIT PAVEMENT - TYPE B	SY	50	
AR510510	TIE DOWN	EACH	74	
AR510515	GROUND ROD	EACH	14	
AR510900	REMOVE TIE DOWN	EACH	98	
AR602510	BITUMINOUS PRIME COAT	GAL	2,520	
AR603510	BITUMINOUS TACK COAT	GAL	6,430	
AR620520	PAVEMENT MARKING - WATERBORNE	SF	4,400	
AR620900	PAVEMENT MARKING REMOVAL	SF	700	
AR625510	TAR EMULSION SEAL COAT	SY	5,800	
AR701512	12" RCP, CLASS IV	LF	250	
AR751416	TYPE 1 INLET	EACH	2	
AR751943	ADJUST MANHOLE	EACH	2	
AR752412	PRECAST REINFORCED CONC. FES 12"	EACH	1	
AR800055	BITUMINOUS MILLING PLACEMENT	CY	1,400	
AR800143	REMOVE BITUMINOUS PAVEMENT (3")	SY	1,510	
AR800144	REMOVE BITUMINOUS PAVEMENT (6"-8")	SY	6,500	
AR905530	TOPSOILING	SY	1,090	
<b>ADDITIVE ALTERNATE NO. 1</b>				
AS156531	EROSION CONTROL BLANKET	SY	230	
AS201610	BITUMINOUS BASE COURSE	TON	1,250	
AS201661	CLEAN & SEAL BITUMINOUS CRACKS	LF	2,600	
AS401610	BITUMINOUS SURFACE COURSE	TON	630	
AS401650	BITUMINOUS PAVEMENT MILLING	SY	4,080	
AS401655	BUTT JOINT CONSTRUCTION	SY	1,065	
AS510510	TIE DOWN	EACH	7	
AS510515	GROUND ROD	EACH	1	
AS510900	REMOVE TIE DOWN	EACH	15	
AS603510	BITUMINOUS TACK COAT	GAL	1,620	
AS905530	TOPSOILING	SY	230	

- 1 COVER SHEET
- 2 INDEX TO SHEETS/SUMMARY OF QUANTITIES
- 3 SITE PLAN / PROJECT CONTROL PLAN
- 4 SEQUENCE OF CONSTRUCTION - GENERAL NOTES AND DETAILS
- 5 SEQUENCE OF CONSTRUCTION PER AC 150/5370-2E (LATEST EDITION) - SHEET 1
- 6 SEQUENCE OF CONSTRUCTION PER AC 150/5370-2E (LATEST EDITION) - SHEET 2
- 7 TYPICAL SECTIONS
- 8 EXISTING CONDITIONS/PROPOSED REMOVALS - SHEET 1
- 9 EXISTING CONDITIONS/PROPOSED REMOVALS - SHEET 2
- 10 GRADING/LANDSCAPING PLAN - SHEET 1
- 11 GRADING/LANDSCAPING PLAN - SHEET 2
- 12 TIEDOWN/PAVEMENT MARKING PLAN - SHEET 1
- 13 TIEDOWN/PAVEMENT MARKING PLAN - SHEET 2
- 14 MISCELLANEOUS DETAILS - SHEET 1
- 15 MISCELLANEOUS DETAILS - SHEET 2
- 16 ENGINEERING INFORMATION - SHEET 1
- 17 ENGINEERING INFORMATION - SHEET 2

**REVISIONS**

NUMBER	BY	DATE



**GREATER KANKAKEE AIRPORT  
 KANKAKEE, ILLINOIS  
 REHABILITATE TERMINAL APRON AND TAXIWAY H - PHASE 1**

**INDEX TO SHEETS/SUMMARY OF QUANTITIES**

© Copyright: CMT, Inc.  
**CMT**  
 CRAWFORD, MURPHY & TILLY, INC.  
 CONSULTING ENGINEERS  
 License No. 841-000618

DESIGN BY: MND

DRAWN BY: JRO

CHECKED BY: MND

APPROVED BY:

DATE: 01/16/09

JOB No: 08075-05

IL PROJECT: IKK-3864  
 A.I.P. PROJECT: 3-17-0057-B16

**FINAL SUBMITTAL**

SHEET 2 OF 17 SHEETS