

K:\Danville\0504203 Taxiway Extension\Draw\Sheets
 FILE: 02_INDEXSUM.dwg
 LAYOUT: INDEXSUM
 UPDATE BY: dallan
 SURVEY BOOK #
 DATE: Mon 1/5/09 4:28pm
 XREF DWG: CIntinfo.dwg

REVISIONS


NUMBER	BY	DATE

0 1 2
 THIS BAR IS EQUAL TO 2'
 AT FULL SCALE (34x22).

INDEX TO SHEETS	
SHT NO.	TITLE
01	COVER SHEET
02	INDEX TO SHEETS & SUMMARY OF QUANTITIES
03	AIRPORT SITE PLAN
04	CONSTRUCTION ACTMITY PLAN
05	EXISTING CONDITIONS & REMOVALS
06	PROPOSED IMPROVEMENTS
07	TYPICAL SECTION
08	TAXIWAY A PLAN & PROFILE STA. 279+00 to STA. 287+00
09	DRAINAGE PLAN
10	DRAINAGE DETAILS 1
11	UNDERDRAIN DETAILS
12	MANHOLE & INLET DETAILS
13	ELECTRICAL & LIGHTING PLAN
14	SIGNAGE LAYOUT
15	ELECTRICAL DETAILS SHEET 1
16	ELECTRICAL DETAILS SHEET 2
17	ELECTRICAL DETAILS SHEET 3
18	ELECTRICAL DETAILS SHEET 4
19	MARKING PLAN
20	TURFING PLAN
21	EROSION CONTROL DETAILS
22	TAXIWAY A CROSS SECTIONS STA. 279+50 to STA. 281+00
23	TAXIWAY A CROSS SECTIONS STA. 281+50 to STA. 282+00
24	TAXIWAY A CROSS SECTIONS STA. 282+30 to STA. 283+00
25	TAXIWAY A CROSS SECTIONS STA. 283+50 to STA. 285+00
26	TAXIWAY A CROSS SECTIONS STA. 285+50 to STA. 287+00

SUMMARY OF QUANTITIES			
ITEM NO.	ITEM DESCRIPTION	UNIT	QUAN.
AR108158	1/C #8 5 KV UG CABLE IN UD	LF	3,500
AR110504	4-WAY CONCRETE ENCASED DUCT	LF	135
AR110900	REMOVE DUCT	LF	60
AR125410	MIL-STAKE MOUNTED	EA	30
AR125415	MIL-BASE MOUNTED	EA	10
AR125901	REMOVE STAKE MOUNTED LIGHT	EA	22
AR125902	REMOVE BASE MOUNTED LIGHT	EA	1
AR125904	REMOVE TAXIWAY GUIDANCE SIGN	EA	1
AR125906	REMOVE SPLICE CAN	EA	1
AR125964	RELOCATE TAXI GUIDANCE SIGN	EA	1
AR150510	ENGINEER'S FIELD OFFICE	LS	1
AR152455	EMBANKMENT IN PLACE	CY	22,800
AR155540	BY-PRODUCT LIME	TON	155
AR155612	SOIL PROCESSING - 12"	SY	6,360
AR156510	SILT FENCE	LF	1,500
AR156520	INLET PROTECTION	EA	4
AR156544	RIPRAP-GRADATION NO 4	SY	70
AR201506	BITUMINOUS BASE COURSE - 6"	SY	5,890
AR209611	CRUSHED AGG. BASE COURSE - 11"	SY	6,360
AR401504	BITUMINOUS SURFACE COURSE - 4"	SY	5,890
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	1,792
AR602510	BITUMINOUS PRIME COAT	GAL	3,180
AR603510	BITUMINOUS TACK COAT	GAL	2,400
AR620520	PAVEMENT MARKING-WATERBORNE	SF	850
AR701560	60" RCP, CLASS IV	LF	100
AR701572	72" RCP, CLASS IV	LF	230
AR705524	4" PERFORATED UNDERDRAIN W/SOCK	LF	1,900
AR705635	UNDERDRAIN COLLECTION STRUCTURE	EA	4
AR705640	UNDERDRAIN CLEANOUT	EA	6
AR751410	INLET	EA	1
AR751530	MANHOLE	EA	1
AR752960	RELOCATE END SECTION	EA	1
AR800217	UNDERCUT BEDDING	CY	85
AR901510	SEEDING	AC	4
AR904510	SODDING	SY	875
AR908510	MULCHING	AC	4
AR908520	EXCELSIOR BLANKET	SY	5,000

**VERMILLION COUNTY AIRPORT
 DANVILLE, ILLINOIS**
EXTEND PARALLEL TAXIWAY 600 FEET
**INDEX TO SHEETS &
 SUMMARY OF QUANTITIES**



DESIGN BY: SMS
 DRAWN BY: DPA
 CHECKED BY: JEF
 APPROVED BY: JEF
 DATE: 01/09/2009
 JOB No: 05042-0300
 ILLINOIS PROJECT DNV-3537
 A.I.P. PROJECT 3-17-0032-B10
 SHEET 02 OF 26 SHEETS