

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	110-34HB-1	CHAMPAIGN	147	1
		ILL. PROJ. CONTRACT NO. 70B98		

168

FOR INDEX OF SHEETS, SEE SHEET NO. 2


FOR LIST OF HIGHWAY STANDARDS, SEE SHEET NO. 2

**PROPOSED  
HIGHWAY PLANS**

F.A.I. ROUTE 57 (I-57)  
SECTION (10-34HB)BR-1  
PROJECT NHPP-F9TY(264)  
BRIDGE REPLACEMENT  
CHAMPAIGN COUNTY

C-95-038-16  
U.S. 150 (NW OF CHAMPAIGN)  
R8E, 3°P.M.

D-95-038-16




LOCATION MAP  
1" = 2000'

**FUNCTIONAL CLASSIFICATION**  
SUBURBAN OTHER PRINCIPAL ARTERIAL  
U.S. 150 OVER I-57: 2017 ADT = 7,400  
P.V. = 87.2% S.U. 7.4% M.U. = 5.4%  
I-57 UNDER U.S. 150: 2017 ADT = 36,100  
P.V. = 71.1% S.U. 3.7% M.U. = 25.2%

**MIDWEST COURT  
IMPROVEMENT**


**BEGIN IMPROVEMENT  
STA. 151 + 25.00**

**BRIDGE REPLACEMENT**  
EXIST SN 010-0050  
PROP SN 010-1050  
STA. 157 + 29.99 (U.S.-150)  
STA. 582 + 52.38 (I-57)  
2 SPANS AT 333'-8" B-B ABUTS.  
49'-0" "O-D WIDTH" REINF. CONC. DECK  
NO SKEW



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.  
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS  
1-800-892-0123  
OR 811  
HENSLY & CHAMPAIGN TWPS



KEVIN REED CRIDER  
062-057383  
LICENSED PROFESSIONAL ENGINEER  
OF ILLINOIS  
5-1-19

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUBMITTED May 7 2019

*[Signature]*  
REGIONAL ENGINEER

*[Signature]*  
ENGINEER OF DESIGN AND ENVIRONMENT

*[Signature]*  
DIRECTOR OF HIGHWAYS PROJECT IMPLEMENTATION

PROJECT ENGINEER: JASON STULTS  
CONSULTANT LIAISON: RYAN CARROLL  
(217)466-4181



BACON | FARMER | WORKMAN  
ENGINEERING & TESTING, INC.

1218 OLDSBURG DRIVE  
MURRAY, KENTUCKY 40361  
PHONE: 502-732-0287

800 SOUTH 117th STREET  
PACIFIC, WISCONSIN 53023  
PHONE: 278-44-1895

458 NORTH H. COURSEY STREET  
MADISON, WISCONSIN 53706  
PHONE: 608-837-8150

WWW.BFWENGINEERS.COM

U.S. 150  
GROSS LENGTH = 1075.00 FT. = 0.204 MILE  
NET LENGTH = 1075.00 FT. = 0.204 MILE

MIDWEST COURT  
GROSS LENGTH = 269.50 FT. = 0.051 MILE  
NET LENGTH = 269.50 FT. = 0.051 MILE

CONTRACT NO. 70B98

PRINTED BY THE AUTHORITY  
OF THE STATE OF ILLINOIS

**INDEX OF SHEETS**

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS & HIGHWAY STANDARDS
3	GENERAL NOTES & COMMITMENTS
4 - 14	SUMMARY OF QUANTITIES
15 - 22	TYPICAL SECTIONS
23 - 32	SCHEDULES OF QUANTITIES
33 - 35	ALIGNMENT, TIES AND BENCHMARKS
36	REMOVAL PLAN - U.S. 150
37	REMOVAL PLAN - MIDWEST COURT
38	PLAN & PROFILE - U.S. 150
39	PLAN & PROFILE - MIDWEST COURT
40	JOINTING PLAN - MIDWEST COURT
41	GRADING PLAN - U.S. 150
42	GRADING PLAN - MIDWEST COURT
43 - 62	MAINTENANCE OF TRAFFIC PLANS
63	DRAINAGE PLAN & PROFILE - U.S. 150
64	DRAINAGE PLAN & PROFILE - MIDWEST COURT
65	DRAINAGE PLAN & PROFILE - I-57 (FOR INFORMATION ONLY)
66	DRAINAGE PLAN & PROFILE - RAMP A (FOR INFORMATION ONLY)
67	DRAINAGE PLAN & PROFILE - RAMP B (FOR INFORMATION ONLY)
68	EROSION CONTROL PLAN - U.S. 150
69	EROSION CONTROL PLAN - MIDWEST COURT
70	LIGHTING PLAN
71 - 108	STRUCTURE PLANS - S.N. 010-1050 U.S. 150 OVER I-57
107 - 108	RIGHT-OF-WAY PLAN - U.S. 150 & MIDWEST COURT
109	PAVEMENT MARKING & SIGN PLAN
110 - 120	DETAILS
121 - 122	DETAILS - SIGN POSTS
123 - 124	DETAILS - GEOTEXTILE RETAINING WALL
125 - 126	DETAILS - BRIDGE APPROACH PAVEMENT CONNECTOR (SPECIAL)
127 - 143	CROSS SECTIONS - U.S. 150
144 - 147	CROSS SECTIONS - MIDWEST COURT

**LIST OF STANDARDS**

000001-07	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-07	TEMPORARY EROSION CONTROL SYSTEMS
420401-13	PAVEMENT CONNECTOR (PCC) FOR BRIDGE APPROACH SLAB
482001-02	HMA SHOULDER ADJACENT TO FLEXIBLE PAVEMENT
515001-04	NAME PLATE FOR BRIDGES
542301-03	PRECAST REINFORCED CONCRETE FLARED END SECTION
542311-07	TRAVERSABLE PIPE GRATE FOR CONCRETE END SECTION
542401-03	METAL FLARED END SECTION FOR PIPE CULVERTS
601101-02	CONCRETE HEADWALL FOR PIPE UNDERDRAINS
602301-04	INLET - TYPE A
602401-06	PRECAST MANHOLE TYPE A 4' (1.22 m) DIAMETER
602701-02	MANHOLE STEPS
604006-05	FRAME AND GRATE TYPE 3
606001-07	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
610001-08	SHOULDER INLET WITH CURB
630001-12	STEEL PLATE BEAM GUARDRAIL
630301-09	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631011-10	TRAFFIC BARRIER TERMINAL, TYPE 2
631031-16	TRAFFIC BARRIER TERMINAL, TYPE 6
635001-02	DELINEATORS
642006	SHOULDER RUMBLE STRIPS, 8 in.
666001-01	RIGHT OF WAY MARKERS
667101-02	PERMANENT SURVEY MARKERS
701001-02	OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5 m) AWAY
701006-05	OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
701011-04	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701311-03	LANE CLOSURE, 2L, 2W MOVING OPERATIONS- DAY ONLY
701321-18	LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER
701400-09	APPROACH TO LANE CLOSURE, FREEWAY / EXPRESSWAY
701401-12	LANE CLOSURE, FREEWAY / EXPRESSWAY
701411-09	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS ≥ 45 MPH
701428-01	TRAFFIC CONTROL SETUP AND REMOVAL FREEWAY / EXPRESSWAY
701451-05	RAMP CLOSURE FREEWAY / EXPRESSWAY
701501-06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701901-08	TRAFFIC CONTROL DEVICES
704001-08	TEMPORARY CONCRETE BARRIER
720001-01	SIGN PANEL MOUNTING DETAILS
720006-04	SIGN PANEL ERECTION DETAILS
720021-02	SIGN PANELS EXTRUDED ALUMINUM TYPE
725001-01	OBJECT AND TERMINAL MARKERS
780001-05	TYPICAL PAVEMENT MARKINGS
781001-04	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS
782006-01	GUARDRAIL AND BARRIER WALL REFLECTOR MOUNTING DETAILS
812001-01	RACEWAY EMBEDDED IN STRUCTURE
886006-01	TYPICAL LAYOUTS FOR DETECTION LOOPS

FILE NAME D570898.sht.germote.dgn	USER NAME binary	DESIGNED CWW	REVISED	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS &amp; HIGHWAY STANDARDS</b>	F.A.I. RTE. 57	SECTION 110-34(B)BR-1	COUNTY CHAMPAIGN	TOTAL SHEETS 147	SHEET NO. 2		
Default	PLOT SCALE 100.0000 / in.	CHECKED BJE	REVISED			SCALE: N.T.S.	SHEET OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 70B98		
	PLOT DATE 5/6/2019 2:44:38 PM	DATE 04/16/2019	REVISED									

**GENERAL NOTES**

- G.N.-100 ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.
- G.N.-100B MICROSTATION AND GEOPAK FILES OF THIS PROJECT WILL BE MADE AVAILABLE TO THE CONTRACTOR AFTER CONTRACT AWARD. IF THERE IS A CONFLICT BETWEEN THE ELECTRONIC FILES AND THE PRINTED CONTRACT PLANS AND DOCUMENTS, THE PRINTED CONTRACT PLANS AND DOCUMENTS SHALL TAKE PRECEDENCE OVER THE ELECTRONIC FILES. THE CONTRACTOR SHALL ACCEPT ALL RISK ASSOCIATED WITH USING THE ELECTRONIC FILES AND SHALL HOLD THE DEPARTMENT HARMLESS FOR ANY ERRORS OR OMISSIONS IN THE ELECTRONIC FILES AND THE DATA CONTAINED THEREIN. ERRORS OR DELAYS RESULTING FROM THE USE OF THE ELECTRONIC FILES BY THE CONTRACTOR SHALL NOT RESULT IN AN EXTENSION OF TIME FOR ANY INTERIM OR FINAL COMPLETION DATE OR SHALL NOT BE CONSIDERED CAUSE FOR ADDITIONAL COMPENSATION. THE CONTRACTOR SHALL NOT USE, SHARE, OR DISTRIBUTE THESE ELECTRONIC FILES EXCEPT FOR THE PURPOSE OF CONSTRUCTING THIS CONTRACT. ANY CLAIMS BY THIRD PARTIES DUE TO USE OR ERRORS SHALL INCLUDE THIS DISCLAIMER WITH THE TRANSFER OF THESE ELECTRONIC FILES TO ANY OTHER PARTIES AND SHALL INCLUDE APPROPRIATE LANGUAGE BINDING THEM TO SIMILAR RESPONSIBILITIES.
- G.N.-105.07C EXISTING STATE-OWNED AND MAINTAINED UNDERGROUND UTILITY FACILITIES EXIST WITHIN THE ROW. THE DEPARTMENT IS NOT A MEMBER OF JULIE AND DOES NOT LOCATE IT'S OWN FACILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE AT THEIR OWN EXPENSE FOR SECURING AN APPROVED LOCATING FIRM TO LOCATE ALL EXISTING IDOT UNDERGROUND FACILITIES PRIOR TO COMMENCING ANY EXCAVATION, PER THE REQUIREMENTS OF ARTICLE 803 OF THE STANDARD SPECIFICATIONS. UTILITY LOCATES MAY ALSO BE REQUIRED OUTSIDE THE PROJECT LIMITS, SUCH AS FOR TRAFFIC CONTROL SIGNING AND OTHER ITEMS. THE CONTRACTOR MAY OBTAIN, ON REQUEST, PLANS OF EXISTING ELECTRICAL FACILITIES FROM THE DEPARTMENT. FOR FURTHER INFORMATION, THE CONTRACTOR MAY CONTACT THE DISTRICT TRAFFIC OPERATIONS ENGINEER, GARY SIMS, AT 217-251-4859.  
  
THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR LOCATING AND PROVIDING PROTECTION FOR FACILITIES DURING ALL PHASES OF CONSTRUCTION. IF, AT ANY TIME, THE FACILITIES ARE DAMAGED, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT AND MAKE ALL NECESSARY ARRANGEMENTS FOR REPAIR TO THE SATISFACTION OF THE ENGINEER. THIS WORK SHALL BE INCLUDED IN THE CONTRACT BID PRICE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- G.N.-105.09A ALL ELEVATIONS SHOWN IN THE PLANS ARE BASED ON NORTH AMERICAN VERTICAL DATUM OF 1988. (NAVD 88)
- G.N.-107.37 UTILITY LINES WERE PLOTTED FROM INFORMATION FURNISHED BY THE VARIOUS UTILITY COMPANIES INVOLVED (QUALITY LEVEL C &/OR QUALITY LEVEL D) AND THE ACCURACY SHOULD BE CONSIDERED APPROXIMATE ONLY.  
  
UTILITY COMPANIES MAY BE ADJUSTING THEIR FACILITIES DURING CONSTRUCTION. THE CONTRACTOR SHALL COOPERATE WITH THESE ORGANIZATIONS WHILE THESE ADJUSTMENTS ARE BEING PERFORMED. J.U.L.I.E. - JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS SYSTEM (800) 892-0123 OR 811.
- G.N.-201 TREES THAT INTERFERE WITH THE CONSTRUCTION OPERATIONS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER. ANY TREE DUE TO ITS LOCATION AND DEEMED SUITABLE FOR SAVING BY THE ENGINEER SHALL BE PROTECTED DURING CLEARING AND SUBSEQUENT CONSTRUCTION OPERATIONS.
- G.N.-205 BENCHING PROCEDURES SHALL BE USED IN AREAS WHERE EXISTING EMBANKMENTS ARE WIDENED FOR THE PROPOSED PAVEMENT. STEPS SHALL BE CUT INTO THE THE EXISTING EMBANKMENT SLOPES AND SHALL HAVE THE FOLLOWING DIMENSIONS:  
HORIZONTAL: VARIES  
VERTICAL: 3'
- G.N.-280 TEMPORARY EROSION CONTROL SEEDING IS INCLUDED IN THIS CONTRACT TO SEED DISTURBED EARTH DURING TIME PERIODS WHEN PERMANENT SEEDING IS NOT ALLOWED. SOME OR ALL OF THE TEMPORARY EROSION CONTROL SEEDING WILL BE DELETED IF IT IS POSSIBLE TO PLACE PERMANENT SEEDING ON EARTH AT THE TIME OF THEIR COMPLETION.
- G.N.-280A THE VARIOUS MULCH PAY ITEMS IN THE PLANS INCLUDE QUANTITIES FOR TEMPORARY MULCH FOR EROSION CONTROL. THE TEMPORARY MULCH INCLUDES MAINTENANCE AND REMOVAL IF NECESSARY, PER THE REQUIREMENTS OF ARTICLE 280 OF THE STANDARD SPECIFICATIONS, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED. SOME OR ALL OF THE MULCH USED AS TEMPORARY EROSION CONTROL WILL BE DELETED IF IT IS NOT NECESSARY DUE TO ESTABLISHMENT OF PERMANENT SEEDING.
- G.N.-406 THE QUANTITIES INCLUDED IN THE PLANS FOR HOT-MIX ASPHALT RESURFACING ARE INTENDED TO GIVE THE COVERAGE SHOWN ON THE TYPICAL CROSS SECTIONS. IT IS NOT INTENDED TO INCREASE THE THICKNESS OF THE HOT-MIX ASPHALT MIXTURE IN ORDER TO USE ALL OF THE QUANTITIES INCLUDED IN THE CONTRACT.

G.N.-406H MIXTURE REQUIREMENTS

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

LOCATION(S):	LANE PAVEMENT-SURFACE	LANE PAVEMENT-UPPER BINDER	LANE PAVEMENT-LOWER BINDER	SHOULDER PAVEMENT-SURFACE	SHOULDER PAVEMENT-BINDER
MIXTURE USE(S):	POLYMERIZED SURFACE COURSE	POLYMERIZED UPPER BINDER	LOWER BINDER	SURFACE COURSE	BINDER COURSE
AC/PG:	SBS PG 64-28	SBS PG 64-28	PG 64-22	PG 64-22	PG 64-22
DESIGN AIR VOIDS:	4.0%, N70	4.0%, N70	4.0%, N70	4.0%, N50	4.0%, N50
MIXTURE COMP (GRADATION)	IL-9.5	IL-19.0	IL-19.0	IL-9.5	IL-19.0
FRICTION AGGREGATE:	MIX "D"	N/A	N/A	MIX "C"	N/A
MIXTURE WEIGHT	112 LB/SY	112 LB/SY	112 LB/SY	112 LB/SY	112 LB/SY
QUALITY MANAGEMENT PROGRAM	QC/QA	QC/QA	QC/QA	QC/QA	QC/QA
SUBLOT SIZE	N/A	N/A	N/A	N/A	N/A

- G.N.-501 THE REMOVAL OF THE EXISTING APPROACH SLAB IS INCLUDED IN THE COST OF THE REMOVAL OF EXISTING STRUCTURES.
- G.N.-609 PRIOR TO ROUTING TRAFFIC ONTO THE SHOULDERS AS SHOWN IN THE STAGING PLANS, THE CONTRACTOR SHALL SECURE THE GRATINGS ON SHOULDER INLETS AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE PAID FOR ACCORDING TO ARTICLE 109.04.
- G.N.-667 THE RESIDENT ENGINEER SHALL CONTACT PROGRAM DEVELOPMENT CHIEF OF SURVEYS PRIOR TO THE PRE-CONSTRUCTION CONFERENCE FOR INSTRUCTION AS TO SETTING OF TEMPORARY OR PERMANENT TIES FOR CENTERLINE ALIGNMENT CONTROL SURVEY MARKERS (PC'S, PT'S, AND PI'S). PROJECT IMPLEMENTATION PERSONNEL WILL BE RESPONSIBLE FOR LAYOUT OF THESE MARKERS.
- G.N.-703A SHORT TERM PAVEMENT MARKING SHALL BE APPLIED TO THE PAVEMENT AFTER ANY OF THE FOLLOWING: COLD MILLING AND/OR PLACING BITUMINOUS MATERIALS (PRIME COAT), LEVELING BINDER (MACHING METHOD), BINDER AND SURFACE COURSES. SHORT TERM PAVEMENT MARKING PLACED ON THE SURFACE, SHALL COINCIDE WITH THE FINAL PAVEMENT STRIPING. SHORT TERM PAVEMENT MARKING PLACED PRIOR TO THE SURFACE SHALL COINCIDE WITH THE EXISTING PAVEMENT MARKINGS. USE 4 FEET PER 40 FEET (OR 10% PER STATION).
- G.N.-781 RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH STANDARD 781001, AND THE DETAILS SHOWN IN THE PLANS. IF THERE IS ANY DISCREPANCY BETWEEN THE STANDARD AND THE DETAILS IN THE PLANS, THE DETAILS IN THE PLANS SHALL GOVERN. THE FINAL PAVEMENT MARKINGS SHALL BE IN PLACE PRIOR TO PLACING THE RAISED REFLECTIVE PAVEMENT MARKERS AND THE RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED MIDWAY IN THE 30 FOOT (9M) SPACE BETWEEN THE DASHED CENTERLINE STRIPES (WHEN APPLICABLE).
- G.N.-Z0038 AN ALUMINUM TABLET OF THE TYPE SHOWN ON STANDARD 667101 SHALL BE PLACED ON THE PROPOSED STRUCTURE AS DIRECTED BY THE ENGINEER. THE BENCH MARK ELEVATION WILL BE ESTABLISHED AND MARKED BY THE DEPARTMENT. THIS WORK WILL BE PAID FOR THE CONTRACT UNIT PRICE EACH FOR PERMANENT BENCH MARKS.

OTHER GENERAL NOTES:

HOT-MIX ASPHALT SHOULDER CURB REMOVAL IS INCLUDED IN PAVED SHOULDER REMOVAL.

APPROACH SLAB REMOVAL SHALL BE INCLUDED IN THE COST OF REMOVAL OF EXISTING STRUCTURES.

**COMMITMENTS**

FILE NAME = D570B98-sht-gennote.dgn	USER NAME = bemory	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES &amp; COMMITMENTS</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - CWW	REVISED -						57	(10-34HB)BR-1	CHAMPAIGN	147	3
	PLOT DATE = 5/6/2019 - 2:44:35 PM	CHECKED - BJE	REVISED -		CONTRACT NO.70B98				ILLINOIS FED. AID PROJECT				
		DATE - 04/16/2019	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				MIDWEST COURT		BRIDGE REPLACEMENT	
				90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE & 5% LOCAL	100% LOCAL
				ROADWAY	BRIDGE	BRIDGE RAILING	SIDEWALK
				0004	0010	0010	0021
URBAN	S.N. 010-1050	URBAN	URBAN				
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	36	36			
20100500	TREE REMOVAL, ACRES	ACRE	4.00		4.00		
20200100	EARTH EXCAVATION	CU YD	7,850	3,455	4,240		155
20400800	FURNISHED EXCAVATION	CU YD	17,430		14,070		3,360
20600200	GRANULAR EMBANKMENT, SPECIAL	CU YD	2,207		2,207		
20800150	TRENCH BACKFILL	CU YD	466	466			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	20,392		20,392		
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	3,359	3,359			
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	792		792		
21400100	GRADING AND SHAPING DITCHES	FOOT	129		129		
25000210	SEEDING, CLASS 2A	ACRE	6.00	1.50	4.50		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	530	130	400		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	530	130	400		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	530	130	400		

\* SPECIALTY ITEM

FILE NAME = D570B98-sht-500.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - CWW	REVISED -						57	(10-34HB)BR-1	CHAMPAIGN	147	4
	PLOT DATE = 5/6/2019 - 2:45:13 PM	CHECKED - BJE	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 70B98	
		DATE - 04/16/2019	REVISED -		ILLINOIS FED. AID PROJECT								

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				MIDWEST COURT	BRIDGE REPLACEMENT		
				90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE & 5% LOCAL	100% LOCAL
				ROADWAY	BRIDGE	BRIDGE RAILING	SIDEWALK
				0004 URBAN	0010 S.N. 010-1050	0010 URBAN	0021 URBAN
25100115	MULCH, METHOD 2	ACRE	2.00	1.00	1.00		
25100630	EROSION CONTROL BLANKET	SQ YD	16,699		16,699		
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1,975		1,975		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	580	150	430		
28000305	TEMPORARY DITCH CHECKS	FOOT	60		60		
28000400	PERIMETER EROSION BARRIER	FOOT	716	402	314		
28000500	INLET AND PIPE PROTECTION	EACH	23	8	15		
28100107	STONE RIPRAP, CLASS A4	SQ YD	127		127		
28200200	FILTER FABRIC	SQ YD	127		127		
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1,979	1,979			
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	3,110		3,110		
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	2,166		2,166		
40600990	TEMPORARY RAMP	SQ YD	433	433			
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	386		386		

\* SPECIALTY ITEM

FILE NAME = D570B98-sht-500.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - CWW	REVISED -						57	(10-34HB)BR-1	CHAMPAIGN	147	5
	PLOT DATE = 5/6/2019 - 2:45:19 PM	CHECKED - BJE	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 70B98	
		DATE - 04/16/2019	REVISED -		ILLINOIS FED. AID PROJECT								

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				MIDWEST COURT		BRIDGE REPLACEMENT	
				90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE & 5% LOCAL	100% LOCAL
				ROADWAY	BRIDGE	BRIDGE RAILING	SIDEWALK
				0004 URBAN	0010 S.N. 010-1050	0010 URBAN	0021 URBAN
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	314		314		
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	218		218		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	167		167		
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	199		199		
42000211	PORTLAND CEMENT CONCRETE PAVEMENT 7 1/2" (JOINTED)	SQ YD	1,793	1,793			
42001300	PROTECTIVE COAT	SQ YD	1,943	1,943			
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	4,584.0	1,803.5			2780.5
44000100	PAVEMENT REMOVAL	SQ YD	3,845	2,654	1,191		
44000300	CURB REMOVAL	FOOT	365	365			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	805	805			
44000600	SIDEWALK REMOVAL	SQ FT	2,215	2,215			
44004250	PAVED SHOULDER REMOVAL	SQ YD	868		868		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	12		12		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		

\* SPECIALTY ITEM

FILE NAME = D570898-sht-500.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - CWW	REVISED -						57	(10-34HB)BR-1	CHAMPAIGN	147	6
	PLOT DATE = 5/6/2019 - 2:45:25 PM	CHECKED - BJE	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 70B98	
		DATE - 04/16/2019	REVISED -		ILLINOIS FED. AID PROJECT								

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				MIDWEST COURT		BRIDGE REPLACEMENT	
				90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE & 5% LOCAL	100% LOCAL
				ROADWAY	BRIDGE	BRIDGE RAILING	SIDEWALK
				0004 URBAN	0010 S.N. 010-1050	0010 URBAN	0021 URBAN
50104400	CONCRETE HEADWALL REMOVAL	EACH	6		6		
50105220	PIPE CULVERT REMOVAL	FOOT	324		324		
50157300	PROTECTIVE SHIELD	SQ YD	783		783		
50200100	STRUCTURE EXCAVATION	CU YD	419		371		48
50300225	CONCRETE STRUCTURES	CU YD	222.6		198.4		24.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	623.9		566.7		57.2
50300300	PROTECTIVE COAT	SQ YD	2,552		2,328		224
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	LSUM	1		0.86		0.14
50500505	STUD SHEAR CONNECTORS	EACH	5,418		4,644		774
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	191,250		172,800		18,450
50800515	BAR SPLICERS	EACH	1,426		1,426		
50800530	MECHANICAL SPLICERS	EACH	128		128		
50901730	BRIDGE FENCE RAILING	FOOT	390			390	
50901750	PARAPET RAILING	FOOT	420			420	

\* SPECIALTY ITEM

FILE NAME = D570B98-sht-500.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - CWW	REVISED -						57	(10-34HB)BR-1	CHAMPAIGN	147	7
	PLOT DATE = 5/6/2019 - 2:45:31 PM	CHECKED - BJE	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 70B98	
		DATE - 04/16/2019	REVISED -		ILLINOIS FED. AID PROJECT								

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				MIDWEST COURT		BRIDGE REPLACEMENT	
				90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE & 5% LOCAL	100% LOCAL
				ROADWAY	BRIDGE	BRIDGE RAILING	SIDEWALK
				0004	0010	0010	0021
URBAN	S.N. 010-1050	URBAN	URBAN				
51100100	SLOPE WALL 4 INCH	SQ YD	437		385		52
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	1,742		1,541		201
51202000	FURNISHING STEEL PILES HP14X102	FOOT	1,648		1,458		190
51202305	DRIVING PILES	FOOT	3,390		2,983		407
51203200	TEST PILE METAL SHELLS	EACH	1		1		
51204000	TEST PILE STEEL HP14X102	EACH	2		2		
51500100	NAME PLATES	EACH	1		1		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	102		86		16
52100520	ANCHOR BOLTS, 1"	EACH	28		24		4
52100540	ANCHOR BOLTS, 1 1/2"	EACH	14		12		2
52200010	TEMPORARY SHEET PILING	SQ FT	3,411		3,411		
52200600	GEOTEXTILE RETAINING WALL	SQ FT	1,056		1,056		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1			
54262712	METAL FLARED END SECTION 12"	EACH	9		9		

\* SPECIALTY ITEM

FILE NAME = D570B98-sht-S00.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / in.	DRAWN - CWW	REVISED -						57	(10-34HB)BR-1	CHAMPAIGN	147	8
	PLOT DATE = 5/6/2019 - 2:45:37 PM	CHECKED - BJE	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 70B98	
		DATE - 04/16/2019	REVISED -		ILLINOIS FED. AID PROJECT								



CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				MIDWEST COURT		BRIDGE REPLACEMENT	
				90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE & 5% LOCAL	100% LOCAL
				ROADWAY	BRIDGE	BRIDGE RAILING	SIDEWALK
				0004 URBAN	0010 S.N. 010-1050	0010 URBAN	0021 URBAN
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	216	216			
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	155	155			
55100900	STORM SEWER REMOVAL 18"	FOOT	635	635			
58600101	GRANULAR BACKFILL FOR STRUCTURES	CU YD	290		255		35
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	134		118		16
60100945	PIPE DRAINS 12"	FOOT	711		686		25
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	4	4			
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	650.5	650.5			
61000050	CONCRETE THRUST BLOCKS	EACH	9		9		
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	9		9		
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1,237.5		1,237.5		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2		2		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4		4		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2		2		

\* SPECIALTY ITEM

FILE NAME = D570B98-sht-500.dgn	USER NAME = bemory	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - CWW	REVISED -						57	(10-34HB)BR-1	CHAMPAIGN	147	9
	PLOT DATE = 5/6/2019 - 2:45:43 PM	CHECKED - BJE	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 70B98	
		DATE - 04/16/2019	REVISED -		ILLINOIS FED. AID PROJECT								

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				MIDWEST COURT		BRIDGE REPLACEMENT	
				90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE & 5% LOCAL	100% LOCAL
				ROADWAY	BRIDGE	BRIDGE RAILING	SIDEWALK
				0004 URBAN	0010 S.N. 010-1050	0010 URBAN	0021 URBAN
63200310	GUARDRAIL REMOVAL	FOOT	1,665		1,665		
63400105	GUARD POSTS	EACH	8		8		
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	1,851		1,851		
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2		
64301090	ATTENUATOR BASE	SQ YD	102		102		
66101150	HOT-MIX ASPHALT SHOULDER CURB	FOOT	1,367		1,367		
66500105	WOVEN WIRE FENCE, 4'	FOOT	1,010		1,010		
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	15		15		
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	161		161		
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1		1		
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	LSUM	1		1		
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	12		12		
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION PLANS	LSUM	1		1		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	15		15		

\* SPECIALTY ITEM

FILE NAME =  
D570B98-sh1-500.dgn  
Default

USER NAME = bemy  
PLOT SCALE = 100.0000' / 1in.  
PLOT DATE = 5/6/2019 - 2:45:48 PM

DESIGNED - CWW  
DRAWN - CWW  
CHECKED - BJE  
DATE - 04/16/2019

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	10
ILLINOIS FED. AID PROJECT			CONTRACT NO. 70B98	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				MIDWEST COURT		BRIDGE REPLACEMENT	
				90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE & 5% LOCAL	100% LOCAL
				ROADWAY	BRIDGE	BRIDGE RAILING	SIDEWALK
				0004 URBAN	0010 S.N. 010-1050	0010 URBAN	0021 URBAN
67100100	MOBILIZATION	LSUM	1		0.9		0.1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5		5		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1		
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	704		704		
70200100	NIGHTTIME WORK ZONE LIGHTING	LSUM	1		1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	167		167		
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	56		56		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5,601		5,601		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3,112.5		3,112.5		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,300.0		1,300.0		
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	3		3		
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	3		3		
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2		
* 72000300	SIGN PANEL - TYPE 3	SQ FT	384		384		

\* SPECIALTY ITEM

FILE NAME = D570898-sht-500.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - CWW	REVISED -						57	(10-34HB)BR-1	CHAMPAIGN	147	11
	PLOT DATE = 5/6/2019 - 2:45:54 PM	CHECKED - BJE	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 70B98	
		DATE - 04/16/2019	REVISED -		ILLINOIS FED. AID PROJECT								

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				MIDWEST COURT		BRIDGE REPLACEMENT	
				90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE & 5% LOCAL	100% LOCAL
				ROADWAY	BRIDGE	BRIDGE RAILING	SIDEWALK
				0004 URBAN	0010 S.N. 010-1050	0010 URBAN	0021 URBAN
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1		1		
* 72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	2		2		
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	3,460		3,460		
73400100	CONCRETE FOUNDATIONS	CU YD	9.0		9.0		
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	1		1		
* 78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	5,601		5,601		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	17		17		
* 78200005	GUARDRAIL REFLECTORS, TYPE A	EACH	20		20		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	21		21		
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	1,600		1,600		
* 81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	4		4		
X0325201	SHOULDER RUMBLE STRIP REMOVAL	SQ YD	25		25		
X0327979	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	4,318		4,318		
X2500002	POWDER COATING OF PARAPET RAILING AND BRIDGE FENCE RAILING	LSUM	1				1

\* SPECIALTY ITEM

FILE NAME = D570898-sht-500.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - CWW	REVISED -						57	(10-34HB)BR-1	CHAMPAIGN	147	12
	PLOT DATE = 5/6/2019 - 2:46:00 PM	CHECKED - BJE	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 70B98	
		DATE - 04/16/2019	REVISED -		ILLINOIS FED. AID PROJECT								

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				MIDWEST COURT		BRIDGE REPLACEMENT	
				90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE & 5% LOCAL	100% LOCAL
				ROADWAY	BRIDGE	BRIDGE RAILING	SIDEWALK
				0004 URBAN	0010 S.N. 010-1050	0010 URBAN	0021 URBAN
*X2600012	REMOVE AND RELOCATE SIGN PANEL AND POLE ASSEMBLY	EACH	1		1		
X4201410	BRIDGE APPROACH PAVEMENT CONNECTOR (SPECIAL)	SQ YD	172		172		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	647		647		
X5030250	BRIDGE DECK GROOVING (LONGITUDINAL)	SQ YD	1,044		1,044		
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	332		287		45
X5040100	PRECAST BRIDGE APPROACH SLAB	SQ FT	2,830		2,470		360
X6340205	GUARD POSTS REMOVAL	EACH	8		8		
X6430120	REMOVE IMPACT ATTENUATORS, NO SALVAGE	EACH	2		2		
X6431110	REMOVE ATTENUATOR BASE	EACH	2		2		
X6640304	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	225		225		
X6650202	WOVEN WIRE FENCE REMOVAL	FOOT	961		961		
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LSUM	1		1		
X7010218	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	EACH	8		8		
X7040125	PINNING TEMPORARY CONCRETE BARRIER	EACH	129		129		

\* SPECIALTY ITEM

FILE NAME = D570B98-sht-S00.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / in.	DRAWN - CWW	REVISED -						57	(10-34HB)BR-1	CHAMPAIGN	147	13
	PLOT DATE = 5/6/2019 - 2:46:06 PM	CHECKED - BJE	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 70B98	
		DATE - 04/16/2019	REVISED -		ILLINOIS FED. AID PROJECT								

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				MIDWEST COURT		BRIDGE REPLACEMENT	
				90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE & 5% LOCAL	100% LOCAL
				ROADWAY	BRIDGE	BRIDGE RAILING	SIDEWALK
				0004 URBAN	0010 S.N. 010-1050	0010 URBAN	0021 URBAN
X7200201	WIDTH RESTRICTION SIGNING	LSUM	1		1		
*X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	5,140		5,140		
Z0013798	CONSTRUCTION LAYOUT	LSUM	1		1		
Z0016702	DETOUR SIGNING	LSUM	1		1		
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	12		12		
Z0029090	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	1,687		1,687		
Z0038700	PERMANENT BENCH MARKS	EACH	1		1		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	184		162		22
Ø	Z0076600	TRAINEES	HOUR	2500	2500		
Ø	Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOUR	2500	2500		


\* SPECIALTY ITEM Ø 0042

FILE NAME = D570B98-sht-500.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -
		DRAWN - CWW	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED - BJE	REVISED -
	PLOT DATE = 5/6/2019 - 2:46:12 PM	DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: N.T.S.	SHEET	OF	SHEETS


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	14
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	



**EXISTING TYPICAL SECTION**  
**U.S. 150 (BLOOMINGTON RD.) OVER I-57** (A)

STA. 149+43.00 TO STA. 155+50.00 (B)

- EXISTING PAVEMENT WIDTH VARIES FROM:  
 11' AT STA. 150+96.92 TO  
 12' AT STA. 151+48.39



**EXISTING TYPICAL SECTION**  
**U.S. 150 (BLOOMINGTON RD.) OVER I-57** (B)

(A) STA. 155+50.00 TO STA. 155+73.19  
 STA. 158+89.19 TO STA. 162+00.00


FILE NAME = D570898-sht-Typicals_Existing.dgn	USER NAME = bemory	DESIGNED - CWW	REVISED -
		DRAWN - CWW	REVISED -
		CHECKED - BJE	REVISED -
		DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**EXISTING TYPICAL SECTIONS**  
**U.S. 150 OVER I-57**


SCALE: N.T.S. SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	15
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	



**EXISTING TYPICAL SECTION  
MIDWEST COURT (C)**

STA. 19+82.96 TO STA. 23+66.28  
EXISTING CUL-DE-SAC FROM  
STA. 23+66.28 TO STA. 25+09.00



**EXISTING TYPICAL SECTION  
F.A.I. 57 (I-57) (D)**

STA. 545+00.00 TO STA. 623+36.00

NOTE 1: HMA SHOULDER DEPTHS  
STA. 575+00.00 TO STA. 623+36.00 = OUTSIDE 16 1/2" TO 13 1/4"  
INSIDE 16 1/2" TO 14 3/4"

PRIOR OMISSION FROM RESURFACING  
STA. 580+60.00 TO STA. 583+40.00 - S.N. 010-0050  
HMA PAVEMENT DEPTH = 4 3/4"  
HMA SHOULDER DEPTH = OUTSIDE 14 3/4" TO 12 3/4"  
INSIDE 14 3/4" TO 13 3/4"

FILE NAME = D570B98-sht-Typicals_Existing.dgn	USER NAME = bemory	DESIGNED - CWW	REVISED -
		DRAWN - CWW	REVISED -
		CHECKED - BJE	REVISED -
		DATE - 04/16/2019	REVISED -


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

EXISTING TYPICAL SECTIONS  
MIDWEST COURT & I-57

SCALE: N.T.S. SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	16
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	






**EXISTING TYPICAL SECTION  
RAMP A**

**(E)**

FOR INFORMATION ONLY

**NOTE:**  
PORTIONS OF THE EXISTING 16' WIDE RAMP PAVEMENTS WERE PATCHED WITH CONTINUOUSLY REINFORCED PCC PAVEMENT (DEPTH = 13") PRIOR TO PLACEMENT OF THE HIGH FRICTION SURFACE TREATMENT (DEPTH = 3/4" +/-). THE APPROXIMATE AMOUNTS OF EXISTING RAMP PAVEMENTS THAT HAVE BEEN PREVIOUSLY PATCHED ARE:

- RAMP A - 18%
- RAMP B - 60%




**EXISTING TYPICAL SECTION RAMP B**

**(F)**

FOR INFORMATION ONLY

FILE NAME = D570B98-sht-Typicals_Existing.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>EXISTING TYPICAL SECTIONS RAMPS A &amp; B</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / in.	DRAWN - CWW	REVISED -		57	(10-34HB)BR-1	CHAMPAIGN	147	17				
	PLOT DATE = 5/6/2019 - 2:46:39 PM	CHECKED - BJE	REVISED -		CONTRACT NO. 70B98								
		DATE - 04/16/2019	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	ILLINOIS FED. AID PROJECT	



**PROPOSED TYPICAL SECTION ①**  
**U.S. 150 (BLOOMINGTON RD.) OVER I-57**


STA. 149+43.00 TO STA. 151+25.00 ②

- EXISTING PAVEMENT WIDTH VARIES FROM:  
 11' AT STA. 150+96.92 TO  
 12' AT STA. 151+48.39


- HOT-MIX ASPHALT BINDER COURSE, IL-19, N50, (952 LB/SY)
- HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50, (224 LB/SY)
- AGGREGATE WEDGE SHOULDERS, TYPE B

**PAVEMENT STRUCTURE DESIGN**


STRUCTURAL DESIGN TRAFFIC: 10,700	YEAR 2030
PV = 9,801	SU = 567 MU = 332
ROAD/STREET CLASSIFICATION:	CLASS II
PERCENT OF STRUCTURAL DESIGN TRAFFIC IN DESIGN LANE:	
P = 50%	S = 50% M = 50%
TRAFFIC FACTOR: ACTUAL TF = 1.93	MINIMUM TF = 3.17
PG GRADE: TOP BINDER = SBS 64-28	LOWER BINDER = PG 64-22
	SURFACE = SBS 64-28
SUBGRADE SUPPORT RATING:	SSR = POOR



**DETAIL "A"**  
 STA. 150+24.00 TO STA. 150+97.00



**DETAIL "B"**  
 STA. 150+97.00 TO STA. 151+25.00




**PROPOSED TYPICAL SECTION ②**  
**U.S. 150 (BLOOMINGTON RD.) OVER I-57**

① STA. 151+25.00 TO STA. 152+87.56 ③  
 ④ STA. 160+45.83 TO STA. 162+00.00

- SEE DETAIL - PAVEMENT PROFILE TRANSITIONS
- SEE SUPERELEVATION DETAIL
- SIDEWALK BEGINS STA. 151+64.50  
 SIDEWALK ENDS STA. 161+50.00
- CORING IS NOT NECESSARY FOR HMA THICKNESS LESS THAN 3"

- HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50, 224 LB/SY & VAR. (PG 64-22) (TYP.)
- HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50, 952 LB/SY & VAR. (PG 64-22) (TYP.)
- POLYMERIZED HMA SURFACE COURSE, MIX "D", N70, 224 LB/SY & VAR. (IL-9.5, SBS PG 64-28)
- POLYMERIZED HMA BINDER COURSE, IL 19.0, N70, 252 LB/SY & VAR. (SBS PG 64-28)
- HMA BINDER COURSE, IL-19.0, N70, 700 LB/SY & VARIABLE (PG 64-22)




**PROPOSED TYPICAL SECTION ③**  
**U.S. 150 (BLOOMINGTON RD.) OVER I-57**  
 ② STA. 152+87.56 TO STA. 155+21.67 (APPROACH PAVEMENT) ④

- SEE PAVEMENT PROFILE TRANSITION DETAIL AND REMOVAL PLANS FOR PAVEMENT REMOVAL LIMITS
- SIDEWALK BUFFER AREA VARIES STA. 154+94.31 TO STA. 155+21.67
- SEE SUPERELEVATION DETAIL
- CORING IS NOT NECESSARY FOR HMA THICKNESS LESS THAN 3"

FILE NAME = D570898-sht-Typicals_Proposed.dgn	USER NAME = bemory	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PROPOSED TYPICAL SECTION U.S. 150 (BLOOMINGTON AVE.) OVER I-57</b>				F.A.I. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000' / in.	CHECKED - BJE	REVISED -						57	(10-34HB)BR-1	CHAMPAIGN	147	19
Default	PLOT DATE = 6/4/2019 - 9:44:36 AM	DATE - 04/16/2019	REVISED -	SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 70B98		







**PROPOSED TYPICAL SECTION MIDWEST COURT**

STA. 19+82.96 TO STA. 21+02.44  
 SEE CUL-DE-SAC DETAIL FOR  
 STA. 21+02.44 TO STA. 22+46.90

FILE NAME = D570B98-sht-Typicals_Proposed.dgn	USER NAME = bemory	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PROPOSED TYPICAL SECTION MIDWEST COURT</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000' / 1" =	CHECKED - BJE	REVISED -					57	(10-34HB)BR-1	CHAMPAIGN	147	22
Default	PLOT DATE = 5/6/2019 - 2:47:02 PM	DATE - 04/16/2019	REVISED -	SCALE: N.T.S. SHEET OF SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT <b>CONTRACT NO. 70B98</b>					

## EROSION CONTROL

LOCATION STATION TO STATION	SIDE	EROSION CONTROL BLANKET	HEAVY DUTY EROSION CONTROL BLANKET	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET & PIPE PROTECTION
		25100630 SQ YD	25100635 SQ YD	28000305 FOOT	28000400 FOOT	28000500 EACH
<b>CHAMPAIGN COUNTY</b>						
<b>PRE-STAGE A</b>						
<b>U.S. 150</b>						
150+24.18 TO 151+25.00	RT	359.4				
<b>STAGE 1</b>						
<b>U.S. 150</b>						
150+60.51 TO 151+25.00	RT	441.6				
151+25.00 TO 152+32.04	RT	886.6				
152+32.04 TO 152+87.56	RT	582.8				
152+58.53	RT					1
152+57.90	RT					1
152+87.56 TO 155+11.67	RT	2,800.0				
153+50.00	RT			10		
153+69.90	RT					1
155+06.51	RT					1
155+11.67 TO 156+24.19	RT	1,350.5				
155+50.00	RT			10		
158+33.95 TO 159+23.35	RT	654.6				
159+00.00 TO 159+23.35	RT		151.6			
159+23.35 TO 160+45.83	RT	1,295.9	169.8			
159+29.00	RT					1
160+23.98	RT					1
160+42.00	RT			10		
160+45.83 TO 161+00.00	RT	624.0	352.5			
160+45.83 TO 161+33.15	RT					
161+01.84	RT					1
161+33.15 TO 162+00.00	RT		584.9			
<b>MIDWEST COURT</b>						
19+82.99 TO 22+49.19	LT					
19+82.99 TO 22+49.19	RT					
20+21.13	LT					1
20+21.13	RT					1
22+07.73	RT					1
22+38.47	LT					1
21+50.00 TO 25+08.35	RT				402	
22+81.97	LT					1
22+84.00	RT					1
24+23.07	RT					1
25+00.00	LT					1

## EROSION CONTROL

LOCATION STATION TO STATION	SIDE	EROSION CONTROL BLANKET	HEAVY DUTY EROSION CONTROL BLANKET	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET & PIPE PROTECTION
		25100630 SQ YD	25100635 SQ YD	28000305 FOOT	28000400 FOOT	28000500 EACH
<b>STAGE 2</b>						
<b>U.S. 150</b>						
151+25.00	LT					1
151+25.00 TO 152+32.04	LT	797.2				
152+32.04 TO 152+87.56	LT	469.4				
152+57.93	LT					1
152+60.02	LT					1
152+87.56 TO 155+11.67	LT	2,299.5				
153+56.34	LT			10		
153+66.75	LT					1
155+06.14	LT					1
155+11.67 TO 156+24.95	LT	1,369.9				
155+87.67	LT			10		
158+37.73 TO 159+23.35	LT	957.9			83	
159+23.35 TO 160+45.83	LT	1,282.5			123	
159+28.75	LT					1
159+95.50	LT			10		
160+24.54	LT					1
160+45.83 TO 161+00.00	LT	526.6				
160+45.83 TO 161+33.15	LT				91	
161+00.00 TO 161+33.15	LT		290.8			
161+01.84	LT					1
161+33.15 TO 161+50.00	LT				17	
161+33.15 TO 162+05.27	LT		425.1			
<b>PROJECT TOTAL</b>		<b>16,699</b>	<b>1,975</b>	<b>60</b>	<b>716</b>	<b>23</b>

## GRADING AND SHAPING DITCHES

LOCATION STATION TO STATION	SIDE	GRADING AND SHAPING DITCHES 21400100 SQ YD
<b>CHAMPAIGN COUNTY</b>		
<b>STAGE 1</b>		
<b>U.S. 150</b>		
150+54.70 TO 151+83.50	RT	129.0
<b>PROJECT TOTAL</b>		<b>129</b>

## EARTHWORK

LOCATION STATION TO STATION	SIDE	EARTH EXCAVATION 20200100 CU YD	FOR INFORMATION ONLY				FURNISHED EXCAVATION 20400800 CU YD	TOPSOIL FURNISH AND PLACE, 4" 21101615 SQ YD	TOPSOIL FURNISH AND PLACE, 12" 21101645 SQ YD
			AVERAGE SHRINKAGE FACTOR %	EARTH EXCAVATION (ADJUSTED) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) CU YD			
<b>CHAMPAIGN COUNTY</b>									
<b>PRE-STAGE A</b>									
<b>U.S. 150</b>									
150+24.18 TO 151+25.00		20	25	15	5	10	-10	361	
<b>STAGE 1</b>									
<b>U.S. 150</b>									
149+50.00 TO 162+00.00	RT	2,785	25	2,089	10,315	-8,226	8,226	10,985	
<b>MIDWEST COURT</b>									
19+82.96 TO 25+08.35		3,455	25	2,591	55	2,536	-2,536		3,359
<b>STAGE 2</b>									
<b>U.S. 150</b>									
151+00.00 TO 162+00.00	LT	1,590	25	1,193	12,935	-11,743	11,743	9,045	
<b>PROJECT TOTAL</b>		<b>7,850</b>					<b>17,430</b>	<b>20,392</b>	<b>3,359</b>

## SEEDING

LOCATION STATION TO STATION	SIDE	SEEDING, CLASS 2A	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
		25000210 ACRE	25100115 ACRE	28000250 POUND	25000400 POUND	25000500 POUND	25000600 POUND
<b>CHAMPAIGN COUNTY</b>							
<b>PRE-STAGE A</b>							
<b>U.S. 150</b>							
149+43.03 TO 151+25.00	LT	0.09	0.01	8.6	7.7	7.7	7.7
<b>I-57</b>							
577+32.37 TO 580+98.37	RT	0.43	0.43	43.3	39.0	39.0	39.0
581+81.04 TO 583+28.98	CL	0.19	0.19	19.1	17.2	17.2	17.2
<b>STAGE 1</b>							
<b>U.S. 150</b>							
150+64.07 TO 151+25.00	RT	0.09		9.1	8.2	8.2	8.2
151+25.00 TO 152+32.04	RT	0.18		18.3	16.5	16.5	16.5
152+32.04 TO 152+87.56	RT	0.12		12.0	10.8	10.8	10.8
152+87.56 TO 155+11.67	RT	0.58		58.2	52.4	52.4	52.4
155+11.67 TO 156+51.16	RT	0.35	0.06	34.6	31.2	31.2	31.2
158+07.37 TO 159+23.35	RT	0.32	0.16	32.5	29.2	29.2	29.2
159+23.35 TO 160+45.83	RT	0.30		30.3	27.3	27.3	27.3
160+45.83 TO 161+33.15	RT	0.20		20.2	18.2	18.2	18.2
161+33.15 TO 162+00.00	RT	0.12		12.1	10.9	10.9	10.9
<b>MIDWEST COURT</b>							
19+82.96 TO 22+49.19	LT	0.15	0.15	15.4	13.8	13.8	13.8
19+82.96 TO 22+49.19	RT	0.04	0.04	4.3	3.9	3.9	3.9
22+49.19 TO 25+08.35	LT	0.62	0.62	61.9	55.7	55.7	55.7
22+49.19 TO 25+08.35	RT	0.13	0.13	13.1	11.8	11.8	11.8
<b>STAGE 2</b>							
<b>U.S. 150</b>							
151+25.00 TO 152+32.04	LT	0.16		16.5	14.8	14.8	14.8
152+32.04 TO 152+87.56	LT	0.10		9.7	8.7	8.7	8.7
152+87.56 TO 155+11.67	LT	0.48		47.6	42.8	42.8	42.8
155+11.67 TO 156+51.58	LT	0.34	0.06	34.2	30.8	30.8	30.8
158+11.46 TO 159+23.35	LT	0.26	0.06	26.1	23.5	23.5	23.5
159+23.35 TO 160+45.83	LT	0.27		27.1	24.4	24.4	24.4
160+45.83 TO 161+33.15	LT	0.17		17.0	15.3	15.3	15.3
161+33.15 TO 162+00.00	LT	0.09		8.8	7.9	7.9	7.9
<b>PROJECT TOTAL</b>		<b>6.00</b>	<b>2.00</b>	<b>580</b>	<b>530</b>	<b>530</b>	<b>530</b>

NOTE: FERTILIZER APPLICATION RATE = 90 LB/ACRE  
 TEMPORARY EROSION CONTROL SEEDING INCLUDES 3 APPLICATIONS, APPLICATION RATE = 100 LB/ACRE

## EXPLORATION TRENCH

LOCATION STATION TO STATION	SIDE	EXPLORATION TRENCH 52" DEPTH
		21301052 FOOT
<b>CHAMPAIGN COUNTY</b>		
<b>STAGE 2</b>		
<b>U.S. 150</b>		
151+49.89 TO 156+00.82	LT	450.9
158+69.58 TO 162+10.00	LT	340.4
<b>PROJECT TOTAL</b>		<b>792</b>

## GEOTEXTILE RETAINING WALL

LOCATION STATION TO STATION	SIDE	GEOTEXTILE RETAINING WALL
		52200600 SQ YD
<b>CHAMPAIGN COUNTY</b>		
<b>STAGE 1</b>		
<b>U.S. 150</b>		
152+87.56 TO 155+50.67	CL	735.0
158+84.35 TO 160+45.83	CL	321.0
<b>PROJECT TOTAL</b>		<b>1,056</b>

## RIPRAP

LOCATION STATION TO STATION	SIDE	STONE RIPRAP, CLASS A4	FILTER FABRIC
		28100107 SQ YD	28200200 SQ YD
<b>CHAMPAIGN COUNTY</b>			
<b>STAGE 1</b>			
<b>U.S. 150</b>			
152+58.00	RT	5.4	5.4
155+00.00	RT	5.4	5.4
159+34.00	RT	6.0	6.0
161+02.00	RT	5.8	5.8
<b>STAGE 2</b>			
<b>U.S. 150</b>			
151+25.00	LT	6.6	6.6
152+58.00	LT	5.4	5.4
155+00.00	LT	5.4	5.4
155+19.67	LT	37.9	37.9
159+15.35	LT	38.0	38.0
159+34.00	LT	5.4	5.4
161+02.00	LT	5.4	5.4
<b>PROJECT TOTAL</b>		<b>127</b>	<b>127</b>



# REMOVAL

LOCATION STATION TO STATION	SIDE	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL, ACRES	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	SHOULDER RUMBLE STRIP REMOVAL	HOT-MX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	CURB REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	GUARDRAIL REMOVAL	GUARD POSTS REMOVAL	REMOVE IMPACT ATTENUATORS, NO SALVAGE	REMOVE ATTENUATOR BASE	REMOVAL OF EXISTING STRUCTURES	PIPE CULVERT REMOVAL	STORM SEWER REMOVAL 18"	CONCRETE HEADWALL REMOVAL	DRAINAGE STRUCTURE TO BE REMOVED
		20100110 UNIT	20100500 ACRE	44000100 SQ YD	4404250 SQ YD	X0325201 SQ YD	X4401198 SQ YD	44000300 FOOT	44000500 FOOT	44000600 SQ FT	63200310 FOOT	X6340205 EACH	X6430120 EACH	X6431110 EACH	50100100 EACH	50105220 FOOT	55100900 FOOT	50104400 EACH	Z0018700 EACH
<b>CHAMPAIGN COUNTY</b>																			
<b>STAGE 1</b>																			
<b>U.S. 150</b>																			
149+36.00 TO 149+80.00	LT					5													
150+65.00 TO 156+25.00	RT		1.25																
150+89.17 TO 155+90.68	RT										501.5								
152+18.50 TO 152+32.04	*RT				0.8														
152+32.04 TO 152+87.56	*RT				7.3														
152+56.77	RT																	1	
152+58.20	RT																		1
152+58.69	RT															54.2			
152+87.56 TO 155+21.67	RT			291.3	220.0														
153+67.14	RT																	1	
153+69.16	RT																		1
153+69.35	RT															52.9			
158+30.00 TO 162+00.00	RT		1.25																
155+21.67 TO 155+73.44	RT			70.6	46.0														
156+02.93 TO 158+59.30	RT														0.5				
158+72.28 TO 161+97.75	RT										325.5								
158+89.19 TO 159+13.35	RT			34.2	21.3														
159+13.55 TO 160+45.83	RT			186.6	115.9														
160+24.02	RT															59.1			
160+24.21	RT																	1	
160+24.72	RT																		1
160+45.83 TO 161+33.15	*RT				7.8														
161+33.15 TO 161+48.00	*RT				1.1														
162+75.00 TO 163+55.00	LT					9													
<b>I-57</b>																			
581+74.00	CL											1							
581+79.00	CL											1							
581+84.00	CL											1							
581+89.00	CL											1							
582+31.00	CL												1	1					
<b>MIDWEST COURT</b>																			
19+82.96 TO 21+04.62	LT			203.6															
19+82.96 TO 21+04.62	RT			202.2															
19+82.96 TO 23+66.12	LT								383										
19+82.96 TO 24+04.59	RT								422										
19+82.96 TO 25+08.35	LT									2,215									
20+21.32	RT																		1
20+21.33	LT																		1
20+21.40	LT																		
20+21.46 TO 22+82.78	RT																	33.1	
21+04.62 TO 22+49.19	LT			240.1															261.3
21+04.62 TO 22+49.19	RT			244.2															
21+29.91	RT	6																	
21+65.23	LT	6																	
21+75.92	LT	6																	
22+09.42	RT	6																	
22+49.19 TO 23+66.12	LT			192.7															
22+49.19 TO 23+66.12	RT			196.3															
22+72.30	LT	6																	
22+81.66	LT																		1
22+82.25	RT																	32.9	
22+82.78	RT																		1
22+82.79 TO 24+22.85	RT																	140.2	
23+66.12 TO 25+08.16	LT&RT								365										
23+66.12 TO 25+08.16	LT			1,027.6															
23+66.12 TO 25+08.16	RT			347.2															

SCHEDULE CONTINUED ON THE NEXT SHEET

# REMOVAL

LOCATION STATION TO STATION	SIDE	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL, ACRES	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	SHOULDER RUMBLE STRIP REMOVAL	HOT-MX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	CURB REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	GUARDRAIL REMOVAL	GUARD POSTS REMOVAL	REMOVE IMPACT ATTENUATORS, NO SALVAGE	REMOVE ATTENUATOR BASE	REMOVAL OF EXISTING STRUCTURES	PIPE CULVERT REMOVAL	STORM SEWER REMOVAL 18"	CONCRETE HEADWALL REMOVAL	DRAINAGE STRUCTURE TO BE REMOVED
		20100110 UNIT	20100500 ACRE	44000100 SQ YD	4404250 SQ YD	X0325201 SQ YD	X4401198 SQ YD	44000300 FOOT	44000500 FOOT	44000600 SQ FT	63200310 FOOT	X6340205 EACH	X6430120 EACH	X6431110 EACH	50100100 EACH	50105220 FOOT	55100900 FOOT	50104400 EACH	Z0018700 EACH
24+22.85	RT																		1
24+43.04	RT																118.1		
24+99.27	LT																		1
24+99.78 TO OUTLET	LT																48.5		
N 1267518.97 E 997122.96		6																	
<b>STAGE 2</b>																			
<b>U.S. 150</b>																			
150+80.57 TO 155+90.95	LT										505.6								
151+40.00 TO 156+25.00	LT		1.00																
152+18.50 TO 152+32.04	*LT					3.2													
152+32.04 TO 152+87.56	*LT					4.7													
152+59.20	LT																	1	
152+60.59	LT															54.5			1
152+87.56 TO 155+21.67	LT			321.4	207.6														
152+66.62	LT																		1
153+64.02	LT																	1	
153+67.53	LT															47.8			
155+21.67 TO 155+73.44	LT			72.6	44.5														
156+02.93 TO 158+59.30	LT														0.5				
158+30.00 TO 162+05.00	LT		0.50																
158+71.59 TO 162+03.06	LT										331.5								
158+89.19 TO 159+13.35	LT			33.4	21.3														
159+13.55 TO 160+45.83	LT			180.1	123.0														
160+24.02	LT															55.1			
160+24.67	LT																		1
160+25.09	LT																	1	
160+45.83 TO 161+33.15	*LT					8.6													
161+33.15 TO 161+48.00	*LT					0.9													
162+75.00 TO 163+68.00	RT						11												
<b>I-57</b>																			
582+73.00	CL												1	1					
583+09.00	CL											1							
583+14.00	CL											1							
583+19.00	CL											1							
583+24.00	CL											1							
<b>STAGE 3</b>																			
<b>U.S. 150</b>																			
151+25.00 TO 152+18.50	LT						206.6												
151+25.00 TO 152+18.50	RT						208.9												
151+25.00 TO 152+18.50	*LT				25.0														
151+25.00 TO 152+18.50	*RT				1.0														
161+48.00 TO 162+00.00	LT						115.6												
161+48.00 TO 162+00.00	RT						115.6												
161+48.00 TO 162+00.00	*LT				3.6														
161+48.00 TO 162+00.00	*RT				3.8														
<b>PROJECT TOTAL</b>		<b>36</b>	<b>4.00</b>	<b>3,845</b>	<b>868</b>	<b>25</b>	<b>647</b>	<b>365</b>	<b>805</b>	<b>2,215</b>	<b>1,665</b>	<b>8</b>	<b>2</b>	<b>2</b>	<b>1</b>	<b>324</b>	<b>635</b>	<b>6</b>	<b>12</b>

NOTES: \* ONLY SHOULDER CURB INCLUDED IN THE REMOVAL

## HOT-MIX ASPHALT PAVEMENT

LOCATION STATION TO STATION	SIDE	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (TACK COAT)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N-70	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N-70	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TEMPORARY RAMP	HOT-MIX ASPHALT SHOULDER CURB	SHOULDER RUMBLE STRIPS, 8"
		40600275	40600290	40603540	40603310	40603235	40603085	40603080	40600990	66101150	64200108
		POUND	POUND	TON	TON	TON	TON	TON	SQ YD	FOOT	FOOT
<b>CHAMPAIGN COUNTY</b>											
<b>PRE-STAGE A</b>											
<b>U.S. 150</b>											
149+43.00 TO 150+97.00	LT		49		8.2			35.0			
<b>STAGE 1</b>											
<b>U.S. 150</b>											
152+24.64 TO 152+31.30	RT								13.4		
152+32.04 TO 152+87.56	RT		73			17.8		13.5			
152+46.34 TO 152+69.76	RT								29.2		
152+87.56 TO 155+06.33	RT	990.1	170			30.7	85.4	93.3			
154+88.32 TO 155+11.66	RT								37.8		
155+11.66 TO 155+21.67	RT								19.9		
159+13.35 TO 159+22.33	RT								18.0		
159+22.33 TO 159+45.67	RT								37.8		
159+28.65 TO 160+45.83	RT	277.3	91			16.4	45.6	49.6			
160+45.83 TO 161+33.15	RT		113			27.9		20.2			
160+90.33 TO 161+13.67	RT								29.2		
161+33.10 TO 161+39.77	RT								13.3		
<b>STAGE 2</b>											
<b>U.S. 150</b>											
151+64.48 TO 152+18.50	LT				2.6						
152+18.50 TO 152+32.04	LT				0.6						
152+24.64 TO 152+31.30	LT								16.2		
152+32.04 TO 152+87.56	LT		82		2.7	22.9		12.7			
152+46.34 TO 152+69.76	LT								29.2		
152+87.56 TO 155+06.33	LT	1,197.4	213		10.5	42.8	118.8	91.7			
154+88.33 TO 155+11.66	LT								48.2		
155+11.66 TO 155+21.67	LT								24.4		
159+13.35 TO 159+22.33	LT								22.0		
159+22.33 TO 159.45.67	LT								48.2		
159+28.65 TO 160+45.83	LT	644.5	114		5.7	23.0	63.8	49.6			
160+45.83 TO 161+33.15	LT		130		4.3	36.1		20.2			
160+90.33 TO 161+13.67	LT								29.2		
161+33.10 TO 161+39.77	LT								16.3		
161+33.15 TO 161+48.00	LT				0.7						
161+48.00 TO 161+50.00	LT				0.1						

SCHEDULE CONTINUED ON THE NEXT SHEET

FILE NAME = D570B98-sht-schedule.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - CWW	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO STA.	CHAMPAIGN	147	27
	PLOT DATE = 5/6/2019 - 2:47:46 PM	CHECKED - BJE	REVISED -								CONTRACT NO.	70B98	
											ILLINOIS FED. AID PROJECT		

# HOT-MIX ASPHALT PAVEMENT

LOCATION STATION TO STATION	SIDE	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (TACK COAT)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N-70	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N-70	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TEMPORARY RAMP	HOT-MIX ASPHALT SHOULDER CURB	SHOULDER RUMBLE STRIPS, 8"
		40600275	40600290	40603540	40603310	40603235	40603085	40603080	40600990	66101150	64200108
		POUND	POUND	TON	TON	TON	TON	TON	SQ YD	FOOT	FOOT
<b>STAGE 3</b>											
<b>U.S. 150</b>											
149+36.00 TO 150+97.00	LT										160
151+25.00 TO 152+18.50	LT		103	14.0	9.2					92.4	94
151+25.00 TO 152+18.50	RT		104	14.1	9.4					94.6	94
152+18.50 TO 152+32.04	LT		15	2.6	1.7					12.7	14
152+18.50 TO 152+32.04	RT		15	2.6	1.7					13.0	14
152+32.04 TO 152+87.56	LT		92	8.3	5.5					55.6	56
152+32.04 TO 152+87.56	RT		92	8.4	5.6					56.9	56
152+87.56 TO 155+06.33	LT		120	32.8	21.6					216.9	224
152+87.56 TO 155+06.33	RT		120	32.6	21.9					221.3	224
155+06.33 TO 155+21.67	LT									15.0	10
155+06.33 TO 155+21.67	RT									15.0	10
159+13.35 TO 159+28.65	LT									15.0	10
159+13.35 TO 159+28.65	RT									15.0	10
159+28.65 TO 160+45.83	LT		65	17.6	11.6					117.5	122
159+28.65 TO 160+45.83	RT		65	17.6	11.7					117.5	122
160+45.83 TO 161+33.15	LT		96	13.1	8.7					87.3	87
160+45.83 TO 161+33.15	RT		96	13.1	8.7					87.3	87
161+33.15 TO 161+48.00	LT		17	2.8	1.8					14.9	15
161+33.15 TO 161+48.00	RT		17	2.8	1.8					14.9	15
161+48.00 TO 162+00.00	LT		57	7.8	5.2					52.0	52
161+48.00 TO 162+00.00	RT		57	7.8	5.2					52.0	52
162+00.00 TO 163+55.00	LT										155
162+00.00 TO 163+55.00	RT										168
<b>PROJECT TOTAL</b>		<b>3,110</b>	<b>2,166</b>	<b>199</b>	<b>167</b>	<b>218</b>	<b>314</b>	<b>386</b>	<b>433</b>	<b>1,367</b>	<b>1,851</b>

## GRANULAR EMBANKMENT, SPECIAL

LOCATION STATION TO STATION	SIDE	GRANULAR EMBANKMENT, SPECIAL
		2060200 CU YD
<b>CHAMPAIGN COUNTY</b>		
<b>STAGE 1</b>		
<b>U.S. 150</b>		
152+87.00 TO 153+87.00	RT	178.2
153+87.00 TO 154+87.00	RT	318.0
154+87.00 TO 155+43.00	RT	215.1
158+91.00 TO 159+45.00	RT	142.7
159+45.00 TO 160+45.00	RT	182.5
<b>STAGE 2</b>		
<b>U.S. 150</b>		
152+87.00 TO 153+87.00	LT	213.2
153+87.00 TO 154+87.00	LT	342.3
154+87.00 TO 155+43.00	LT	253.7
158+91.00 TO 159+45.00	LT	168.2
159+45.00 TO 160+45.00	LT	192.3
<b>PROJECT TOTAL</b>		<b>2,207</b>

## AGGREGATE SHOULDER

LOCATION STATION TO STATION	SIDE	AGGREGATE WEDGE SHOULDER, TYPE B
		48102100 TON
<b>CHAMPAIGN COUNTY</b>		
<b>PRE-STAGE A</b>		
<b>U.S. 150</b>		
149+43.00 TO 150+97.00	LT	12
<b>PROJECT TOTAL</b>		<b>12</b>

## PAVEMENT CONNECTOR

LOCATION STATION TO STATION	SIDE	BRIDGE APPROACH PAVEMENT CONNECTOR (SPECIAL)	* PARAPET RAILING
		X4201410 SQ YD	50901750 FOOT
<b>CHAMPAIGN COUNTY</b>			
<b>STAGE 1</b>			
<b>U.S. 150</b>			
155+06.33 TO 155+21.67	RT	32.2	
159+13.23 TO 159+28.65	RT	31.5	
<b>STAGE 2</b>			
<b>U.S. 150</b>			
155+06.33 TO 155+21.67	LT	54.6	15.0
159+13.23 TO 159+28.65	LT	53.5	15.0
<b>PROJECT TOTAL</b>		<b>172</b>	<b>30</b>

NOTES: \* SEE STRUCTURE PLANS BILL OF MATERIALS FOR ADDITIONAL QUANTITY

## DRAINAGE

LOCATION STATION TO STATION	SIDE	TRENCH BACKFILL	STORM SEWERS, CLASS A, TYPE 2 18"	STORM SEWERS, CLASS A, TYPE 2 24"	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	TYPE E INLET BOX, STANDARD	PIPE DRAINS 12"	CONCRETE THRUST BLOCKS	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	METAL END SECTIONS 12"
		20800150 CU YD	550A0380 FOOT	550A0410 FOOT	60218500 EACH	61000115 EACH	60100945 FOOT	61000050 EACH	54213669 EACH	54215547 EACH
<b>CHAMPAIGN COUNTY</b>										
<b>STAGE 1</b>										
<b>U.S. 150</b>										
152+58.00	RT					1	61	1		1
155+00.00	RT					1	86	1		1
159+34.00	RT					1	95	1		1
161+02.00	RT					1	84	1		1
<b>MIDWEST COURT</b>										
20+21.11	LT				1					
20+21.11	RT				1					
20+21.11	CL	39	30							
20+21.11 TO 22+07.80	RT	106	186							
20+21.46 TO 22+82.78	RT	236								
22+07.80	RT				1					
22+07.80 TO 22+38.58	RT	77		103						
22+38.58	LT				1					
22+38.58 TO 22+90.00	LT	8		52						
22+90.00	LT							1		
<b>STAGE 2</b>										
<b>U.S. 150</b>										
151+25.00	LT					1	47	1		1
152+58.00	LT					1	68	1		1
155+00.00	LT					1	94	1		1
159+34.00	LT					1	95	1		1
161+02.00	LT					1	81	1		1
<b>PROJECT TOTAL</b>		<b>466</b>	<b>216</b>	<b>155</b>	<b>4</b>	<b>9</b>	<b>711</b>	<b>9</b>	<b>1</b>	<b>9</b>

## SIDEWALK

LOCATION STATION TO STATION	SIDE	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH 42400300
		SQ FT
<b>CHAMPAIGN COUNTY</b>		
<b>STAGE 1</b>		
<b>MIDWEST COURT</b>		
19+82.96 TO 21+04.62	LT	608.2
21+04.62 TO 22+67.44	LT	1195.1
<b>STAGE 2</b>		
<b>U.S. 150</b>		
151+64.48 TO 152+18.50	LT	258.50
152+18.50 TO 152+32.04	LT	63.10
152+32.04 TO 152+87.56	LT	272.78
152+87.56 TO 153+71.02	LT	410.88
153+71.02 TO 155+06.33	LT	668.30
159+28.65 TO 159+59.65	LT	155.00
159+59.65 TO 160+45.83	LT	430.90
160+45.83 TO 161+33.15	LT	436.60
161+33.15 TO 161+48.00	LT	74.25
161+48.00 TO 161+50.00	LT	10.00
<b>PROJECT TOTAL</b>		<b>4,584.0</b>

## R.O.W. MARKERS

LOCATION STATION TO STATION	SIDE	OFFSET	FURNISHING AND ERECTING R.O.W. MARKERS 66600105
			EACH
<b>CHAMPAIGN COUNTY</b>			
<b>STAGE 1</b>			
<b>U.S. 150</b>			
152+75.00	RT	120.08	1
152+75.00	RT	130.00	1
153+84.08	RT	145.00	1
154+78.15	RT	145.00	1
155+62.08	RT	145.00	1
160+90.32	RT	125.00	1
161+60.00	RT	125.00	1
161+90.00	RT	88.47	1
<b>I-57</b>			
575+80.00	RT	122.94	1
579+65.00	RT	175.20	1
<b>STAGE 2</b>			
<b>U.S. 150</b>			
152+20.00	LT	109.94	1
155+10.00	LT	145.00	1
159+04.97	LT	140.00	1
161+00.00	LT	140.00	1
161+76.03	LT	75.02	1
<b>PROJECT TOTAL</b>			<b>15</b>

## P.C.C. PAVEMENT

LOCATION STATION TO STATION	SIDE	PROTECTIVE COAT	PORTLAND CEMENT CONCRETE PAVEMENT 7 1/2"	SUBBASE GRANULAR MATERIAL, TYPE A 12"	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18
		42001300 SQ YD	42000211 SQ YD	31100910 SQ YD	60604400 FOOT
<b>CHAMPAIGN COUNTY</b>					
<b>STAGE 1</b>					
<b>MIDWEST COURT</b>					
19+82.96 TO 21+04.62	LT	230	202	237	121.7
18+92.96 TO 21+04.62	RT	230	202	237	121.7
21+04.62 TO 22+46.90	CUL-DE-SAC	1,483	1,389	1,505	407.0
<b>PROJECT TOTAL</b>		<b>1,943</b>	<b>1,793</b>	<b>1,979</b>	<b>650.5</b>

## TEMPORARY CONCRETE BARRIER

LOCATION STATION TO STATION	SIDE	DESCRIPTION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	PINNING TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
			70400100 FOOT	70400200 FOOT	X7040125 EACH	70600250 EACH	70600260 EACH	70600350 EACH
<b>CHAMPAIGN COUNTY</b>								
<b>PRE-STAGE A</b>								
<b>I-57</b>								
578+36.00	*LT	NORTHBOUND I-57					1	
578+36.00 TO 583+11.00	*LT	NORTHBOUND I-57	475.0					
578+79.50	*RT	NORTHBOUND I-57					1	
578+79.50 TO 583+04.50	*RT	NORTHBOUND I-57	425.0					
581+93.00 TO 586+68.00	*LT	SOUTHBOUND I-57	475.0					
581+96.00 TO 586+08.50	*RT	SOUTHBOUND I-57	412.5					
586+08.50	*RT	SOUTHBOUND I-57				1		
586+68.00	*LT	SOUTHBOUND I-57					1	
<b>STAGE 1</b>								
<b>U.S. 150</b>								
150+25.00	RT					1		
150+25.00 TO 163+25.00	LT		1,300.0					
163+25.00	RT					1		
<b>STAGE 2</b>								
<b>U.S. 150</b>								
150+12.50	LT							1
150+12.50 TO 163+12.50	RT			1,300.0				
163+12.50 TO 163+37.50	RT		25.0					
163+37.50	LT							1
152+06.30 TO 155+21.67	RT				72			
159+13.35 TO 161+58.10	RT				57			
<b>PROJECT TOTAL</b>			<b>3,112.5</b>	<b>1,300.0</b>	<b>129</b>	<b>3</b>	<b>3</b>	<b>2</b>

NOTES: \* LT/RT SIDES ARE GIVEN WITH RESPECT TO THE DIRECTION OF TRAFFIC.

## IMPACT ATTENUATOR

LOCATION STATION TO STATION	SIDE	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	ATTENUATOR BASE	GUARD POSTS
		64300450 EACH	64301090 SQ YD	63400105 EACH
<b>CHAMPAIGN COUNTY</b>				
<b>STAGE 1</b>				
<b>I-57</b>				
581+70.00	CL			1
581+75.00	CL			1
581+80.00	CL			1
581+85.00	CL			1
582+31.00	CL	1	51	
<b>STAGE 2</b>				
<b>I-57</b>				
583+25.00	CL			1
583+30.00	CL			1
583+35.00	CL			1
583+40.00	CL			1
582+79.00	CL	1	51	
<b>PROJECT TOTAL</b>		<b>2</b>	<b>102</b>	<b>8</b>

## FENCE

LOCATION STATION TO STATION	SIDE	WOVEN WIRE FENCE, 4' 66500105	WOVEN WIRE FENCE REMOVAL X6650202	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED X6640304
		FOOT	FOOT	FOOT
<b>CHAMPAIGN COUNTY</b>				
<b>I-57</b>				
575+77.01 TO 581+52.32	RT	581		
575+77.01 TO 581+52.70	RT		590	
579+37.19 TO 579+60.71	RT		35	
581+06.40 TO 581+32.94	LT		27	
583+39.12 TO 583+92.36	RT		54	
583+63.66 TO 584+02.95	LT		40	
<b>U.S. 150</b>				
152+75.00 TO 154+62.69	RT			225
154+59.89 TO 155+71.65	RT		113	
154+62.69 TO 155+74.71	RT	114		
155+11.04 TO 155+23.91	LT	38		
155+11.04 TO 155+99.21	LT	89		
158+74.03 TO 159+03.95	LT	30		
158+94.11 TO 159+03.95	LT	53		
160+96.63 TO 161+86.18	RT	105		
160+96.63 TO 161+86.18	RT		102	
<b>PROJECT TOTAL</b>		<b>1,010</b>	<b>961</b>	<b>225</b>

# SIGNS

LOCATION STATION TO STATION	SIDE	OFFSET	SIGN DESCRIPTION	SIGN PANEL	STRUCTURAL	CONCRETE	RELOCATE	REMOVE AND	REMOVE
				TYPE 3	STEEL SIGN		SIGN PANEL	REMOVE AND	OVERHEAD SIGN
				72000300	SUPPORT -	FOUNDATIONS	ASSEMBLY -	PANEL AND POLE	STRUCTURE -
				SQ FT	BREAKAWAY	CU YD	TYPE A	ASSEMBLY	BRIDGE
					72700100			X2600012	MOUNTED
							EACH	EACH	
									73602000
									EACH
<b>CHAMPAIGN COUNTY</b>									
<b>PRE-STAGE A</b>									
<b>I-57</b>									
580+95.00	*RT	78.00	W13-3			1.4		1	
580+95.00	*RT	125.25	Exit 237B	28.8					
580+95.00	*RT	124.50	I-74 West, Peoria 1/4 Mile	136.5	1,560	3.8			
580+95.00	*RT	147.25	Exit 237A	28.8					
580+95.00	*RT	143.00	I-74 East, Indianapolis	190.0	1,900	3.8			
<b>STAGE 1</b>									
<b>U.S. 150</b>									
157+85.00	RT								1
<b>STAGE 2</b>									
<b>U.S. 150</b>									
154+80.00	LT	21.00	W2-2				1		
<b>PROJECT TOTAL</b>				<b>384</b>	<b>3,460</b>	<b>9.0</b>	<b>1</b>	<b>1</b>	<b>1</b>

NOTES: \* LT/RT SIDES ARE GIVEN WITH RESPECT TO THE DIRECTION OF TRAFFIC. OFFSET DISTANCE IS FROM THE I-57 CENTERLINE TO THE CENTER OF THE SIGN PANEL.

# CHANGEABLE MESSAGE SIGN

LOCATION STATION TO STATION	NUMBER OF SIGNS	NUMBER OF DAYS	ADDITIONAL DAYS	CHANGEABLE MESSAGE SIGN
	EACH	DAY	CAL DAY	70107025 CAL DAY
<b>CHAMPAIGN COUNTY</b>				
<b>U.S. 150 OVER I-57 DETOUR</b>				
I-72	2	8	21	58
I-74	2	8	21	58
I-57	2	8	21	58
<b>CARDINAL ROAD DETOUR</b>				
U.S. 150	2	244	21	530
<b>PROJECT TOTAL</b>				<b>704</b>

SEE DETOUR PLANS FOR APPROXIMATE LOCATIONS. 3 WEEKS NOTICE NEEDED PRIOR TO ROAD CLOSURE.

# RAISED REFLECTIVE PAVEMENT MARKERS

LOCATION STATION TO STATION	SIDE	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
		78100100	78300200
		TWO-WAY AMBER	
		EACH	EACH
<b>CHAMPAIGN COUNTY</b>			
<b>STAGE 1</b>			
<b>U.S. 150</b>			
141+31.00 TO 165+00.00	CL		21
<b>STAGE 3</b>			
<b>U.S. 150</b>			
148+31.00 TO 155+21.67	CL	9	
159+13.35 TO 165+00.00	CL	8	
<b>PROJECT TOTAL</b>		<b>17</b>	<b>21</b>

# GUARDRAIL

LOCATION STATION TO STATION	SIDE	FOR INFORMATION ONLY	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	GUARDRAIL REFLECTORS, TYPE A	TERMINAL MARKER - DIRECT APPLIED
		LENGTH	63000001	63100045	63100085	63100167	78200005	72501000
		FOOT	FOOT	EACH	EACH	EACH	EACH	EACH
<b>CHAMPAIGN COUNTY</b>								
<b>STAGE 1</b>								
<b>U.S. 150</b>								
150+78.84 TO 151+28.84	RT	50.0				1		1
150+78.63 TO 155+39.17	RT						6	
151+28.63 TO 154+99.56	RT		375.0					
154+99.56 TO 155+39.16	RT	39.4		1				
158+95.82 TO 159+35.22	RT	39.4		1				
159+26.15 TO 161+97.72	RT						4	
159+35.25 TO 161+97.72	RT		262.5					
<b>I-57</b>								
582+16.66 TO 582+29.19	RT	12.5		1				
<b>STAGE 2</b>								
<b>U.S. 150</b>								
150+52.62 TO 151+02.62	LT	50.0				1		1
150+52.62 TO 155+08.83	LT						6	
151+02.62 TO 154+69.33	LT		362.5					
154+69.33 TO 155+08.83	LT	39.4			1			
159+10.85 TO 159+50.25	LT	39.4			1			
159+10.85 TO 162+03.06	LT						4	
159+65.55 TO 162+03.06	LT		237.5					
<b>I-57</b>								
582+75.35 TO 582+87.85	LT	12.5		1				
<b>PROJECT TOTAL</b>			<b>1,237.5</b>	<b>2</b>	<b>4</b>	<b>2</b>	<b>20</b>	<b>2</b>

FILE NAME = D570898-sht-schedule.dgn	USER NAME = bemory	DESIGNED - CWV	REVISED -
		DRAWN - CWV	REVISED -
		CHECKED - BJE	REVISED -
		DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULES OF QUANTITIES**

SCALE: N.T.S. SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	31
CONTRACT NO. 70B98				
ILLINOIS FED. AID PROJECT				

# PAVEMENT MARKING

LOCATION STATION TO STATION	SIDE	DESCRIPTION	POLYUREA PAVEMENT MARKING TYPE II - LINE 4" 78008310		GROOVING FOR RECESSED PAVEMENT MARKING X7830070	
			LINE 4"		5"	
			WHITE FOOT	YELLOW FOOT	WHITE FOOT	YELLOW FOOT
<b>CHAMPAIGN COUNTY</b>						
<b>STAGE 3</b>						
<b>U.S. 150</b>						
148+31.00 TO 155+21.67	CL	SKIP DASH		173		691
148+31.00 TO 155+21.67	CL	CL SOLID		691		691
149+43.00 TO 163+41.00	LT	EDGE	1,398		1,398	
150+63.65 TO 163+68.00	RT	EDGE	1,382		1,382	
155+21.67 TO 165+00.00	CL	DOUBLE SOLID		1,957		978
<b>COLOR SUBTOTAL</b>			<b>2,780</b>	<b>2,821</b>	<b>2,780</b>	<b>2,360</b>
<b>PROJECT TOTAL</b>			<b>5,601</b>		<b>5,140</b>	

# TEMPORARY PAVEMENT MARKING

LOCATION STATION TO STATION	SIDE	DESCRIPTION	TEMPORARY PAVEMENT MARKING 7030220		TEMPORARY PAVEMENT MARKING (FOR INFORMATION ONLY)		SHORT TERM PAVEMENT MARKING 70300100	SHORT TERM PAVEMENT MARKING REMOVAL 70300150	PAVEMENT MARKING REMOVAL - GRINDING X0327979	
			LINE 4"		LINE 4"	LINE 24"	LINE 4"	LINE 4"	WHITE	YELLOW
			WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	YELLOW FOOT	YELLOW SQ FT	WHITE SQ FT	YELLOW SQ FT
<b>CHAMPAIGN COUNTY</b>										
<b>STAGE 1</b>										
<b>U.S. 150</b>										
148+49.00	RT	SKIP DASH AND SOLID CL								63
148+49.00 TO 150+00.00	CL	STOP BAR			11					
148+59.00 TO 164+62.00	RT	EDGE			1,603					
149+36.00 TO 163+55.00	LT	EDGE			1,419				473	
163+00.00 TO 164+50.00	CL	DOUBLE SOLID CL								100
166+84.00 TO 167+00.00	LT	STOP BAR				16				
168+30.00	LT	STOP BAR				11				
<b>STAGE 2</b>										
<b>U.S. 150</b>										
148+31.00	RT	STOP BAR				11				
148+31.00 TO 148+49.00	CL	SKIP DASH AND SOLID CL								8
148+49.00	RT	STOP BAR							22	
148+59.00 TO 152+31.30		EDGE							124	
148+91.00 TO 164+91.00	LT	EDGE			1,602					
149+43.00 TO 152+31.30		EDGE							95	
149+86.00 TO 163+68.00	RT	EDGE			1,384					
150+63.65 TO 163+68.00	RT	EDGE							461	
164+50.00 TO 165+00.00	CL	DOUBLE SOLID								33
<b>STAGE 3</b>										
<b>U.S. 150</b>										
148+31.00	RT	STOP BAR							22	
148+31.00 TO 155+21.67	CL	SKIP DASH		173						58
148+31.00 TO 155+21.67	CL	SOLID CL		691						230
148+31.00 TO 165+00.00	CL	SKIP DASH					167	55.7		
148+91.00 TO 164+91.00		EDGE							534	
149+43.00 TO 163+41.00	LT	EDGE	1,398						466	
149+86.00 TO 163+68.00	RT	EDGE	1,382						922	
155+21.67 TO 165+00.00	CL	DOUBLE SOLID CL		1,957						652
166+84.00 TO 167+00.00	LT	STOP BAR							32	
168+30.00	LT	STOP BAR							22	
<b>COLOR SUBTOTAL</b>			<b>2,780</b>	<b>2,821</b>					<b>3,173</b>	<b>1,144</b>
<b>PROJECT TOTAL</b>			<b>5,601</b>		<b>6,008</b>	<b>49</b>	<b>167</b>	<b>56</b>	<b>4,318</b>	

FILE NAME = D570B98-sht-schedule.dgn  
 Default

USER NAME = bemory  
 PLOT SCALE = 100.0000' / 1" = 10000000  
 PLOT DATE = 5/6/2019 - 2:48:09 PM

DESIGNED - CWW  
 DRAWN - CWW  
 CHECKED - BJE  
 DATE - 04/16/2019

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**


**SCHEDULES OF QUANTITIES**

SCALE: N.T.S.    SHEET    OF    SHEETS    STA.    TO    STA.


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	32
<b>CONTRACT NO. 70B98</b>				
<small>ILLINOIS FED. AID PROJECT</small>				



ALIGNMENTS COORDINATES - U.S. 150				
U.S. 150	STATION	OFFSET	N	E
PC	144+16.86	0.00'	1267065.61	996350.08
PI	149+64.98	85.16' RT	1266532.54	996477.63
PT	154+78.15	0.00'	1266171.36	996889.93
PC	169+88.41	0.00'	1265176.20	998025.94




PROP. CURVE US150.6  
 PI STA. = 149+64.98  
 $\Delta = 35^\circ 19' 30''$  (LT)  
 $D = 3^\circ 19' 43''$   
 $R = 1,721.38'$   
 $T = 548.12'$   
 $L = 1,061.30'$   
 $E = 85.16'$   
 $e = 3.40\%$   
 $T.R. = 36'$   
 $S.E. RUN = 82'$   
 P.C. STA. = 144+16.86  
 P.T. STA. = 154+78.15




HORIZONTAL DATUM - NAD 83 (1997) ILLINOIS STATE PLANE, EAST ZONE, FEET; VERTICAL DATUM - NAVD 1988, FEET

ALIGNMENTS COORDINATES - MIDWEST COURT				
MIDWEST CT	STATION	OFFSET	N	E
PI	19+82.96	0.00'	1267747.21	996632.33
POT	25+08.35	0.00'	1267455.26	997069.15



PROP. CURVE MIDWESTCT.3  
 PI STA. = 12+90.09  
 $\Delta = 108^\circ 32' 47''$  (RT)  
 $D = 63^\circ 39' 43''$   
 $R = 90.00'$   
 $T = 125.12'$   
 $L = 170.50'$   
 $E = 64.13'$   
 P.C. STA. = 11+64.96  
 P.T. STA. = 13+35.47

PROP. CURVE MIDWESTCT.6  
 PI STA. = 15+26.22  
 $\Delta = 33^\circ 22' 32''$  (LT)  
 $D = 95^\circ 29' 35''$   
 $R = 60.00'$   
 $T = 17.99'$   
 $L = 34.95'$   
 $E = 2.64'$   
 P.C. STA. = 15+08.24  
 P.T. STA. = 15+43.19



HORIZONTAL DATUM - NAD 83 (1997) ILLINOIS STATE PLANE, EAST ZONE, FEET; VERTICAL DATUM - NAVD 1988, FEET

FILE NAME = D570898-sh1-ATB.dgn	USER NAME = bemory	DESIGNED - CWW	REVISED -
Default		DRAWN - CWW	REVISED -
		CHECKED - BJE	REVISED -
		DATE - 04/16/2019	REVISED -




**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**ALIGNMENTS**




SCALE: 1" = 100' SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34H)BR-1	CHAMPAIGN	147	33
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	

ALIGNMENTS COORDINATES - I-57				
I-57	STATION	OFFSET	N	E
PI	548+01.95	0.00'	1263409.70	994806.09
PI	666+62.04	85.16' RT	1272331.90	1002619.93



HORIZONTAL DATUM - NAD 83 (1997) ILLINOIS STATE PLANE, EAST ZONE, FEET; VERTICAL DATUM - NAVD 1988, FEET











HORIZONTAL DATUM - NAD 83 (1997) ILLINOIS STATE PLANE, EAST ZONE, FEET; VERTICAL DATUM - NAVD 1988, FEET

FILE NAME = D570898-sh1-ATB.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -
Default	PLOT SCALE = 200.0000' / in.	DRAWN - CWW	REVISED -
	PLOT DATE = 5/6/2019 - 2:48:35 PM	CHECKED - BJE	REVISED -
		DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

ALIGNMENTS			
F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS
57	(10-34)B)BR-1	CHAMPAIGN	147
			SHEET NO. 34
CONTRACT NO. 70B98			
SCALE: 1" = 200'	SHEET	OF SHEETS	STA. TO STA.

ILLINOIS FED. AID PROJECT	
---------------------------	--



### BENCHMARKS

BM #4409-5	CHISELED SQUARE ON TOP OF THE CONCRETE BASE OF THE FIRST LIGHT POLE NORTH OF U.S. 150 ON THE WEST SIDE OF I-57. APPROXIMATE I-57 STA 583+73 EL 767.92
BM #4409-6	CHISELED SQUARE ON TOP OF THE EAST CONCRETE FOUNDATION FOR AN OVERHEAD SIGN FOR THE NORTH BOUND TRAFFIC APPROXIMATE I-57 STA 582+00 EL 773.35
BM #4802-1	CHISELED SQUARE IN CENTER OF OVERHEAD SIGN FOUNDATION IN THE MEDIAN OF FAI 57. STATION 612+70.80, 1.46' LT EL 764.855
BM #4802-13	CHISELED SQUARE ON TOP OF NORTH END OF NORTH CRASH BARREL PAD IN MEDIAN OF FAI 57. STATION 547+47.94, 3.59' LT EL 770.183
BM #4802-15	CHISELED SQUARE ON WEST SIDE OF WEST LEG OF LODGING SIGN FOUNDATION. FAI 57 STATION 644+01.61, 132.51' RT EL 766.499

FILE NAME = D570898-sht-ATB.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -
Default	PLOT SCALE = 200.0000' / in.	DRAWN - CWW	REVISED -
	PLOT DATE = 5/6/2019 - 2:48:35 PM	CHECKED - BJE	REVISED -
		DATE - 04/16/2019	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>TIES &amp; BENCHMARKS</b>		VERTICAL DATUM - NAVD 1988, FEET	
SCALE: N.T.S.	SHEET OF SHEETS	STA. TO STA.	

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	35
CONTRACT NO. 70B98				
ILLINOIS FED. AID PROJECT				

NOTES:  
 1. HOT-MIX ASPHALT SHOULDER CURB REMOVAL IS INCLUDED IN PAVED SHOULDER REMOVAL.  
 2. APPROACH SLAB REMOVAL SHALL BE INCLUDED IN THE COST OF REMOVAL OF EXISTING STRUCTURES.

	TREE REMOVAL		HMA SURFACE REMOVAL, VARIABLE DEPTH
	DRAINAGE STRUCTURE TO BE REMOVED		PAVEMENT REMOVAL
	STORM SEWER / PIPE CULVERT REMOVAL		SIDEWALK REMOVAL
	GUARDRAIL REMOVAL		REMOVAL OF EXISTING STRUCTURES
	COMB. CONC. CURB AND GUTTER / CURB REMOVAL		PAVED SHOULDER REMOVAL
	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED		TREE REMOVAL, ACRES
	WOVEN WIRE FENCE REMOVAL		





N. INV. = 769.67  
 S. INV. = 769.46

S.N. 010-8621  
 8' X 3' RC BOX  
 W. INV. = 763.60  
 E. INV. = 763.23

REMOVE IMPACT ATTENUATORS, NO SALVAGE  
 REMOVE EXISTING CONCRETE SLAB.  
 (SEE SPECIAL PROVISIONS)

GUARD POSTS REMOVAL 4-EACH  
 REMOVE IMPACT ATTENUATORS, NO SALVAGE  
 REMOVE EXISTING CONCRETE SLAB.  
 (SEE SPECIAL PROVISIONS)

REMOVE OVERHEAD SIGN  
 STRUCTURE - BRIDGE MOUNTED  
 159+10  
 280' RT



FILE NAME =  
 D570898-sht-removal.dgn

USER NAME = bemory  
 PLOT SCALE = 100.0000' / in.  
 PLOT DATE = 6/4/2019 - 9:53:55 AM

DESIGNED - CWW  
 DRAWN - CWW  
 CHECKED - BJE  
 DATE - 04/16/2019



REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**REMOVAL PLAN  
 U.S. 150 & I-57**

SCALE: 1" = 50' SHEET OF SHEETS STA. 149+00.00 TO STA. 164+00.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	36
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	



	TREE REMOVAL		HMA SURFACE REMOVAL, VARIABLE DEPTH
	DRAINAGE STRUCTURE TO BE REMOVED		PAVEMENT REMOVAL
	STORM SEWER / PIPE CULVERT REMOVAL		SIDEWALK REMOVAL
	GUARDRAIL REMOVAL		REMOVAL OF EXISTING STRUCTURES
	COMB. CONC. CURB AND GUTTER / CURB REMOVAL		PAVED SHOULDER REMOVAL
	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED		TREE REMOVAL, ACRES
	WOVEN WIRE FENCE REMOVAL		

FILE NAME = D570898-sht-removal.dgn	USER NAME = bemory	DESIGNED - CWW	REVISED -
Default	PLOT SCALE = 100.0000' / in.	DRAWN - CWW	REVISED -
	CHECKED - BJE	DATE - 04/16/2019	REVISED -
	PLOT DATE = 5/6/2019 - 2:48:57 PM		REVISED -




**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>REMOVAL PLAN MIDWEST COURT</b>			
SCALE: 1" = 50'	SHEET	OF SHEETS	STA. 15+00.00 TO STA. 25+08.35

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34)BR-1	CHAMPAIGN	147	37
				CONTRACT NO. 70B98
ILLINOIS FED. AID PROJECT				

PLAN	SURVEYED	DATE
	PLOTTED	
	GRADES CHECKED	
	STRUCTURE NOTATIONS CHECKED	
	NOTE BOOK NO.	
	CARD FILE NAME	



PROFILE	SURVEYED	DATE
	PLOTTED	
	GRADES CHECKED	
	STRUCTURE NOTATIONS CHECKED	
	NOTE BOOK NO.	
	CARD FILE NAME	



FILE NAME = D570898-shr-plnprf.dgn	USER NAME = bemery	DESIGNED - MKK	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b> <b>PLAN &amp; PROFILE</b> <b>U.S. 150</b> SCALE: 1" = 50' SHEET OF SHEETS STA. 150+00.00 TO STA. 165+00.00	F.A.I. RTE. 57	SECTION (10-34H)BR-1	COUNTY CHAMPAIGN	TOTAL SHEETS 147	SHEET NO. 38	
Default	PLOT SCALE = 100.0000' / 1"	CHECKED - BJE	REVISED -		CONTRACT NO. 70B98	ILLINOIS FED. AID PROJECT				
	PLOT DATE = 6/4/2019 - 9:42:44 AM	DATE - 04/16/2019	REVISED -							

PLAN	SURVEYED	BY	DATE
	PLOTTED		
	NOTE BOOK		
	NO.		
	ALIGNED		
	CHECKED		
	FILE NAME		

PROFILE	SURVEYED	BY	DATE
	PLOTTED		
	GRADES CHECKED		
	NO.		
	STRUCTURE		
	NOTATIONS		



780.86	781.14	781.10	781.18	781.26	780.61	779.33	779.21	778.05	777.23	776.63	775.17	775.19	774.36	773.97	773.46	773.02	772.80	772.32	772.06	772.02	17+00	18+00	19+00	20+00	21+00	22+00	23+00	24+00	25+00
--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	-------	-------	-------	-------	-------	-------	-------	-------	-------

FILE NAME = D570898-sht-plnprf\_midwestct.dgn

USER NAME = bemery  
 DESIGNED - CWW  
 DRAWN - CWW  
 CHECKED - BJE  
 PLOT DATE = 5/6/2019 - 2:49:42 PM


REVISIED -  
 REVISIED -  
 REVISIED -  
 REVISIED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**PLAN & PROFILE  
 MIDWEST COURT**




SCALE: 1" = 50' SHEET OF SHEETS STA. 17+00.00 TO STA. 25+00.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	39
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	



LEGEND	
	TYPE A SAWED TRANSVERSE JOINT
	TYPE E SAWED LONGITUDINAL JOINT
	TYPE F LONGITUDINAL CONSTRUCTION JOINT
	TYPE A OR E JOINT

NOTE: SEE CITY OF CHAMPAIGN PCC PAVEMENT DETAILS AND JOINT LAYOUT FOR MORE INFORMATION



- NOTES:
1. ALL TRANSVERSE JOINTS ARE SPACED AT 15' UNLESS OTHERWISE NOTED.
  2. ELEVATIONS SHOWN AT CURB AND GUTTER LOCATIONS ARE EDGE OF PAVEMENT ELEVATIONS.


FILE NAME = D570898-sht-jointing.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -
		DRAWN - CWW	REVISED -
		CHECKED - BJE	REVISED -
		DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>CUL-DE-SAC DETAIL MIDWEST COURT</b>	
SCALE: 1" = 10'	SHEET OF SHEETS STA. 19+82.96 TO STA. 22+55.00

F.A.I. RTE. 57	SECTION (10-34HB)BR-1	COUNTY CHAMPAIGN	TOTAL SHEETS 147	SHEET NO. 40
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	





FILE NAME =  
D570898-sht-grading.dgn  
Default

USER NAME = bemory  
PLOT SCALE = 100.0000' / in.  
PLOT DATE = 6/4/2019 - 10:12:14 AM

DESIGNED - MKK  
DRAWN - MKK  
CHECKED - BJE  
DATE - 04/16/2019


REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**GRADING PLAN  
U.S. 150 OVER I-57**

SCALE: 1" = 50'    SHEET    OF    SHEETS    STA. 150+00.00    TO    STA. 164+00.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34)BR-1	CHAMPAIGN	147	41
			CONTRACT NO. 70B98	
ILLINOIS FED. AID PROJECT				



FILE NAME =  
D570B98-sht-grading.dgn

USER NAME = bemery  
PLOT SCALE = 100.0000' / 1" =  
PLOT DATE = 5/6/2019 - 2:50:28 PM

DESIGNED - CWW  
DRAWN - CWW  
CHECKED - BJE  
DATE - 04/16/2019

REVISED -  
REVISED -  
REVISED -  
REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**GRADING PLAN  
MIDWEST COURT**

SCALE: 1" = 50' SHEET OF SHEETS STA. 13+00.00 TO STA. 25+08.35

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34H)BR-1	CHAMPAIGN	147	42
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	





**PRE-STAGE A**

**TRAFFIC**  
U.S. 150 - MAINTAIN TRAFFIC IN EXISTING LANE CONFIGURATIONS. UTILIZE HIGHWAY STANDARD 701201 AS NEEDED TO WIDEN EXISTING SHOULDER.

I-57 - MAINTAIN TRAFFIC IN EXISTING LANE CONFIGURATIONS.

**ROADWAY CONSTRUCTION**  
U.S. 150 - WIDEN EXISTING SHOULDER.

I-57 - PLACE TEMPORARY CONCRETE BARRIER. SEE TRAFFIC CONTROL AND PROTECTION (SPECIAL) DETAIL SHEET AND SPECIAL PROVISIONS.

**STAGE GENERAL NOTES**  
TWO-WAY TRAFFIC SHALL REMAIN OPEN DURING NON-WORKING HOURS.

NO OPEN HOLES SHALL BE ALLOWED OVERNIGHT.

PRIMARY IDOT STANDARDS THIS STAGE  
(SEE SPECIAL PROVISIONS FOR ADDITIONAL APPLICABLE STANDARDS)  
701001, 701006, 701400, 701401, 701501, 701901

LEGEND	
	WORK ZONE
	DIRECTION OF TRAFFIC FLOW
	TEMPORARY CONCRETE BARRIER WALL
	VERTICAL PANEL, POST MOUNTED
	TYPE II BARRICADE WITH STEADY BURNING LIGHT
	DRUM WITH STEADY BURNING LIGHT
	CONE, DRUM, OR BARRICADE


FILE NAME = D570898-sh1-MOT-PreStageA.dgn	USER NAME = bemory	DESIGNED - BJE	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - BJE	REVISED -
	PLOT DATE = 5/6/2019 - 2:51:13 PM	CHECKED - KRC	REVISED -
		DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**MAINTENANCE OF TRAFFIC PLAN  
U.S. 150 OVER I-57 PRE-STAGE A**

SCALE: N.T.S. SHEET OF SHEETS STA. TO STA.


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	44
CONTRACT NO. 70B98				
ILLINOIS FED. AID PROJECT				




FILE NAME = D570B9B-sh1-MOT-PreStageA.dgn	USER NAME = bemery	DESIGNED - BJE	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>MAINTENANCE OF TRAFFIC PLAN U.S. 150 OVER I-57 PRE-STAGE A</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - BJE	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	147	45
	PLOT DATE = 6/4/2019 - 9:36:30 AM	CHECKED - KRC	REVISED -									CHAMPAIGN	CONTRACT NO. 70B98
		DATE - 04/16/2019	REVISED -									ILLINOIS	FED. AID PROJECT







**ROAD CLOSED**  
R11-2



LEGEND	
	WORK ZONE
	WORK FROM PREVIOUS STAGES
	MILL/OVERLAY
	TEMPORARY RAMP
	TRAFFIC SIGNAL
	TEMPORARY CONCRETE BARRIER WALL
	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3
	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3
	DRUM WITH STEADY BURNING LIGHT
	TYPE II BARRICADE WITH STEADY BURNING LIGHT
	TYPE III BARRICADE WITH FLASHING LIGHTS
	DIRECTION OF TRAFFIC FLOW


FILE NAME = D570B98-sht-MOT-Stage1.dgn	USER NAME = bemory	DESIGNED - BJE	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - BJE	REVISED -
	PLOT DATE = 5/6/2019 - 2:51:36 PM	CHECKED - KRC	REVISED -
		DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>MAINTENANCE OF TRAFFIC PLAN MIDWEST COURT STAGE 1</b>			
SCALE: 1" = 50'	SHEET	OF	SHEETS
	STA. 10+00.00	TO	STA. 25+00.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	48
ILLINOIS FED. AID PROJECT			CONTRACT NO. 70B98	





**STAGE 2 TYPICAL #1 - U.S. 150**  
SEE PROPOSED TYPICAL SECTION SHEETS FOR MORE DETAIL

**STAGE 2**

**TRAFFIC**  
U.S. 150 - SHIFT TRAFFIC SOUTH AND PROVIDE ONE 12' TRAVEL LANE, UTILIZING ALTERNATING ONE-WAY OPERATIONS. TRAFFIC CONTROL DEVICES NOT SHOWN IN THESE PLANS SHALL FOLLOW HIGHWAY STANDARD 701321.

CARDINAL ROAD - LOCAL ROAD CLOSURE. SEE DETOUR PLANS FOR SIGNING. SHALL FOLLOW DISTRICT 5 DETAIL 70200000.

**ROADWAY CONSTRUCTION**  
U.S. 150 - REMOVE EXISTING WESTBOUND PAVEMENT AND CONSTRUCT PROPOSED WESTBOUND EMBANKMENT AND PAVEMENT. SURFACE COURSE TO BE CONSTRUCTED IN STAGE 3.

SEE PROPOSED TYPICAL SECTION SHEETS FOR DETAILED INFORMATION.

**STAGE GENERAL NOTES**  
SEE PAVEMENT PROFILE TRANSITIONS DETAIL.





SEE STRUCTURE PLANS FOR BRIDGE STAGING.

USE I-57 DETOUR PLANS FOR TRAFFIC DURING BEAM REMOVAL AND REPLACEMENT OPERATIONS.

PRIMARY IDOT STANDARDS THIS STAGE (SEE SPECIAL PROVISIONS FOR ADDITIONAL APPLICABLE STANDARDS) 701001, 701006, 701011, 701206, 701301, 701301, 701321, 701400, 701401, 701411, 701501, 701901, D5-70200000

LEGEND	
	WORK ZONE
	DIRECTION OF TRAFFIC FLOW
	TEMPORARY CONCRETE BARRIER WALL
	VERTICAL PANEL, POST MOUNTED
	TYPE II BARRICADE WITH STEADY BURNING LIGHT
	DRUM WITH STEADY BURNING LIGHT
	CONE, DRUM, OR BARRICADE

FILE NAME = D570B98-sht-MOT-Stage2.dgn	USER NAME = bemory	DESIGNED - BJE	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>MAINTENANCE OF TRAFFIC PLAN U.S. 150 OVER I-57 STAGE 2</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000' / 1in.	CHECKED - KRC	REVISED -					57	(10-34HB)BR-1	CHAMPAIGN	147	49
Default	PLOT DATE = 5/6/2019 - 2:51:58 PM	DATE - 04/16/2019	REVISED -	SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 70B98	



**LEGEND**

	WORK ZONE		TEMPORARY CONCRETE BARRIER WALL
	WORK FROM PREVIOUS STAGES		IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3
	MILL/OVERLAY		IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3
	TEMPORARY RAMP		DRUM WITH STEADY BURNING LIGHT
	TRAFFIC SIGNAL		TYPE II BARRICADE WITH STEADY BURNING LIGHT
	SHOULDER RUMBLE STRIP REMOVAL		TYPE III BARRICADE WITH FLASHING LIGHTS
			DIRECTION OF TRAFFIC FLOW

FILE NAME = D570898-sht-MOT-Stage2.dgn  
 Default

USER NAME = bemery  
 PLOT SCALE = 100.0000' / 1" = 100'  
 PLOT DATE = 6/4/2019 - 9:40:55 AM

DESIGNED - BJE  
 DRAWN - BJE  
 CHECKED - KRC  
 DATE - 04/16/2019


REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**


**MAINTENANCE OF TRAFFIC PLAN  
 U.S. 150 OVER I-57 STAGE 2**  
 SCALE: 1" = 50'  
 SHEET OF SHEETS STA. 147+00.00 TO STA. 177+00.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34H)BR-1	CHAMPAIGN	147	50
				CONTRACT NO. 70B98
ILLINOIS FED. AID PROJECT				





NOTES:  
 FOR BRIDGE CLOSURE POUR UTILIZE TRAFFIC CONTROL SETUP FROM STAGE 2.  
 TRAFFIC CONTROL AS SHOWN IN STAGE 3 PLAN REPRESENTS ROADWAY SURFACE COURSE CONSTRUCTION AND SHORT TERM PAVEMENT MARKINGS.  
 SEE STRUCTURE PLANS FOR STAGE 3 BRIDGE CLOSURE DETAILS.



**LEGEND**

	WORK ZONE		TEMPORARY CONCRETE BARRIER WALL
	WORK FROM PREVIOUS STAGES		IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3
	MILL/OVERLAY		IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3
	TEMPORARY RAMP		DRUM WITH STEADY BURNING LIGHT
	TRAFFIC SIGNAL		TYPE II BARRICADE WITH STEADY BURNING LIGHT
			TYPE III BARRICADE WITH FLASHING LIGHTS
			DIRECTION OF TRAFFIC FLOW


FILE NAME = D570898-sht-MOT-Stage3.dgn	USER NAME = bemery	DESIGNED - BJE	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - BJE	REVISED -
	PLOT DATE = 5/6/2019 - 2:52:21 PM	CHECKED - KRC	REVISED -
		DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**MAINTENANCE OF TRAFFIC PLAN  
 U.S. 150 OVER I-57 STAGE 3**

SCALE: 1" = 50' SHEET OF SHEETS STA. 147+00.00 TO STA. 177+00.00


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34H)BR-1	CHAMPAIGN	147	52
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	




**NOTES**

1. PRIOR TO INSTALLING POST MOUNTED SIGNS, THE CONTRACTOR SHALL CONTACT J.U.L.I.E.
2. ALL SIGN MESSAGES AND SIZES SHALL BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.
3. THE CONTRACTOR SHALL FURNISH THE SIGNS AND POSTS AND ERECT THE SIGNS AT THE LOCATIONS DIRECTED BY THE ENGINEER. ALL THE SIGNS SHALL BE POST MOUNTED.
4. THE DETOUR AND SIGNAGE IS REQUIRED TO REMAIN IN PLACE FOR THE DURATION OF CONSTRUCTION UNTIL U.S. 150 IS OPEN TO TWO-WAY TRAFFIC.
5. ALL SIGNING SHALL BE FURNISHED BY THE CONTRACTOR, ERECTED AT THE LOCATIONS SHOWN WITHIN THE CONTRACT PLANS, MAINTAINED, AND REMOVED BY THE CONTRACTOR UNLESS OTHERWISE NOTED IN THE PLANS. ALL WORK ASSOCIATED WITH THE FURNISHING, ERECTING, MAINTAINING, AND REMOVAL OF DETOUR SIGNING WILL BE PAID FOR AS DETOUR SIGNING, L SUM.
6. ANY SIGN THAT IS COVERED OR CHANGED SHALL BE DONE IN A MANNER WHICH DOES NOT DAMAGE ANY SIGNS OR POSTS. ANY SIGN OR POST WHICH THE ENGINEER DETERMINES HAS BEEN DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED OR REPLACED AT THE CONTRACTOR'S OWN EXPENSE.
7. THE CHANGEABLE MESSAGE SIGNS SHALL STATE THE DAY THE ROAD CLOSURE WILL BEGIN AND SHALL BE LOCATED AS DIRECTED BY THE ENGINEER. ONCE CONSTRUCTION BEGINS THE SIGNS SHALL STATE CARDINAL ROAD CLOSED FOLLOW MARKED DETOUR. THE EXACT MESSAGES SHALL BE APPROVED BY THE ENGINEER. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE OF CAL DA FOR CHANGEABLE MESSAGE SIGN.
8. CONTRACTOR SHALL NOTIFY IDOT DISTRICT 5 OPERATIONS 21 DAYS IN ADVANCE OF ROAD CLOSURE.
9. ALL CARDINAL ROAD SIGNS (DETOUR) SHALL BE ORANGE BACKGROUND WITH 6" BLACK LETTERS.
10. SEE DISTRICT 5 DETAIL 70200000 AND STAGED MAINTENANCE OF TRAFFIC PLAN SHEETS FOR ADDITIONAL INFORMATION.



**LEGEND**



**SIGN DETAIL**




FILE NAME = D570B98-sht-detour-CardinalRd.dgn	USER NAME = bemory	DESIGNED - DRAWN -	CWW CWW	REVISED - REVISED -		<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>DETOUR PLAN CARDINAL ROAD</b>		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.					
Default	PLOT SCALE = 400.0000' / in.	CHECKED -	BJE	REVISED -			SCALE: 1" = 200'	SHEET	OF	SHEETS	STA.	TO	STA.	57	(10-34H)BR-1	CHAMPAIGN	147	53
	PLOT DATE = 5/6/2019 - 2:52:42 PM	DATE -	04/16/2019	REVISED -														




**NOTES**

- PRIOR TO INSTALLING POST MOUNTED SIGNS, THE CONTRACTOR SHALL CONTACT J.U.L.I.E.
- ALL SIGN MESSAGES AND SIZES SHALL BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.
- THE CONTRACTOR SHALL FURNISH THE SIGNS AND POSTS AND ERECT THE SIGNS AT THE LOCATIONS DIRECTED BY THE ENGINEER. ALL THE SIGNS SHALL BE POST MOUNTED.
- ALL SIGNING SHALL BE FURNISHED BY THE CONTRACTOR, ERECTED AT THE LOCATIONS SHOWN WITHIN THE CONTRACT PLANS, MAINTAINED, AND REMOVED BY THE CONTRACTOR UNLESS OTHERWISE NOTED IN THE PLANS. ALL WORK ASSOCIATED WITH THE FURNISHING, ERECTING, MAINTAINING, AND REMOVAL OF DETOUR SIGNING WILL BE PAID FOR AS DETOUR SIGNING, L SUM.
- ANY SIGN THAT IS COVERED OR CHANGED SHALL BE DONE IN A MANNER WHICH DOES NOT DAMAGE ANY SIGNS OR POSTS. ANY SIGN OR POST WHICH THE ENGINEER DETERMINES HAS BEEN DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED OR REPLACED AT THE CONTRACTOR'S OWN EXPENSE.
- THE CHANGEABLE MESSAGE SIGNS SHALL STATE THE DAY THE ROAD CLOSURE WILL BEGIN AND SHALL BE LOCATED AS DIRECTED BY THE ENGINEER. ONCE CONSTRUCTION BEGINS THE SIGNS SHALL STATE I-57 CLOSED FOLLOW MARKED DETOUR. THE EXACT MESSAGES SHALL BE APPROVED BY THE ENGINEER. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CAL DA FOR CHANGEABLE MESSAGE SIGN.
- CONTRACTOR SHALL NOTIFY IDOT DISTRICT 5 OPERATIONS 21 DAYS IN ADVANCE OF ROAD CLOSURE.
- I-57 WILL REMAIN OPEN EXCEPT FOR REMOVAL AND SETTING OF BRIDGE BEAMS ON U.S. 150. THE REMOVAL AND SETTING OF BRIDGE BEAMS WILL BE DONE AT NIGHT AS DESCRIBED IN THE SPECIAL PROVISIONS.
- SEE DISTRICT 5 DETAIL X7011005, STANDARD 701451, AND STAGED MAINTENANCE OF TRAFFIC PLAN SHEETS FOR ADDITIONAL INFORMATION.

**SIGN DETAIL**



**LEGEND**



NOT TO SCALE



FILE NAME = D570898-sht-detour-157.dgn	USER NAME = bemory	DESIGNED - CWW	REVISED -
		DRAWN - CWW	REVISED -
		CHECKED - BJE	REVISED -
		DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**DETOUR PLAN  
I-57**

SCALE: N.T.S. SHEET OF SHEETS STA. TO STA.

F.A.I. RTE. 57	SECTION (10-34HB)BR-1	COUNTY CHAMPAIGN	TOTAL SHEETS 147	SHEET NO. 54
CONTRACT NO. 70B98				
ILLINOIS FED. AID PROJECT				



**LEGEND**

→ DETOUR TRAFFIC TRAVEL ROUTE

▨ PROPOSED PROJECT


**SIGN DETAIL**

**(A) NORTH**  
 M4-8 (24 X 12)(0)  
 M3-4 (24X12)  
 M1-1 (24 X 24)  
 INTERSTATE 57  
 WHITE ON BLUE

**(B) SOUTH**  
 M4-8 (24 X 12)(0)  
 M3-4 (24X12)  
 M1-1 (24 X 24)  
 INTERSTATE 57

SEE PREVIOUS SHEET ①

SEE PREVIOUS SHEET ③



FILE NAME = D570898-sht-detour-157.dgn	USER NAME = bemory	DESIGNED - CWW	REVISED -
Default	PLOT SCALE = 600.0000' / in.	DRAWN - CWW	REVISED -
	PLOT DATE = 5/6/2019 - 2:53:04 PM	CHECKED - BJE	REVISED -
		DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**DETOUR PLAN  
I-57**

SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.
---------------	-------	----	--------	------	----	------

F.A.I. RTE. 57	SECTION (10-34HB)BR-1	COUNTY CHAMPAIGN	TOTAL SHEETS 147	SHEET NO. 55
CONTRACT NO. 70B98				
ILLINOIS FED. AID PROJECT				


# INTERSTATE DETOUR USING ENTRANCE AND EXIT RAMP

A CHANGEABLE MESSAGE SIGN SHALL BE USED IN ADVANCE OF SIGNING TO WARN OF CLOSURE


CMS	ROAD CLOSED	2-3 MILES AHEAD	FOLLOW DETOUR SIGNS
-----	-------------	-----------------	---------------------

DIRECTIONAL BARRICADES WITH STEADY BURNING LIGHTS AT 50' (15 m) CTS. IN TAPER. DRUMS WITH STEADY BURNING LIGHTS IN TANGENT (BETWEEN TAPERS) AT 100' (30 m) CTS.


FOR OFF PEAK CLOSURES LESS THAN 24 HOURS, THE TANGENT SECTION MAY BE OMITTED BY APPROVAL OF THE ENGINEER.



SYMBOLS	
	ARROW BOARD
	SIGN
	DRUM W/STEADY BURNING LIGHT
	TYPE III BARRICADE
	DIRECTIONAL BARRICADE W/STEADY BURNING LIGHT
	LIGHTED FLAGGER STATIONS



CROSSROAD CLOSED TO TRAFFIC



CROSSROAD OPEN TO TRAFFIC

Note: All dimensions are in INCHES (millimeters) unless otherwise shown.

## DISTRICT 5 DETAIL NO. X7011005

FILE NAME = D570B98-sht-detour-157-details.dgn

USER NAME = bemory  
 PLOT SCALE = 48.0000' / in.  
 PLOT DATE = 5/6/2019 - 2:53:26 PM

DESIGNED -	REVISD - 12/06
DRAWN -	REVISD - 1/10
CHECKED -	REVISD -
DATE -	REVISD -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

### TRAFFIC CONTROL & PROTECTION FOR TEMPORARY DETOUR

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	56
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	



### SIGN DETAIL A

Panel Style: tab1.tbl  
M.U.T.C.D.: 2009 Edition

**SIGN DETAIL A**  
N.T.S.

SIGN NUMBER	I-57 NB Ahead SB Right
WIDTH x HGHT.	6'-0" x 7'-0"
BORDER WIDTH	1"
CORNER RADIUS	3"
MOUNTING	Temp. Ground
BACKGROUND	TYPE: Reflective COLOR: Green
LEGEND/BORDER	TYPE: Reflective COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT
MI_1	0	21.0	71.21	36	36

Panel Style: Peoria.tbl  
M.U.T.C.D.: 2009 Edition

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)										LENGTH	SERIESIZE
W	E	S	T								E(M)
74.4	97.2	110.4	123.6							60.0	18,15
P	e	o	r	i	a						E(M)
34.8	54.0	72	91.2	105.6	116.2					94.7	20,15
I	/	4	M	I	L	E					E(M)
42.4	47.57	60.7	81.9	98.49	101.6	112.5				79.0	12
E	X	I	T	2	3	7	B				E(M)
16.3	25.2	35.9	39.36	79.87	76.1	89.9	109.7			30.5, 59.7	10,15

### SIGN DETAIL B

Panel Style: tab1.tbl  
M.U.T.C.D.: 2009 Edition

**SIGN DETAIL B**  
N.T.S.

SIGN NUMBER	I-57 SB Ahead NB Right
WIDTH x HGHT.	6'-0" x 7'-0"
BORDER WIDTH	1"
CORNER RADIUS	3"
MOUNTING	Temp. Ground
BACKGROUND	TYPE: Reflective COLOR: Green
LEGEND/BORDER	TYPE: Reflective COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT
AR-TYPE A	45	199.3	66.4	34.9	22.1
MI_1	0	63	57.72	36	36

Panel Style: Peoria.tbl  
M.U.T.C.D.: 2009 Edition

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)										LENGTH	SERIESIZE			
E	A	S	T								E(M)			
116.7	131.9	148.8	11.3							45.9	18,15			
I	n	d	i	a	n	a	p	o	l	i	s	E(M)		
21.5	32.3	51.7	72.9	83.1	104.3	123.7	144.9	162.5	182.3	194.3	204.13	182.6	20,15	
E	X	I	T	2	3	7	A						E(M)	
14.7	23.9	34.3	37.8	60.3	74.5	88.3	108.0						30.5, 63	10,15

### SIGN DETAILS

SIGN DESCRIPTION	SIGN DETAIL LETTER	SIGN STANDARD NUMBER	LOCATION		MOUNTING TYPE
			STATION	LT/RT *	
<b>CHAMPAIGN COUNTY</b>					
<b>PRE-STAGE A</b>					
<b>I-57</b>					
** ADVANCE GUIDE: I-74 WEST, EXT 237B	A	-	580+95.00	124.5' RT	PERMANENT
** ADVANCE GUIDE: I-74 EAST, EXT 237A	B	-	580+95.00	143.0' RT	PERMANENT
** ADVISORY RAMP SPEED 30 MPH	C ***	W13-3	580+95.00	78.0' RT	PERMANENT

NOTES:  
 \* LT/RT OFFSETS ARE GIVEN WITH RESPECT TO THE DIRECTION OF TRAFFIC. OFFSETS ARE TO THE CENTER OF THE SIGN PANELS.  
 \*\* PRIOR TO THE REMOVAL OF EXISTING ADVANCE GUIDE SIGNS, THE CONTRACTOR SHALL ENSURE THAT THE SIMILAR PROPOSED ADVANCE GUIDE SIGNS HAVE BEEN INSTALLED OR ARE INSTALLED DURING THE SAME OPERATION AS THE REMOVAL.  
 \*\*\* EXISTING SIGN TO BE REMOVED AND RELOCATED

FILE NAME = D570898-sht-MOT-signs.dgn	USER NAME = bemery	DESIGNED - BJE	REVISED -
		DRAWN - BJE	REVISED -
		CHECKED - CWW	REVISED -
		DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SIGN PANEL DETAILS**

SCALE: N.T.S. SHEET OF SHEETS STA. TO STA.

F.A.I. RE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	57
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	






**TRAFFIC CONTROL AND PROTECTION (SPECIAL)**

NOTES:  
UTILIZE TRAFFIC CONTROL STANDARD 701401 FOR THE PLACEMENT OF TEMPORARY CONCRETE BARRIER, (SEE SPECIAL PROVISIONS).


TAPERED PORTION OF THE TEMPORARY CONCRETE BARRIER SHALL BE PLACED USING A 1:12 TAPER RATE AS SHOWN ON THE PLANS.

VERTICAL PANELS WITH MONODIRECTIONAL STEADY BURNING TYPE A LIGHTS SHALL BE MOUNTED ON THE TAPERED PORTIONS OF THE TEMPORARY CONCRETE BARRIER AT 25' CENTERS, FOR THE LAST 100' OF TAPER PRIOR TO THE TANGENT.

BARRIER WALL REFLECTORS, TYPE C, SHALL BE MOUNTED ON THE TANGENT PORTIONS OF THE TEMPORARY CONCRETE BARRIER AS SHOWN ON THE BARRIER WALL REFLECTORS DETAIL, AND INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION (SPECIAL).



**BARRIER WALL REFLECTORS**



**LEGEND**

- TEMPORARY CONCRETE BARRIER
- IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3
- IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3
- SIGN
- MONODIRECTIONAL REFLECTOR, TYPE C
- MONODIRECTIONAL BURNING LIGHTS AND VERTICAL PANELS
- DIRECTION OF TRAFFIC FLOW



FILE NAME = D570B98-sht-MOT-Special.dgn	USER NAME = bemory	DESIGNED - BJE	REVISED -
		DRAWN - BJE	REVISED -
		CHECKED - XXX	REVISED -
		DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**TRAFFIC CONTROL AND PROTECTION (SPECIAL)**

SCALE: 1" = 50' SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	58
				CONTRACT NO. 70B98
ILLINOIS FED. AID PROJECT				



**NOTES**

ALL TRAFFIC CONTROL SHOWN ON THIS SHEET SHALL MEET THE REQUIREMENTS SHOWN ON DISTRICT 5 WIDTH RESTRICTION SIGNING DETAIL NO. X7200201 AND SHALL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR WIDTH RESTRICTION SIGNING.


FILE NAME = D570B98-sht-MOT-details.dgn	USER NAME = bemory	DESIGNED - BJE	REVISED -
		DRAWN - BJE	REVISED -
	PLOT SCALE = 40.0000' / in.	CHECKED - CWW	REVISED -
Default	PLOT DATE = 5/6/2019 - 2:54:32 PM	DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**WIDTH RESTRICTION SIGNING DETAIL**

SCALE: N.T.S. SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	59
ILLINOIS FED. AID PROJECT			CONTRACT NO. 70B98	




W12-I102(O) - 48"x48" (1200x1200)


STAGE	X' - X''
1	12' - 6"
2	12' - 6"
3	12' - 6"

SIGN (A) 4 SIGNS - W12-2(O) - 48"x48" (1200x1200) ARE TO BE PLACED AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER.

SIGN (B) 2 SIGNS - (SIGN PANEL, TYPE II) AS SHOWN ARE TO BE PLACED AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER.



SIGN PANEL, TYPE II



W12-I103(O) - 48"x48" (1200x1200)  
"D" LETTERS/NUMBERS

STAGE	X' - X''
1	12' - 6"
2	12' - 6"
3	12' - 6"

GENERAL NOTES

1. ALL TRAFFIC CONTROL DEVICES SHALL BE FURNISHED, ERECTED AND MAINTAINED BY THE CONTRACTOR.
2. ALL (B) SIGNS SHALL HAVE FLAGS INSTALLED UNLESS OTHERWISE DIRECTED.
3. LOCATIONS OF TRAFFIC CONTROL DEVICES MAY BE ADJUSTED BY THE ENGINEER.
4. ALL TRAFFIC CONTROL SHOWN ON THIS SHEET SHALL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR WIDTH RESTRICTION SIGNING.
5. ALL SIGNS SHALL BE POST MOUNTED UNLESS OTHERWISE DIRECTED.
6. ALL SIGNS SHOWN ORANGE (O) SHALL BE FLUORESCENT ORANGE.
7. ALL SIGNS SHOWN SHALL CONSIST OF THE CURRENT RETROREFLECTIVE SHEETING REQUIREMENTS AS OUTLINED IN SECTION 1106.01 OF THE STANDARD SPECIFICATIONS BOOK.

Note: All dimensions are in INCHES (millimeters) unless otherwise shown.

FILE NAME = D570B98-sht-MOT-details.dgn	USER NAME = bemory	DESIGNED - BJE	REVISED - 03/11 - KJT
		DRAWN - BJE	REVISED - 05/08
		CHECKED - CWW	REVISED - 10/08 - KJT
		DATE - 04/16/2019	REVISED - 7/09 - KJT

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

WIDTH RESTRICTION SIGNING

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.


DISTRICT 5 DETAIL NO. X7200201

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	60
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 70B98	

# ROAD CLOSURE

# SIDEROAD / STREET CLOSURE


SYMBOLS	
	TYPE III BARRICADE (SEE NOTE 1)
	FLASHING AMBER LIGHT (TYPE A)



## GENERAL NOTES

- TYPE III BARRICADES SHALL BE AS SHOWN ON STANDARD 701901 "TYPICAL APPLICATIONS OF TYPE III BARRICADES CLOSING A ROAD". EACH TYPE III BARRICADE SHALL HAVE TWO FLASHING AMBER LIGHTS MOUNTED ABOVE IT.
- IF THE ROAD IS OPEN TO LOCAL TRAFFIC OR EXCEEDS 1000' (300 m), ANOTHER SET OF TYPE III BARRICADES, EQUIPPED AS IN NOTE 1 ABOVE, SHALL BE PLACED AT EACH END OF THE WORK AREA.
- WHEN A STOP CONDITION EXISTS, NO SIGNS ARE REQUIRED IN ADVANCE OF THE "STOP" SIGN WHEN THE ROAD IS CLOSED WITHIN 100' (30 m) OF THE INTERSECTION.
- STANDARD 701901 SHALL APPLY FOR THE PLACEMENT & DESIGN OF TYPE III BARRICADES.
- IF A TYPE III BARRICADE WITH AN ATTACHED SIGN PANEL WHICH MEETS NCHRP 350 IS NOT AVAILABLE, THE SIGNS MAY BE MOUNTED ON AN NCHRP 350 TEMPORARY SIGN SUPPORT DIRECTLY IN FRONT OF THE BARRICADE.
- REFLECTORIZED STRIPING SHALL APPEAR ON BOTH SIDES OF THE TYPE III BARRICADES IF ROAD IS OPEN TO LOCAL TRAFFIC.
- ALL SIGNS SHALL BE POST MOUNTED IF THE CLOSURE TIME EXCEEDS FOUR DAYS.
- A MINIMUM OF TWO FLASHING LIGHTS SHALL BE USED AT NIGHT ON EACH APPROACH IN ADVANCE OF THE WORK AREA. FLASHING LIGHTS SHALL BE INSTALLED ABOVE THE FIRST TWO SIGNS IN THE SERIES.
- LONGITUDINAL DIMENSIONS MAY BE ADJUSTED SLIGHTLY TO FIT FIELD CONDITIONS.
- FORMS BT. 725 AND BT. 726 ARE REQUIRED.
- WHEN A SIDEROAD INTERSECTS THE HIGHWAY ON WHICH WORK IS BEING PERFORMED, ADDITIONAL TRAFFIC DEVICES SHALL BE ERECTED AND PROVIDED AS DIRECTED BY THE ENGINEER.
- AN ADDITIONAL SIGN MAY BE REQUIRED AT A MAJOR INTERSECTING ROAD IN ADVANCE OF THE CLOSURE. THE ADDITIONAL SIGN SHALL GIVE THE DISTANCE TO THE BARRICADE IN MILES OR FRACTIONS OF A MILE.

SYMBOLS	
	TYPE III BARRICADE (SEE NOTE)
	FLASHING LIGHT
	FLAGGER WITH TRAFFIC CONTROL SIGN (WHILE WORK IS BEING PERFORMED)
	CONES (DAYLIGHT HOURS ONLY), DRUM, TYPE I OR TYPE II BARRICADE
	WORK AREA
	TRAFFIC FLOW



## GENERAL NOTES

- TYPE III BARRICADES SHALL BE AS SHOWN ON "TYPICAL APPLICATIONS OF TYPE III BARRICADES CLOSING A ROAD". EACH TYPE III BARRICADE SHALL HAVE TWO FLASHING AMBER LIGHTS MOUNTED ABOVE IT.
- WHERE A STOP CONDITION EXISTS, AS SHOWN ABOVE, WARNING SIGNS MAY BE OMITTED IN ADVANCE OF THE "STOP" SIGN.
- STANDARD 701901 SHALL APPLY FOR THE PLACEMENT & MANUFACTURE OF TYPE III BARRICADES.
- ALL SIGNS SHALL BE POST MOUNTED IF THE CLOSURE TIME EXCEEDS FOUR DAYS.
- ONE FLASHING LIGHT IS REQUIRED ABOVE EACH ADVANCE WARNING SIGN DURING HOURS OF DARKNESS.
- LONGITUDINAL DIMENSIONS MAY BE ADJUSTED SLIGHTLY TO FIT FIELD CONDITIONS.
- FORMS BT 725 AND BT 726 ARE REQUIRED.
- THE MAINLINE ROUTE TEMPORARY TRAFFIC CONTROL SHALL BE IN ACCORDANCE WITH THE PLANS, SPECIAL PROVISIONS AND STANDARD SPECIFICATIONS.
- ALL FLAGGERS REQUIRED AT SIDE ROADS AND ENTRANCES REMAINING OPEN TO TRAFFIC AND/OR ADDITIONAL BARRICADES REQUIRED BY THE ENGINEER TO CLOSE SIDE ROADS AND ENTRANCES WILL BE PAID FOR ACCORDING TO ARTICLE 109.04.

Note: All dimensions are in INCHES (millimeters) unless otherwise shown.

## DISTRICT 5 DETAIL NO. 7020000


FILE NAME =	USER NAME = bemory	DESIGNED -	REVISED - 11/06
D570898-sh1-MOT-details.dgn		DRAWN -	REVISED - 12/07
	PLOT SCALE = 48.0000' / in.	CHECKED -	REVISED - 09/09 - KJT
	PLOT DATE = 5/6/2019 - 2:54:32 PM	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION


TRAFFIC CONTROL & PROTECTION DEVICES  
(ROAD & SIDEROAD/STREET CLOSURES)

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	61
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		CONTRACT NO. 70B98



**DETECTOR LOOPS**  
SEE SPECIAL PROVISIONS



**EMERGENCY VEHICLE PREEMPTION SEQUENCE**



**TEMPORARY TRAFFIC SIGNAL INSTALLATION DIAGRAM  
FOR EMERGENCY VEHICLE PREEMPTION**

SEE SPECIAL PROVISIONS  
AND STAGING DETAIL SHEETS

**LEGEND**

- ←● TEMPORARY BRIDGE TRAFFIC SIGNALS
- | CONFIRMATION BEACON
- ② DENOTES NUMBER OF CONDUCTORS


FILE NAME = D570B98-sht-MOT-details.dgn	USER NAME = bemory	DESIGNED - BJE	REVISED -
		DRAWN - BJE	REVISED -
		CHECKED - KRC	REVISED -
Default	PLOT DATE = 5/6/2019 - 2:54:33 PM	DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


<b>DETECTOR LOOP DETAILS CLEARLAKE BLVD &amp; TEMPORARY TRAFFIC SIGNAL INSTALLATION PREEMPTION DETAILS</b>			
SCALE: N.T.S.	SHEET	OF SHEETS	STA. TO STA.

F.A.I. RTE. 57	SECTION (10-34HB)BR-1	COUNTY CHAMPAIGN	TOTAL SHEETS 147	SHEET NO. 62
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	


PLAN	SURVEYED	DATE
NOTE BOOK	ALIGNED	BY
NO.	CHECKED	
	FILE NAME	



PROFILE	SURVEYED	DATE
GRADES CHECKED	NOTED	BY
STRUCTURE	NOTED	
NO.	NOTED	




FILE NAME = D570898-shd-drain.dgn	USER NAME = bemery	DESIGNED - MKK	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>DRAINAGE PLANS U.S. 150</b>	F.A.I. RTE. = 57	SECTION = (10-34H)BR-1	COUNTY = CHAMPAIGN	TOTAL SHEETS = 147	SHEET NO. = 63		
Default	PLOT SCALE = 100.0000' / in.	CHECKED - BJE	REVISED -			SCALE: 1" = 50'	SHEET OF SHEETS	STA. 150+00.00 TO STA. 164+00.00	CONTRACT NO. 70B98			
	PLOT DATE = 6/4/2019 - 9:31:27 AM	DATE - 04/16/2019	REVISED -			ILLINOIS FED. AID PROJECT						



SCALE IN FEET


PLAN	SURVEYED	DATE
	PLOTTED	
	ALIGNED	
	CHECKED	
	FILED	
	NO.	

PROFILE	SURVEYED	DATE
	PLOTTED	
	GRADES	
	CHECKED	
	STRUCTURE	
	NOTATIONS	
	CHKD	
	NO.	




STRUCTURE NO.	STATION	OFFSET	STRUCTURE	CASTING	RIM ELEVATION	BOTTOM ELEVATION
1	20+21.11	16.42' LT.	MH TY A 4'	TY3 F & G	778.13	770.27
2	20+21.11	16.42' RT.	MH TY A 4'	TY3 F & G	778.13	767.84
3	22+07.80	34.37' RT.	MH TY A 4'	TY3 F & G	773.41	768.91
4	22+38.58	65.85' LT.	MH TY A 4'	TY3 F & G	773.24	767.54
5	22+90.00	70.09' LT.	PRC FES 24"		773.41	767.38

PIPE NO.	SIZE/TYPE	LENGTH (FEET)	SLOPE (%)	US INVERT	DS INVERT
P1	18" STORM SEWER CLA A 2	30	1.00	770.27	769.98
P2	18" STORM SEWER CLA A 2	186	0.50	769.84	768.91
P3	24" STORM SEWER CLA A 2	103	0.30	767.84	767.54
P4	24" STORM SEWER CLA A 2	52	0.31	767.54	767.38



LEFT TRUNKLINE STORM SEWER PROFILE



RIGHT TRUNKLINE STORM SEWER PROFILE

FILE NAME = D570898-shd-drain.dgn

USER NAME = bemery	DESIGNED - CWW	REVISED -
	CHECKED - CWW	REVISED -
PLOT SCALE = 100.0000' / in.	DRAWN - BJE	REVISED -
PLOT DATE = 5/6/2019 - 2:54:56 PM	CHECKED - 04/16/2019	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION


DRAINAGE PLANS  
MIDWEST COURT

SCALE: 1" = 50' SHEET OF SHEETS STA. 16+00.00 TO STA. 25+08.35

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	64
CONTRACT NO. 70B98				


ILLINOIS FED. AID PROJECT





PLAN	SURVEYED	DATE
	PLOTTED	
	GRADES CHECKED	
	STRUCTURE NOTATIONS CHECKED	
	NOTE BOOK NO.	
	BY	




PROFILE	SURVEYED	DATE
	PLOTTED	
	GRADES CHECKED	
	STRUCTURE NOTATIONS CHECKED	
	NOTE BOOK NO.	
	BY	



FILE NAME =	USER NAME =	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>DRAINAGE PLANS</b> <b>FUTURE I-57 (FOR INFORMATION ONLY)</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
D570898-shd-drain.dgn	bemery	DRAWN -	REVISED -			57	(10-34HB)BR-1	CHAMPAIGN	147	65	
Default		CHECKED -	REVISED -			CONTRACT NO. 70B98		ILLINOIS FED. AID PROJECT			
		DATE -	REVISED -			SCALE: 1" = 50'	SHEET OF SHEETS	STA. 575+00.00 TO STA. 589+00.00			

PLAN	SURVEYED	DATE
	PLOTTED	
	ALIGNED	
	CHECKED	
	FILED	
NOTE BOOK NO.	CARD FILE NAME	



PROFILE	SURVEYED	DATE
	PLOTTED	
	GRADES CHECKED	
	STRUCTURE NOTATIONS CHECKED	
NOTE BOOK NO.	NOTATIS CHECKED	



FILE NAME = D570898-shd-drain.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>DRAINAGE PLANS</b> <b>FUTURE RAMP A (FOR INFORMATION ONLY)</b>	F.A.I. RTE. = 57	SECTION = (10-34H)BR-1	COUNTY = CHAMPAIGN	TOTAL SHEETS = 147	SHEET NO. = 66
Default	PLOT SCALE = 100.0000' / in.	CHECKED - BJE	REVISED -			SCALE: 1" = 50'	SHEET OF SHEETS	STA. 102+00.00 TO STA. 116+00.00	CONTRACT NO. 70B98	ILLINOIS FED. AID PROJECT
	PLOT DATE = 5/6/2019 - 2:54:57 PM	DATE = 04/16/2019	REVISED -							

PLAN	SURVEYED	BY	DATE
	PLOTTED		
	ALIGNED		
	CHECKED		
	FILED		
	NO.		

PROFILE	SURVEYED	BY	DATE
	PLOTTED		
	GRADES		
	CHECKED		
	STRUCTURE		
	NOTATIONS		
	CHKD		
	NO.		




FILE NAME =	USER NAME = bemory	DESIGNED -	CWW	REVISED -	
D570898-shd-drain.dgn		DRAWN -	CWW	REVISED -	
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	BJE	REVISED -	
	PLOT DATE = 5/6/2019 - 2:54:57 PM	DATE -	04/16/2019	REVISED -	

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**DRAINAGE PLANS  
FUTURE RAMP B (FOR INFORMATION ONLY)**


SCALE: 1" = 50' SHEET OF SHEETS STA. 233+00.00 TO STA. 247+00.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	67
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	



**LEGEND**

	PERIMETER EROSION BARRIER
	EROSION CONTROL BLANKET & SEEDING CLASS 2A
	HEAVY DUTY EROSION CONTROL BLANKET & SEEDING CLASS 2A
	INLET PROTECTION
	TEMPORARY DITCH CHECK
	SEEDING CLASS 2A & MULCH METHOD 2
	STONE RIPRAP CLASS A4



S.W. 010-8021  
 B.P. X 3' RC BOX  
 W. INV. = 763.50  
 E. INV. = 763.25

N. INV. = 769.67  
 S. INV. = 769.46


FILE NAME = D570898-sht-eros.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -
Default	PLOT SCALE = 100.0000' / in.	DRAWN - CWW	REVISED -
	PLOT DATE = 6/4/2019 - 9:32:54 AM	CHECKED - BJE	REVISED -
		DATE - 04/16/2019	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**








**EROSION CONTROL PLAN  
 U.S. 150**

SCALE: 1" = 50' SHEET OF SHEETS STA. 150+00.00 TO STA. 164+00.00

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34H)BR-1	CHAMPAIGN	147	68
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	



**LEGEND**

-  PERIMETER EROSION BARRIER
-  EROSION CONTROL BLANKET & SEEDING CLASS 2A
-  HEAVY DUTY EROSION CONTROL BLANKET & SEEDING CLASS 2A
-  INLET PROTECTION
-  TEMPORARY DITCH CHECK
-  SEEDING CLASS 2A & MULCH METHOD 2
-  STONE RIPRAP CLASS A4

NOTE:  
 PROVIDE INLET PROTECTION AROUND  
 EXISTING INLETS UNTIL PROPOSED STORM  
 SEWER SYSTEM IS FULLY FUNCTIONAL.



FILE NAME =  
 D570B98-sht-eros.dgn

USER NAME = bemery  
 PLOT SCALE = 100.0000' / 1in.  
 PLOT DATE = 5/6/2019 - 2:55:21 PM

DESIGNED - CWW  
 DRAWN - CWW  
 CHECKED - BJE  
 DATE - 04/16/2019

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**EROSION CONTROL PLAN  
 MIDWEST COURT**

SCALE: 1" = 50' SHEET OF SHEETS STA. 15+00.00 TO STA. 25+08.35

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	69
				CONTRACT NO. 70B98
ILLINOIS FED. AID PROJECT				

**NOTES:**

- 2-2" DIA. PVC TO BE EMBEDDED IN STRUCTURE FOR FUTURE USE.



**LIGHTING SUMMARY OF QUANTITIES**


PAY ITEM	DESCRIPTION	UNIT	QUANTITY
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	1,600
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	4

**LIGHTING LEGEND**

- JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, SIZE AS INDICATED ON PLAN

**HIGHWAY STANDARDS**

812001 RACEWAY EMBEDDED IN STRUCTURE



FILE NAME = D570898-sht-light.dgn	USER NAME = bemery	DESIGNED -	REVISED -
Default	PLOT SCALE = 200.0000' / in.	DRAWN -	REVISED -
	PLOT DATE = 6/4/2019 - 9:34:34 AM	CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**U.S. 150 OVER I-57  
LIGHTING PLAN**

SCALE: 1" = 100' SHEET OF SHEETS STA. TO STA.



F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34HB)BR-1	CHAMPAIGN	147	70
CONTRACT NO. 70B98				
ILLINOIS FED. AID PROJECT				

Bench Mark: Chisled "□" on the concrete foundation of the first light pole north of Bloomington Rd. (US 150) located on the west side of FAI 57, Sta. 583+73, 91' LT. Elev. 767.92.

Existing Structure: S.N. 010-0050 built 1964 as F.A.I. 57 (I-57) Section (10-34HB) at Station 582+50.00. Existing structure is a four-span rolled steel beam structure with open stub abutments on concrete piles and single hammerhead reinforced concrete piers supported on spread footings. In 2000, the structure was widened, the deck replaced, and the existing abutments and piers were widened as Section (10-34HB)BR. 258'-6" back-to-back abutments, 42'-7<sup>3</sup>/<sub>4</sub>" out-to-out deck. Structure to be removed and replaced using stage construction.

No Salvage

Note:  
Up to 1/4" may be ground off the bridge deck and the bridge approach slabs.



**APPROVED**  
For Structural Adequacy Only  
*[Signature]*  
Engineer of Bridges & Structures

\*Future roadway configurations of F.A.I 57, Ramp B and Ramp A shown.

----- In Elevation View, indicates portion of roadway configuration to be constructed in future contract.

**LOADING HL-93**  
Allow 50#/sq. ft. for future wearing surface.

**DESIGN SPECIFICATIONS**  
2014 AASHTO LRFD Bridge Design Specifications, 7th Edition with 2015 Interims.

**DESIGN STRESSES**

**FIELD UNITS**  
f'c = 3,500 psi  
f'c = 4,000 psi (superstructure concrete)  
fy = 60,000 psi (Reinforcement)  
fy = 50,000 psi (M270 Grade 50)


**SEISMIC DATA**  
Seismic Performance Zone (SPZ) = 1  
Design Spectral Acceleration at 1.0 sec. (S<sub>D1</sub>) = 0.135g  
Design Spectral Acceleration at 0.2 sec. (S<sub>D5</sub>) = 0.234g  
Soil Site Class = D

STATION 157+29.99  
BUILT BY  
STATE OF ILLINOIS  
F.A.P. RT. 719 - SEC. (10-34HB)BR-1  
LOADING HL-93  
STRUCTURE NO. 010-1050

**NAME PLATE**  
See Std. 515001

**F.A.P. 719 CURVE DATA**

PI STA. = 149+64.98  
Δ = 35° 19' 30" (LT)  
D = 3° 19' 43"  
R = 1,721.38'  
T = 548.12'  
L = 1,061.30'  
E = 85.16'  
e = 3.4%  
T.R. = 36'  
S.E. RUN = 82'  
P.C. STA. = 144+16.86  
P.T. STA. = 154+78.15  
S.E. Removed from Sta. 154+32.00 to Sta. 155+50.00



**LOCATION SKETCH**

**GENERAL PLAN & ELEVATION**  
U.S. 150 (BLOOMINGTON RD.) OVER F.A.I. 57  
F.A.P. RT 719 - SEC (10-34HB)BR-1  
CHAMPAIGN COUNTY  
STATION 157+29.99  
STRUCTURE NO. 010-1050

LICENSED STRUCTURAL ENGINEER  
GERALD B. ROTHERHAM  
081-005673  
STATE OF ILLINOIS  
*[Signature]*  
04/15/2019  
Expires 11/30/2020

FILE NAME * 0101050-7897-001-GPE.dgn	USER NAME *	DESIGNED - AAH	REVISED *	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
BACON   FARMER   WORKMAN ENGINEERING & TESTING, INC.		CHECKED - BWP	REVISED -		T19	110-34HB)BR-1	CHAMPAIGN	147	71
	PLDT SCALE *	DRAWN - BJV	REVISED -		CONTRACT NO. 70B98				
	PLDT DATE * 4/15/2019	CHECKED - BWP	REVISED -		ILLINOIS FED. AID PROJECT				

**INDEX OF SHEETS**

- 1 General Plan and Elevation
- 2 General Data
- 3 Stage Construction Details
- 4 Temporary Concrete Barrier for Stage Construction
- 5-9 Top of Slab Elevations
- 10 Top of West Approach Slab Elevations
- 11 Top of East Approach Slab Elevations
- 12 Superstructure
- 13-14 Superstructure Details
- 15 Diaphragm Details
- 16-20 Precast Bridge Approach Slab Details
- 21 Bridge Fence Railing, Parapet Mounted
- 22 Parapet Railing
- 23 Structural Steel
- 24 Structural Steel Details
- 25 Fixed Bearing Details
- 26 West Abutment
- 27 East Abutment
- 28 Wingwalls
- 29 Pier 1
- 30 HP Pile Details
- 31 Metal Shell Pile Details
- 32 Bar Splicer Assembly and Mechanical Splicer Details
- 33 Concrete Parapet Slipforming Option
- 34-36 Soil Boring Logs

**GENERAL NOTES**

Fasteners shall be ASTM A325 Type 1, hot dip galvanized bolts.  
 Bolts 7/8 in.  $\phi$ , holes 15/16 in.  $\phi$ , unless otherwise noted.  
 Calculated weight of Structural Steel: AASHTO M 270 Gr. 50 = 684,710 lbs.  
 AASHTO M 270 Gr. 36 = 41,820 lbs.

No field welding is permitted except as specified in the contract documents.  
 Reinforcement bars designated (E) shall be epoxy coated.  
 Bearing seat surfaces shall be constructed or adjusted to the designated elevations within a tolerance of 1/8 inch (0.01 ft.). Adjustment shall be made either by grinding the surface or by shimming the bearings.

All structural Steel shall be metallized. The metallized areas shall be painted with System 1. Exterior fascia and bottom of bottom flange areas of exterior girders shall be metallized and shop painted (System 3). Cost included in Furnishing and Erecting Structural Steel. See Special Provisions.


The embankment configuration shown shall be the minimum that must be placed and compacted prior to construction of the abutments.  
 The existing structural steel coating contains lead. The Contractor shall take appropriate precautions to deal with the presence of lead on this project.

When the deck pour is stopped for the day at one or more of the transverse bonded construction joints in the deck pouring sequence as shown, the next pour shall not be made until both of the following are met:

- 1) At least 72 hours shall have elapsed from the end of the previous pour.
- 2) The concrete strength shall have attained a minimum flexural strength of 675 psi or a minimum compressive strength of 4000 psi.

**TOTAL BILL OF MATERIAL**

ITEM	UNIT	SUPER	SUB	TOTAL
Removal of Existing Structures	Each			1
Protective Shield	Sq. Yd.	783		783
Structure Excavation	Cu. Yd.		419	419
Concrete Structures	Cu. Yd.		222.6	222.6
Concrete Superstructure	Cu. Yd.	623.9		623.9
Protective Coat	Sq. Yd.	2,552		2,552
Furnishing and Erecting Structural Steel	L. Sum	1		1
Stud Shear Connectors	Each	5,418		5,418
Reinforcement Bars, Epoxy Coated	Pound	161,860	29,390	191,250
Bar Splicers	Each	1,251	175	1,426
Mechanical Splicers	Each		128	128
Bridge Fence Railing	Foot	390		390
Parapet Railing	Foot	390		390
Slope Wall 4 Inch	Sq. Yd.		437	437
Furnishing Steel Piles HP 14x102	Foot		1,648	1,648
Furnishing Metal Shell Piles 14"x0.250"	Foot		1,742	1,742
Driving Piles	Foot		3,390	3,390
Test Pile Metal Shells	Each		1	1
Test Pile Steel HP 14x102	Each		2	2
Name Plates	Each		1	1
Preformed Joint Strip Seal	Foot	102		102
Anchor Bolts, 1"	Each		28	28
Anchor Bolts, 1 1/2"	Each		14	14
Temporary Sheet Piling	Sq. Ft.		3,411	3,411
Geocomposite Wall Drain	Sq. Yd.		134	134
Concrete Wearing Surface, 5"	Sq. Yd.	332		332
Precast Bridge Approach Slab	Sq. Ft.	2,830		2,830
Granular Backfill for Structures	Cu. Yd.		290	290
Bridge Deck Grooving (Longitudinal)	Sq. Yd.	1,044		1,044
Diamond Grinding (Bridge Section)	Sq. Yd.	1,687		1,687
Pipe Underdrains for Structures 4"	Foot		184	184
Powder Coating of Parapet Railing and Bridge Fence Railing	L Sum	1		1




"A" - Berm width varies 0" to 5'-7" at W. Abut. 0" to 2'-10" at E. Abut.

**SECTION THRU INTEGRAL ABUTMENT**


(Horizontal Dimensions @ Rt. L's)

\*Included in the cost of Pipe Underdrains for Structures, 4". (See Special Provisions)


Note: All drainage system components shall extend to 2'-0" from the end of each wingwall extension except an outlet pipe shall extend until intersecting with the side slopes. The pipes shall drain into concrete headwalls. (See Article 601.05 of the Standard Specifications and Highway Standard 601101).




**DECK POURING SEQUENCE**



**PROFILE GRADE FUTURE RAMP B**  
(along @ roadway)




**PROFILE GRADE F.A.P. 719**  
(along @ roadway)



**FUTURE PROFILE GRADE F.A.I. 57**  
(along @ roadway)


The profile grade shows the final elevations after grinding.




**SECTION THRU CONCRETE SLOPEWALL**

Slope wall shall be reinforced with welded wire fabric, 6" x 6" - W4.0 x W4.0, weighing 58 lbs. per 100 sq. ft.







**STAGE I REMOVAL**




**STAGE I CONSTRUCTION**



**STAGE II REMOVAL**




**STAGE II CONSTRUCTION**




**STAGE III CONSTRUCTION**

Notes:  
 All staging cross sections are looking East.  
 For quantity of Temporary Concrete Barrier, see roadway plans.  
 Hatched area indicates Removal of Existing Structures.

Notes:  
 The Contractor shall connect the first sheet to the existing abutment wall to ensure stability of sheets driven to the top of the existing footing. This connection shall be reviewed and accepted by the Engineer and included in the cost for Temporary Sheet Piling.  
 If the Contractor chooses to alter the temporary cantilevered sheet piling design requirements shown on the plans, a design submittal including plan details and calculations will be required for review and acceptance by the Engineer.



**TEMPORARY SHEET PILING AT EAST ABUTMENT**



**TEMPORARY SHEET PILING AT WEST ABUTMENT**

FILE NAME = 0101050-70897-003-Stg Const Details.dgn	USER NAME =	DESIGNED - AAH	REVISED -
BACON   FARMER   WORKMAN ENGINEERING & TESTING, INC.		CHECKED - BWP	REVISED -
433 NORTH COURT STREET MARENA, ILLINOIS 60091 PHONE: 815.977.9100	PLOT SCALE =	DRAWN - BJV	REVISED -
	PLOT DATE = 4/16/2019	CHECKED - BWP	REVISED -


**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**STAGE CONSTRUCTION DETAILS  
 STRUCTURE NO. 010-1050**

SHEET NO. 3 OF 36 SHEETS


F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
719	(10-34HB)BR-1	CHAMPAIGN	147	73
CONTRACT NO. 70B98				

ILLINOIS FED. AID PROJECT



When "A" is 3'-1" or less, the temporary concrete barrier shall be restrained to the new slab according to Detail I, II or III. No restraint is required when "A" is greater than 3'-1".

**NEW SLAB OR NEW DECK BEAM**




Drill 3-1/4"  $\phi$  Holes in existing slab for 1"  $\phi$  restraining pins. Traffic side only. Cost of restraining pins are included with Temporary Concrete Barrier. No restraint is required when "A" is greater than 3'-1".

**EXISTING SLAB**

\* When hot-mix asphalt wearing surface is present, embedment shall be 3" plus the wearing surface depth.


**EXISTING DECK BEAM**

**SECTIONS THRU SLAB OR DECK BEAM**




US Std. 1/16" I.D. x 2 1/2" O.D. x approx. 8 gauge thick washer


**RESTRAINING PIN**




**DETAIL I**




**DETAIL II**




**DETAIL III**



**BAR SPLICER FOR #4 BAR - DETAIL III**



**STEEL RETAINER 1" x 8" x "W"**  
(Detail I and II)




**STEEL RETAINER 1" x "H" x 10"**  
(Detail III)

Notes:  
 Cost of retainer assembly is included with Temporary Concrete Barrier.  
 A retainer assembly shall be located at the approximate  $\phi$  of each temporary concrete barrier.  
 The retainer plate shall not be removed until the concrete on the adjacent stage is ready to be poured. For Detail III applications the retainer plate shall not be removed until just prior to placing the adjacent beam.  
 When the 'A' dimension is less than 1 1/2", the wood block shall be omitted and the barrier shall be placed in direct contact with the steel retainer plate. For deck beam applications the minimum required 'A' distance is 6" to accommodate the shear key clamping device.

- Detail I - Installation for a new bridge deck or bridge slab.
- Detail II - Installation for a new deck beam with an initial concrete wearing surface. Additional bar splicers shall be provided at 6'-0" centers and paired with the bar splicers of the concrete wearing surface reinforcement to accommodate the installation of the retainer assemblies. The cost of the additional bar splicers is included with the concrete wearing surface.
- Detail III - Installation for a new deck beam with no initial wearing surface or with an initial hot-mix asphalt (HMA) wearing surface present. The deck beam directly beneath the temporary concrete barrier shall be fabricated with bar splicer inserts in the side of the beam, as detailed, to accommodate the installation of the retainer assemblies. A pair of bar splicers, 6" apart, shall be placed at 6'-0" centers along the length of the beam. The cost of the bar splicers is included with the deck beam.

R-27 8-11-2017

FILE NAME = 0101050-70897-004-Temporary Concrete Barrier	DESIGNED - AAH	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION STRUCTURE NO. 010-1050</b>	F.A.P. RTE. = 719	SECTION = (10-34H)BR-1	COUNTY = CHAMPAIGN	TOTAL SHEETS = 147	SHEET NO. = 74
BACON   FARMER   WORKMAN ENGINEERING & TESTING, INC.	CHECKED - BWP	REVISED -			CONTRACT NO. 70B98				
PLOT SCALE =	DRAWN - BJV	REVISED -			ILLINOIS FED. AID PROJECT				
PLOT DATE = 4/16/2019	CHECKED - BWP	REVISED -			SHEET NO. 4 OF 36 SHEETS				




**DEAD LOAD DEFLECTION DIAGRAM**

(Includes weight of concrete only).

Note:


The above deflections are not to be used in the field if the engineer is working from the grade elevations adjusted for dead load deflection and grinding as shown on sheets 6 thru 9 of 36.



**FILLET HEIGHTS**

To determine "t": After all structural steel has been erected, elevations of the top flanges of the beams shall be taken at intervals shown below. These elevations subtracted from the "Theoretical Grade Elevations Adjusted for Dead Load Deflection and Grinding" shown on sheets 6 thru 9 of 36, minus slab thickness, equals the fillet heights "t" above top flange of beams.

The slab is to be ground after curing to achieve smoothness, but the slab is not to be ground to elevations below the "Theoretical Grade Elevations" shown on Sheets 6 thru 9 of 36. For grinding the deck, see Special Provisions.



**PLAN**

FILE NAME = 0101050-70897-005-TOS Elevations.dgn BACON   FARMER   WORKMAN ENGINEERING & TESTING, INC. 433 NORTH COURT STREET MAHON, ILLINOIS 62451 PHONE: 618.997.9100	USER NAME = PLOT SCALE = PLOT DATE = 4/16/2019	DESIGNED - AAH CHECKED - BWP DRAWN - BJV CHECKED - BWP	REVISED - REVISED - REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TOP OF SLAB ELEVATIONS STRUCTURE NO. 010-1050</b> SHEET NO. 5 OF 36 SHEETS	F.A.P. RTE. = 719 SECTION = (10-34HB)BR-1 COUNTY = CHAMPAIGN TOTAL SHEETS = 147 SHEET NO. = 75 CONTRACT NO. 70B98	ILLINOIS FED. AID PROJECT

BEAM 1

Table with 5 columns: Location, Station, Offset, Theoretical Grade Elevations, and Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding. Rows include Bk. W. Abut., C Brg. W. Abut., A-Q, C Brg. Pier 1, R-Z, AA-EE, C Brg. E. Abut., and Bk. E. Abut.

BEAM 2

Table with 5 columns: Location, Station, Offset, Theoretical Grade Elevations, and Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding. Rows include Bk. W. Abut., C Brg. W. Abut., A-Q, C Brg. Pier 1, R-Z, AA-EE, C Brg. E. Abut., and Bk. E. Abut.

BEAM 3

Table with 5 columns: Location, Station, Offset, Theoretical Grade Elevations, and Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding. Rows include Bk. W. Abut., C Brg. W. Abut., A-Q, C Brg. Pier 1, R-Z, AA-EE, C Brg. E. Abut., and Bk. E. Abut.

**BEAM 4**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding
Bk. W. Abut.	155+50.66	-2.83	795.01	795.03
☉ Brg. W. Abut	155+52.33	-2.83	795.03	795.05
A	155+62.33	-2.83	795.18	795.29
B	155+72.33	-2.83	795.31	795.51
C	155+82.33	-2.83	795.44	795.71
D	155+92.33	-2.83	795.55	795.89
E	156+02.33	-2.83	795.66	796.05
F	156+12.33	-2.83	795.76	796.18
G	156+22.33	-2.83	795.84	796.29
H	156+32.33	-2.83	795.92	796.36
I	156+42.33	-2.83	795.99	796.41
J	156+52.33	-2.83	796.04	796.43
K	156+62.33	-2.83	796.09	796.43
L	156+72.33	-2.83	796.13	796.42
M	156+82.33	-2.83	796.16	796.39
N	156+92.33	-2.83	796.18	796.35
O	157+02.33	-2.83	796.18	796.30
P	157+12.33	-2.83	796.18	796.25
Q	157+22.33	-2.83	796.17	796.21
☉ Brg. Pier 1	157+29.99	-2.83	796.16	796.18
R	157+39.99	-2.83	796.13	796.14
S	157+49.99	-2.83	796.09	796.11
T	157+59.99	-2.83	796.04	796.07
U	157+69.99	-2.83	795.98	796.04
V	157+79.99	-2.83	795.91	796.00
W	157+89.99	-2.83	795.84	795.96
X	157+99.99	-2.83	795.75	795.90
Y	158+09.99	-2.83	795.65	795.82
Z	158+19.99	-2.83	795.54	795.73
AA	158+29.99	-2.83	795.43	795.61
BB	158+39.99	-2.83	795.30	795.47
CC	158+49.99	-2.83	795.16	795.31
DD	158+59.99	-2.83	795.02	795.13
EE	158+69.99	-2.83	794.86	794.93
☉ Brg. E. Abut.	158+82.65	-2.83	794.65	794.67
Bk. E. Abut.	158+84.32	-2.83	794.62	794.64

**STAGE II CONSTRUCTION JOINT**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding
Bk. W. Abut.	155+50.66	-1.00	795.03	795.06
☉ Brg. W. Abut	155+52.33	-1.00	795.06	795.08
A	155+62.33	-1.00	795.21	795.32
B	155+72.33	-1.00	795.34	795.54
C	155+82.33	-1.00	795.47	795.74
D	155+92.33	-1.00	795.58	795.92
E	156+02.33	-1.00	795.69	796.08
F	156+12.33	-1.00	795.79	796.21
G	156+22.33	-1.00	795.87	796.31
H	156+32.33	-1.00	795.95	796.38
I	156+42.33	-1.00	796.02	796.44
J	156+52.33	-1.00	796.07	796.46
K	156+62.33	-1.00	796.12	796.46
L	156+72.33	-1.00	796.16	796.45
M	156+82.33	-1.00	796.19	796.42
N	156+92.33	-1.00	796.20	796.37
O	157+02.33	-1.00	796.21	796.33
P	157+12.33	-1.00	796.21	796.28
Q	157+22.33	-1.00	796.20	796.24
☉ Brg. Pier 1	157+29.99	-1.00	796.18	796.20
R	157+39.99	-1.00	796.16	796.17
S	157+49.99	-1.00	796.12	796.14
T	157+59.99	-1.00	796.07	796.10
U	157+69.99	-1.00	796.01	796.07
V	157+79.99	-1.00	795.94	796.03
W	157+89.99	-1.00	795.86	795.98
X	157+99.99	-1.00	795.78	795.92
Y	158+09.99	-1.00	795.68	795.85
Z	158+19.99	-1.00	795.57	795.76
AA	158+29.99	-1.00	795.46	795.64
BB	158+39.99	-1.00	795.33	795.50
CC	158+49.99	-1.00	795.19	795.34
DD	158+59.99	-1.00	795.05	795.16
EE	158+69.99	-1.00	794.89	794.96
☉ Brg. E. Abut.	158+82.65	-1.00	794.68	794.70
Bk. E. Abut.	158+84.32	-1.00	794.65	794.67

**☉ ROADWAY & PG**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding
Bk. W. Abut.	155+50.66	0.00	795.05	795.07
☉ Brg. W. Abut	155+52.33	0.00	795.08	795.10
A	155+62.33	0.00	795.22	795.33
B	155+72.33	0.00	795.36	795.56
C	155+82.33	0.00	795.48	795.76
D	155+92.33	0.00	795.60	795.94
E	156+02.33	0.00	795.70	796.09
F	156+12.33	0.00	795.80	796.22
G	156+22.33	0.00	795.89	796.33
H	156+32.33	0.00	795.96	796.40
I	156+42.33	0.00	796.03	796.45
J	156+52.33	0.00	796.09	796.47
K	156+62.33	0.00	796.14	796.48
L	156+72.33	0.00	796.17	796.46
M	156+82.33	0.00	796.20	796.43
N	156+92.33	0.00	796.22	796.39
O	157+02.33	0.00	796.23	796.35
P	157+12.33	0.00	796.23	796.30
Q	157+22.33	0.00	796.22	796.26
☉ Brg. Pier 1	157+29.99	0.00	796.20	796.22
R	157+39.99	0.00	796.17	796.19
S	157+49.99	0.00	796.13	796.15
T	157+59.99	0.00	796.08	796.12
U	157+69.99	0.00	796.03	796.09
V	157+79.99	0.00	795.96	796.05
W	157+89.99	0.00	795.88	796.00
X	157+99.99	0.00	795.79	795.94
Y	158+09.99	0.00	795.69	795.86
Z	158+19.99	0.00	795.59	795.77
AA	158+29.99	0.00	795.47	795.65
BB	158+39.99	0.00	795.34	795.52
CC	158+49.99	0.00	795.21	795.36
DD	158+59.99	0.00	795.06	795.18
EE	158+69.99	0.00	794.90	794.98
☉ Brg. E. Abut.	158+82.65	0.00	794.69	794.71
Bk. E. Abut.	158+84.32	0.00	794.66	794.68

**STAGE I CONSTRUCTION JOINT**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding
Bk. W. Abut.	155+50.66	2.75	795.01	795.03
⊕ Brg. W. Abut	155+52.33	2.75	795.03	795.05
A	155+62.33	2.75	795.18	795.29
B	155+72.33	2.75	795.31	795.51
C	155+82.33	2.75	795.44	795.71
D	155+92.33	2.75	795.56	795.89
E	156+02.33	2.75	795.66	796.05
F	156+12.33	2.75	795.76	796.18
G	156+22.33	2.75	795.84	796.29
H	156+32.33	2.75	795.92	796.36
I	156+42.33	2.75	795.99	796.41
J	156+52.33	2.75	796.05	796.43
K	156+62.33	2.75	796.09	796.43
L	156+72.33	2.75	796.13	796.42
M	156+82.33	2.75	796.16	796.39
N	156+92.33	2.75	796.18	796.35
O	157+02.33	2.75	796.19	796.30
P	157+12.33	2.75	796.18	796.25
Q	157+22.33	2.75	796.17	796.21
⊕ Brg. Pier 1	157+29.99	2.75	796.16	796.18
R	157+39.99	2.75	796.13	796.14
S	157+49.99	2.75	796.09	796.11
T	157+59.99	2.75	796.04	796.08
U	157+69.99	2.75	795.98	796.04
V	157+79.99	2.75	795.91	796.00
W	157+89.99	2.75	795.84	795.96
X	157+99.99	2.75	795.75	795.90
Y	158+09.99	2.75	795.65	795.82
Z	158+19.99	2.75	795.54	795.73
AA	158+29.99	2.75	795.43	795.61
BB	158+39.99	2.75	795.30	795.47
CC	158+49.99	2.75	795.16	795.31
DD	158+59.99	2.75	795.02	795.13
EE	158+69.99	2.75	794.86	794.94
⊕ Brg. E. Abut.	158+82.65	2.75	794.65	794.67
Bk. E. Abut.	158+84.32	2.75	794.62	794.64

**BEAM 5**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding
Bk. W. Abut.	155+50.66	4.50	794.98	795.00
⊕ Brg. W. Abut	155+52.33	4.50	795.01	795.03
A	155+62.33	4.50	795.15	795.26
B	155+72.33	4.50	795.29	795.48
C	155+82.33	4.50	795.41	795.69
D	155+92.33	4.50	795.53	795.87
E	156+02.33	4.50	795.63	796.02
F	156+12.33	4.50	795.73	796.15
G	156+22.33	4.50	795.82	796.26
H	156+32.33	4.50	795.89	796.33
I	156+42.33	4.50	795.96	796.38
J	156+52.33	4.50	796.02	796.40
K	156+62.33	4.50	796.07	796.41
L	156+72.33	4.50	796.10	796.39
M	156+82.33	4.50	796.13	796.36
N	156+92.33	4.50	796.15	796.32
O	157+02.33	4.50	796.16	796.28
P	157+12.33	4.50	796.16	796.23
Q	157+22.33	4.50	796.14	796.19
⊕ Brg. Pier 1	157+29.99	4.50	796.13	796.15
R	157+39.99	4.50	796.10	796.12
S	157+49.99	4.50	796.06	796.08
T	157+59.99	4.50	796.01	796.05
U	157+69.99	4.50	795.96	796.02
V	157+79.99	4.50	795.89	795.98
W	157+89.99	4.50	795.81	795.93
X	157+99.99	4.50	795.72	795.87
Y	158+09.99	4.50	795.62	795.79
Z	158+19.99	4.50	795.52	795.70
AA	158+29.99	4.50	795.40	795.58
BB	158+39.99	4.50	795.27	795.45
CC	158+49.99	4.50	795.14	795.29
DD	158+59.99	4.50	794.99	795.11
EE	158+69.99	4.50	794.83	794.91
⊕ Brg. E. Abut.	158+82.65	4.50	794.62	794.64
Bk. E. Abut.	158+84.32	4.50	794.59	794.61

**BEAM 6**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding
Bk. W. Abut.	155+50.66	11.83	794.87	794.89
⊕ Brg. W. Abut	155+52.33	11.83	794.89	794.91
A	155+62.33	11.83	795.04	795.15
B	155+72.33	11.83	795.17	795.37
C	155+82.33	11.83	795.30	795.57
D	155+92.33	11.83	795.41	795.75
E	156+02.33	11.83	795.52	795.91
F	156+12.33	11.83	795.62	796.04
G	156+22.33	11.83	795.70	796.14
H	156+32.33	11.83	795.78	796.21
I	156+42.33	11.83	795.85	796.27
J	156+52.33	11.83	795.90	796.29
K	156+62.33	11.83	795.95	796.29
L	156+72.33	11.83	795.99	796.28
M	156+82.33	11.83	796.02	796.25
N	156+92.33	11.83	796.04	796.21
O	157+02.33	11.83	796.04	796.16
P	157+12.33	11.83	796.04	796.11
Q	157+22.33	11.83	796.03	796.07
⊕ Brg. Pier 1	157+29.99	11.83	796.01	796.04
R	157+39.99	11.83	795.99	796.00
S	157+49.99	11.83	795.95	795.97
T	157+59.99	11.83	795.90	795.93
U	157+69.99	11.83	795.84	795.90
V	157+79.99	11.83	795.77	795.86
W	157+89.99	11.83	795.70	795.81
X	157+99.99	11.83	795.61	795.76
Y	158+09.99	11.83	795.51	795.68
Z	158+19.99	11.83	795.40	795.59
AA	158+29.99	11.83	795.29	795.47
BB	158+39.99	11.83	795.16	795.33
CC	158+49.99	11.83	795.02	795.17
DD	158+59.99	11.83	794.88	794.99
EE	158+69.99	11.83	794.72	794.79
⊕ Brg. E. Abut.	158+82.65	11.83	794.51	794.53
Bk. E. Abut.	158+84.32	11.83	794.48	794.50

**BEAM 7**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding
Bk. W. Abut.	155+50.66	19.17	794.71	794.73
⊕ Brg. W. Abut	155+52.33	19.17	794.74	794.76
A	155+62.33	19.17	794.88	795.00
B	155+72.33	19.17	795.02	795.22
C	155+82.33	19.17	795.15	795.42
D	155+92.33	19.17	795.26	795.60
E	156+02.33	19.17	795.37	795.76
F	156+12.33	19.17	795.46	795.89
G	156+22.33	19.17	795.55	795.99
H	156+32.33	19.17	795.63	796.06
I	156+42.33	19.17	795.70	796.12
J	156+52.33	19.17	795.75	796.14
K	156+62.33	19.17	795.80	796.14
L	156+72.33	19.17	795.84	796.12
M	156+82.33	19.17	795.87	796.09
N	156+92.33	19.17	795.88	796.05
O	157+02.33	19.17	795.89	796.01
P	157+12.33	19.17	795.89	795.96
Q	157+22.33	19.17	795.88	795.92
⊕ Brg. Pier 1	157+29.99	19.17	795.86	795.88
R	157+39.99	19.17	795.83	795.85
S	157+49.99	19.17	795.80	795.82
T	157+59.99	19.17	795.75	795.78
U	157+69.99	19.17	795.69	795.75
V	157+79.99	19.17	795.62	795.71
W	157+89.99	19.17	795.54	795.66
X	157+99.99	19.17	795.46	795.60
Y	158+09.99	19.17	795.36	795.53
Z	158+19.99	19.17	795.25	795.43
AA	158+29.99	19.17	795.13	795.32
BB	158+39.99	19.17	795.01	795.18
CC	158+49.99	19.17	794.87	795.02
DD	158+59.99	19.17	794.72	794.84
EE	158+69.99	19.17	794.57	794.64
⊕ Brg. E. Abut.	158+82.65	19.17	794.36	794.38
Bk. E. Abut.	158+84.32	19.17	794.33	794.35

**NORTH EDGE OF SIDEWALK**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End W. Appr. Pav't.	155+21.66	-28.58	794.03	794.05
A1	155+31.66	-27.89	794.22	794.24
A2	155+41.66	-27.20	794.41	794.43
E. End W. Appr. Pav't.	155+51.66	-26.58	794.57	794.59

**SOUTH EDGE OF SIDEWALK**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End W. Appr. Pav't.	155+21.66	-21.58	794.18	794.20
A1	155+31.66	-21.58	794.36	794.38
A2	155+41.66	-21.58	794.52	794.54
E. End W. Appr. Pav't.	155+51.66	-21.58	794.68	794.70

**NORTH EDGE OF SHOULDER**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End W. Appr. Pav't.	155+21.66	-20.00	794.21	794.23
A1	155+31.66	-20.00	794.39	794.41
A2	155+41.66	-20.00	794.56	794.58
E. End W. Appr. Pav't.	155+51.66	-20.00	794.71	794.73

**NORTH EDGE OF PAVEMENT**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End W. Appr. Pav't.	155+21.66	-12.00	794.38	794.40
A1	155+31.66	-12.00	794.56	794.58
A2	155+41.66	-12.00	794.72	794.74
E. End W. Appr. Pav't.	155+51.66	-12.00	794.88	794.90

**CL ROADWAY & PG**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End W. Appr. Pav't.	155+21.66	0.00	794.57	794.59
A1	155+31.66	0.00	794.74	794.76
A2	155+41.66	0.00	794.91	794.93
E. End W. Appr. Pav't.	155+51.66	0.00	795.07	795.09

**STAGE CONST. JOINT  
(CONCRETE WEARING SURFACE)**


Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End W. Appr. Pav't.	155+21.66	3.58	794.55	794.57
A1	155+31.66	3.58	794.72	794.74
A2	155+41.66	3.58	794.87	794.89
E. End W. Appr. Pav't.	155+51.66	3.58	795.01	795.03

**SOUTH EDGE OF PAVEMENT**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End W. Appr. Pav't.	155+21.66	12.00	794.52	794.54
A1	155+31.66	12.00	794.65	794.67
A2	155+41.66	12.00	794.76	794.78
E. End W. Appr. Pav't.	155+51.66	12.00	794.88	794.90

**SOUTH EDGE OF SHOULDER**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End W. Appr. Pav't.	155+21.66	20.00	794.36	794.38
A1	155+31.66	20.00	794.48	794.50
A2	155+41.66	20.00	794.60	794.62
E. End W. Appr. Pav't.	155+51.66	20.00	794.71	794.73



**PLAN**





**NORTH EDGE OF SIDEWALK**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End E. Appr. Pav't.	158+83.32	-26.58	794.19	794.21
A3	158+93.32	-27.20	794.00	794.02
A4	159+03.32	-27.89	793.79	793.81
E. End E. Appr. Pav't.	159+13.32	-28.58	793.58	793.60

**SOUTH EDGE OF SIDEWALK**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End E. Appr. Pav't.	158+83.32	-21.58	794.29	794.31
A3	158+93.32	-21.58	794.11	794.13
A4	159+03.32	-21.58	793.93	793.95
E. End E. Appr. Pav't.	159+13.32	-21.58	793.73	793.75

**NORTH EDGE OF SHOULDER**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End E. Appr. Pav't.	158+83.32	-20.00	794.33	794.35
A3	158+93.32	-20.00	794.15	794.17
A4	159+03.32	-20.00	793.96	793.98
E. End E. Appr. Pav't.	159+13.32	-20.00	793.76	793.78

**NORTH EDGE OF PAVEMENT**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End E. Appr. Pav't.	158+83.32	-12.00	794.49	794.51
A3	158+93.32	-12.00	794.31	794.33
A4	159+03.32	-12.00	794.13	794.15
E. End E. Appr. Pav't.	159+13.32	-12.00	793.93	793.95

**☉ ROADWAY & PG**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End E. Appr. Pav't.	158+83.32	0.00	794.68	794.70
A3	158+93.32	0.00	794.50	794.52
A4	159+03.32	0.00	794.31	794.33
E. End E. Appr. Pav't.	159+13.32	0.00	794.11	794.13

**STAGE CONST. JOINT  
(CONCRETE WEARING SURFACE)**


Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End E. Appr. Pav't.	158+83.32	3.58	794.62	794.64
A3	158+93.32	3.58	794.45	794.47
A4	159+03.32	3.58	794.26	794.28
E. End E. Appr. Pav't.	159+13.32	3.58	794.06	794.08

**SOUTH EDGE OF PAVEMENT**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End E. Appr. Pav't.	158+83.32	12.00	794.49	794.51
A3	158+93.32	12.00	794.31	794.33
A4	159+03.32	12.00	794.13	794.15
E. End E. Appr. Pav't.	159+13.32	12.00	793.93	793.95


**SOUTH EDGE OF SHOULDER**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Grinding
W. End E. Appr. Pav't.	158+83.32	20.00	794.33	794.35
A3	158+93.32	20.00	794.15	794.17
A4	159+03.32	20.00	793.96	793.98
E. End E. Appr. Pav't.	159+13.32	20.00	793.76	793.78



**PLAN**






**MINIMUM BAR LAP**

- #5 bar = 3'-6"
- #6 bar = 4'-10"

**PLAN**

Notes:  
 See Sheet 13 of 36 for superstructure details and Bill of Material.  
 Bars indicated thus 20 x 3-#5 etc. indicates 20 lines of bars with 3 lengths per line.  
 See Sheet 13 and 14 of 36 for parapet reinforcement.




**NEAR MIDSPAN**

**CROSS SECTION**

**NEAR PIER**

FILE NAME = 0101050-70897-012-Superstructure.dgn <b>BFW</b> BACON   FARMER   WORKMAN ENGINEERING & TESTING, INC. 433 NORTH COURT STREET MAHOMET, ILLINOIS 62450 PHONE: 618.937.9100	USER NAME = PLOT SCALE = PLOT DATE = 4/16/2019	DESIGNED - AAH CHECKED - BWP DRAWN - BJV CHECKED - BWP	REVISED - REVISED - REVISED - REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUPERSTRUCTURE</b> <b>STRUCTURE NO. 010-1050</b> SHEET NO. 12 OF 36 SHEETS	F.A.P. R.E. = 719	SECTION = (10-34HB)BR-1	COUNTY = CHAMPAIGN	TOTAL SHEETS = 147	SHEET NO. = 82
	CONTRACT NO. 70B98					ILLINOIS FED. AID PROJECT				




**INSIDE ELEVATION OF NORTH ROADWAY PARAPET**  
(South Parapet Similar)


**MINIMUM BAR LAP**  
(Parapet)  
#4 bar = 2'-8"  
#8 bar = 5'-11"

**SUPERSTRUCTURE  
BILL OF MATERIAL**

Bar	No.	Size	Length	Shape
a(E)	724	#5	18'-4"	—
a1(E)	724	#5	29'-10"	—
a2(E)	724	#6	6'-6"	—
a3(E)	443	#5	29'-6"	—
a4(E)	443	#5	18'-0"	—
a5(E)	724	#6	12'-6"	—
b(E)	612	#5	30'-10"	—
b1(E)	245	#6	26'-9"	—
b2(E)	588	#5	26'-11"	—
d(E)	332	#4	4'-2"	L
d1(E)	332	#6	3'-8"	L
d2(E)	136	#4	2'-0"	L
d3(E)	362	#5	7'-8"	L
d4(E)	724	#5	5'-7"	L
d5(E)	362	#5	6'-10"	L
e(E)	160	#4	19'-5"	—
e1(E)	44	#4	19'-8"	—
e2(E)	140	#4	18'-8"	—
e3(E)	22	#8	31'-4"	—
e4(E)	4	#8	19'-8"	—
e5(E)	22	#4	28'-9"	—
m(E)	12	#6	29'-10"	—
m1(E)	12	#6	18'-6"	—
m2(E)	60	#6	7'-0"	—
m3(E)	20	#6	2'-1"	—
m4(E)	84	#5	4'-0"	—
s(E)	88	#5	9'-11"	U
s1(E)	88	#5	15'-6"	U
Reinforcement Bars, Epoxy Coated		Pound	148,760	
Concrete Superstructure		Cu. Yds.	608.9	




**SECTION THRU  
EAST PARAPET**




**PARAPET JOINT DETAILS**


**Notes:**  
The 1/8" Aluminum sheet shall be ASTM B 209 alloy 3003-H14 and coated to minimize reaction with wet concrete. Cost included with Concrete Superstructure.  
The Polyurethane Sealant shall be non-staining gray one component non-sag elastomeric gun grade meeting the requirements of ASTM C-920, Type S, Grade NS, Class 25. Use T with a 5/8" backer rod.  
The 1/2" Preformed Self-Expanding Cork Joint Filler shall be according to Article 1051.07 of the Std. Spec. Cost included with Concrete Superstructure.  
Headed bars shall conform to ASTM A970 Class HA. Cost included with Reinforcement Bars, Epoxy Coated.




**BAR d4(E)**




**BAR d5(E)**



**BAR s1(E)**




**BAR s(E)  
(Headed)**




**INSIDE ELEVATION OF NORTH SIDEWALK PARAPET WALL**  
(Looking North)


\*\* 2-2" PVC conduit, Sch. 40 min.  
Maintain 1/2" cl. from reinforcement




**SECTION THRU SIDEWALK**




**BAR d1(E)**




**BAR d2(E)**



**BAR d3(E)**




**DETAIL A**



**NORTH SIDEWALK PARAPET JOINT DETAILS**

Note:  
The 1/8" Aluminum sheet shall be ASTM B 209 alloy 3003-H14 and coated to minimize reaction with wet concrete. Cost included with Concrete Superstructure.



**ALTERNATE BAR d3(E)**

\* Drill and set Alternate #5 d3(E) bar according to Article 509.06 of the Standard Specifications. Drilled holes shall be roughened or scored per manufacturer's recommendations. Maximum depth of hole shall not exceed 6".  
The Contractor shall take all necessary precautions to prevent drilled hole interference with deck reinforcement bars. Locate longitudinal bars to miss drilled locations. Locate drilled holes to miss transverse bars in deck.  
If alternate parapet reinforcement is chosen, cost of alternate d3(E) bars, drilling, and setting is included with the cost of Reinforcement Bars, Epoxy Coated.




FILE NAME = 0101050-70897-014-Super Details.dgn	USER NAME =	DESIGNED - AAH	REVISED -
BACON   FARMER   WORKMAN ENGINEERING & TESTING, INC.		CHECKED - BWP	REVISED -
433 NORTH COURT STREET MORRIS, ILLINOIS 62451 PHONE: 618.997.8100	PLOT SCALE =	DRAWN - BJV	REVISED -
	PLOT DATE = 4/16/2019	CHECKED - BWP	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**SUPERSTRUCTURE DETAILS  
STRUCTURE NO. 010-1050**

SHEET NO. 14 OF 36 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
719	(10-34HB)BR-1	CHAMPAIGN	147	84
CONTRACT NO. 70B98				
ILLINOIS FED. AID PROJECT				




Notes:  
 Reinforcement bars in diaphragm are billed with superstructure on sheet 13 of 36.  
 Concrete in diaphragm is included with Concrete Superstructure on sheet 13 of 36.  
 For details of bars s(E) and s<sub>1</sub>(E) see sheet 13 of 36.  
 The approach slab seat shall have a constant slope determined from the control points shown.  
 For bearing details see sheet 25 of 36.  
 Beams shall be braced for stability during erection and remain braced until deck is poured and cured.




**PLAN**

(Showing wearing surface, East approach shown, West approach similar by mirror image.)




**DETAIL 'A'**



**SECTION A-A**

\*\*\* Prior to grinding

\*\*Varies from 5 1/4\"/>



**CROSS SECTION**



(Looking East)

\*Varies from 3'-9\"/>




**NEAR ABUTMENT**

**AT APPROACH FOOTING**



(Sheet 1 of 5)



Notes:  
 The precast bridge approach slab shall be according to Section 504 of the Standard Specifications and shall be paid for at the contract unit price per square foot for Precast Bridge Approach Slab.  
 Cast-in-place substitution of Precast Bridge Approach Slab is not allowed.  
 The top surface of precast bridge approach slabs shall be finished similar to precast prestressed deck beams with concrete wearing surface as specified in the IDOT "Manual for Fabrication of Precast Prestressed Concrete Products."  
 Two 1/8" fabric adjusting shims of the dimensions of the exterior bearing pad shall be provided for each bearing pad location. Cost included with Precast Bridge Approach Slab.  
 A minimum 2 1/2" φ lifting pins shall be used to engage the lifting loops during handling.  
 Compressive strength of precast concrete, f'c shall be 6,000 psi.  
 Compressive strength of precast concrete during initial lifting, f'ci shall be 5,000 psi.




Notes:  
 All bearing pads shall be 1/2" thick.  
 Omit holes for fabric bearing pads at approach slab footing end of beams.  
 Expansion bearing pad shall be bonded to the approach slab footing.



BARS D(E) D1(E) & D2(E)

BARS S(E) S1(E) & S2(E)



LIFTING LOOP DETAIL

(An alternate lifting loop with a proof load of 25,000 lbs. and utilized according to the manufacturer's recommendations may be used)

BAR LIST EACH  
 11" x 3'-1" INTERIOR BEAM  
 (For information only)

Bar	No.	Size	Length	Shape
B(E)	3	#5	29'-8"	—
B1(E)	7	#9	29'-8"	—
D1(E)	22	#4	4'-8"	□
S1(E)	60	#5	7'-8"	▭

BAR LIST EACH  
 11" x 4'-9" INTERIOR BEAM  
 (For information only)

Bar	No.	Size	Length	Shape
B(E)	5	#5	29'-8"	—
B1(E)	11	#9	29'-8"	—
D2(E)	22	#4	6'-4"	□
S2(E)	60	#5	11'-0"	▭

BAR LIST  
 EACH 11" x 5'-9" INTERIOR BEAM  
 (For information only)

Bar	No.	Size	Length	Shape
B(E)	6	#5	29'-8"	—
B1(E)	13	#9	29'-8"	—
D(E)	22	#4	7'-4"	□
S(E)	60	#5	13'-0"	▭

BAR LIST  
 11" x 5'-9" SOUTH EXTERIOR BEAM  
 (For information only)

Bar	No.	Size	Length	Shape
B(E)	6	#5	29'-8"	—
B1(E)	13	#9	29'-8"	—
D(E)	32	#4	7'-4"	□
S(E)	60	#5	13'-0"	▭

BA-P-34FS-0

07-22-16

(Beams: 36" min. width; 72" max. width)

FILE NAME = 0101050-70897-017-Prec Br Appr Slab.dgn	USER NAME =	DESIGNED - AAH	REVISED -
BACON   FARMER   WORKMAN ENGINEERING & TESTING, INC.		CHECKED - BWP	REVISED -
433 NORTH COURT STREET MORRIS, ILLINOIS 62450 PHONE - 618.937.9100	PLOT SCALE =	DRAWN - BJV	REVISED -
	PLOT DATE = 4/16/2019	CHECKED - BWP	REVISED -


STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

PRECAST BRIDGE APPROACH SLAB  
 STRUCTURE NO. 010-1050

SHEET NO. 17 OF 36 SHEETS


F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
719	(10-34HB)BR-1	CHAMPAIGN	147	87
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	

(Sheet 2 of 5)




**PLAN**


(Showing the North variable width exterior beam at the East approach slab. West approach slab similar.)




**SECTION D-D**  
(Showing dimensions)




**SECTION D-D**  
(Showing reinforcement)




**SECTION F-F**  
(Showing reinforcement)



**BARS D<sub>3</sub>(E)**



**BARS S<sub>3</sub>(E) & S<sub>4</sub>(E)**



**BARS S<sub>5</sub>(E), S<sub>6</sub>(E) & S<sub>7</sub>(E)**

**BAR LIST EACH NORTH EXTERIOR BEAM**  
(For information only)

Bar	No.	Size	Length	Shape
B(E)	6	#5	29'-8"	—
B <sub>1</sub> (E)	13	#9	29'-8"	—
D <sub>3</sub> (E)	41	#4	5'-4"	□
S <sub>3</sub> (E)	20	#5	6'-6"	□
S <sub>4</sub> (E)	20	#5	6'-10"	□
S <sub>5</sub> (E)	14	#5	8'-7"	□
S <sub>6</sub> (E)	22	#5	9'-3"	□
S <sub>7</sub> (E)	44	#5	9'-11"	□

(Sheet 3 of 5)



Notes:

The joint opening shall be adjusted for temperature per Article 520.04 of the Standard Specifications. However, since this detail is for jointless structures, the length of bridge used to calculate the adjustment shall be equal to half the total bridge length plus the length of the bridge approach pavement.

After precast bridge approach slabs have been erected, holes shall be drilled into abutment and anchor dowels placed. Dowel holes shall be filled with non-shrink grout to top of precast slab and cured according to Article 1020.13(a)(3) or 1020.13(a)(5) of the Standard Specifications for a minimum of 24 hours before casting the shear keys and wearing surface.

Any concrete poured monolithically with the wearing surface, such as curbs, shall not be paid for separately, but will be included in the cost of Concrete Wearing Surface, 5".

The strip seal shall be made continuous and shall have a minimum thickness of 1/4". The strip seal shall extend 6" beyond the edge of the approach slab on each end. The configuration of the strip seal shall match the configuration of the Locking Edge Rails. Open or "webbed" strip seal gland configurations are not permitted. The gland shall be sized for a maximum rated movement of 4 inches.

The Locking Edge Rails depicted are conceptual only, except for the minimum dimensions shown. The actual configuration of the Locking Edge Rails and matching strip seal may vary from manufacturer to manufacturer. Flanged edge rails will not be allowed. Locking Edge Rails may be spliced at slope discontinuities and stage construction joints.

The manufacturer's recommended installation methods shall be followed.

All steel components shall be galvanized after fabrication according to Article 520.03 of the Standard Specifications.


Maximum space between rail segments at stage lines shall be 3/16", sealed with a suitable sealant. Joints in rails within 10 ft. of curbs shall be welded.

Parapet concrete shall be paid for as Concrete Superstructure.


Approach footing concrete shall be paid for as Concrete Structures.

The approach footing maximum applied service bearing pressure (Qmax) = 2.0 ksf. Cost of excavation for approach footing included with Concrete Structures.


For Granular Backfill for Structures and drainage treatment details, see sheet 2 of 36.



SECTION E-E



SECTION THRU STRIP SEAL JOINT




ROLLED (EXTRUDED) RAIL

WELDED RAIL


LOCKING EDGE RAIL

\* Back gouge not required if complete joint penetration is verified by mock-up.




LOCKING EDGE RAIL SPLICE


The inside of the locking edge rail groove shall be free of weld residue. Rolled rail shown, welded rail similar.



BAR d10(E)



BAR d11(E)



BAR d12(E) & d13(E)

BARS a11(E) & a13(E)

TWO APPROACHES BILL OF MATERIAL

Bar	No.	Size	Length	Shape
a <sub>10</sub> (E)	62	#4	17'-6"	—
a <sub>11</sub> (E)	30	#4	7'-5"	—
a <sub>12</sub> (E)	62	#4	32'-0"	—
a <sub>13</sub> (E)	62	#4	14'-5"	—
a <sub>14</sub> (E)	8	#4	1'-6"	—
b <sub>10</sub> (E)	104	#4	29'-8"	—
b <sub>11</sub> (E)	6	#4	14'-8"	—
d <sub>2</sub> (E)	24	#4	2'-0"	—
d <sub>10</sub> (E)	102	#5	5'-7"	—
d <sub>11</sub> (E)	102	#5	5'-11"	—
d <sub>12</sub> (E)	62	#4	3'-5"	—
d <sub>13</sub> (E)	62	#6	3'-5"	—
e <sub>10</sub> (E)	68	#4	14'-8"	—
e <sub>11</sub> (E)	2	#8	14'-8"	—
e <sub>12</sub> (E)	2	#8	29'-8"	—
e <sub>13</sub> (E)	2	#4	29'-8"	—
t <sub>10</sub> (E)	204	#4	9'-8"	—
w <sub>10</sub> (E)	80	#5	18'-6"	—
w <sub>11</sub> (E)	80	#5	31'-10"	—
Concrete Superstructure			Cu. Yd.	15.0
Concrete Structures			Cu. Yd.	39.4
Reinforcement Bars, Epoxy Coated			Pound	13,100
Precast Bridge Approach Slab			Sq. Ft.	2,830
Concrete Wearing Surface, 5"			Sq. Yd.	332
Preformed Joint Strip Seal			Foot	102

BA-P-34FS-0

07-22-16

(Beams: 36" min. width; 72" max. width)

(Sheet 4 of 5)

FILE NAME = 0101050-70897-019-Prec Br Appr Slab.dgn	USER NAME =	DESIGNED - AAH	REVISED -
BACON   FARMER   WORKMAN ENGINEERING & TESTING, INC.		CHECKED - BWP	REVISED -
433 NORTH COURT STREET MAHOMET, ILLINOIS 62451 PHONE: 618.977.9100	PLOT SCALE =	DRAWN - BJV	REVISED -
	PLOT DATE = 4/16/2019	CHECKED - BWP	REVISED -



STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

PRECAST BRIDGE APPROACH SLAB STRUCTURE NO. 010-1050

SHEET NO. 19 OF 36 SHEETS


F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
719	(10-34H)BR-1	CHAMPAIGN	147	89
CONTRACT NO. 70B98			ILLINOIS FED. AID PROJECT	

Note: East Approach shown, West Approach similar.




**INSIDE ELEVATION OF PARAPET AND CURB**  
(South Roadway Parapet at East approach)

**VIEW D-D**






**INSIDE ELEVATION OF PARAPET WALL**  
(North Sidewalk Parapet at East approach)







**INSIDE ELEVATION OF PARAPET**  
(North Roadway Parapet at East Approach)

(Sheet 5 of 5)

FILE NAME = 0101050-70897-020-Prec Br Appr Slab.dgn BACON   FARMER   WORKMAN ENGINEERING & TESTING, INC. 433 NORTH COURT STREET MAHON, ILLINOIS 60951 PHONE: 618.997.9100	USER NAME =	DESIGNED - AAH CHECKED - BWP	REVISED - REVISED - REVISED - REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>PRECAST BRIDGE APPROACH SLAB</b> <b>STRUCTURE NO. 010-1050</b>	F.A.P. RTE. = 719	SECTION = (10-34H)BR-1	COUNTY = CHAMPAIGN	TOTAL SHEETS = 147	SHEET NO. = 90
	PLOT SCALE =	DRAWN - BJV CHECKED - BWP	PLOT DATE = 4/16/2019			SHEET NO. 20 OF 36 SHEETS	CONTRACT NO. 70B98	ILLINOIS FED. AID PROJECT		



**Notes:**  
 All steel rail elements shall be galvanized according to Article 509.05 of the Standard Specifications. All of these elements, except the chain link fabric and ties, shall also be powder coated. At a minimum, the powder coating process shall consist of a zinc phosphate pretreatment/wash, a gray zinc rich primer coat, and a black top coat.  
 The galvanized chain link fabric and ties shall be vinyl coated black according to Section 509 and Article 1006.27(a)(1)d of the Standard Specifications.



**ANCHOR BOLT DETAILS**  
 In lieu of the cast-in-place anchor device shown, the Contractor has the option of drilling and setting 5/8"  $\phi$  anchor rods according to Article 509.06 of the Standard Specifications. Embedment shall be according to the manufacturer's specifications.

**BILL OF MATERIAL**

Item	Unit	Quantity
Bridge Fence Railing	Foot	390

R-32

1-12-15

\*Variable - See Plans  
 (10'-0" Maximum Post Spacing)

FILE NAME = 0101050-70897-021-Bridge Fence Railing.dgn	USER NAME =	DESIGNED - AAH	REVISED -
BACON   FARMER   WORKMAN ENGINEERING & TESTING, INC.		CHECKED - BWP	REVISED -
433 NORTH COURT STREET MORRIS, ILLINOIS 62451 PHONE - 618.937.9100	PLOT SCALE =	DRAWN - BJV	REVISED -
	PLOT DATE = 4/16/2019	CHECKED - BWP	REVISED -


**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**BRIDGE FENCE RAILING, PARAPET MOUNTED  
 STRUCTURE NO. 010-1050**


SHEET NO. 21 OF 36 SHEETS

F.A.P. RTE. 719	SECTION (10-34HB)BR-1	COUNTY CHAMPAIGN	TOTAL SHEETS 147	SHEET NO. 91
			CONTRACT NO. 70B98	
ILLINOIS FED. AID PROJECT				

Notes:  
 All steel rail elements shall be galvanized according to Article 509.05 of the Standard Specifications. All of these elements shall also be powder coated. At a minimum, the powder coating process shall consist of a zinc phosphate pretreatment/wash, a gray zinc rich primer coat, and a black top coat.




**ANCHOR BOLT DETAILS**




In lieu of the cast-in-place anchor device shown, the Contractor has the option of drilling and setting 5/8"  $\phi$  anchor rods according to Article 509.06 of the Standard Specifications. Embedment shall be according to the manufacturer's specifications.

(10'-0" Maximum Post Spacing)



**SECTION THRU DECK**




**PARAPET RAILING ELEVATION**  
 (Inside face of two element rail)

**BILL OF MATERIAL**


Notes:  
 All structural steel tubing, post and railing, for parapet railing shall be CVN tested according to 1006.34(b) of the Standard Specifications.

Item	Unit	Quantity
Parapet Railing	Foot	390



**PLAN**

\* Location of temporary articulated bracing (see sheet 24 of 36).



**BEARING STIFFENER AT ABUTMENT**

(No. plates required = 28)


**BEARING STIFFENER AT PIER**

(No. plates required = 14)

\*\* Terminate 1/4" (± 1/8") from the end of plate intersects.

**Notes:**


All flange, web, and bearing stiffener plates shall be AASHTO M 270 Grade 50.  
All cross frames shall be installed as steel is erected and secured with erection pins and bolts except as otherwise noted. Individual cross frames at supports may be temporarily disconnected to install bearing anchor rods.



**GIRDER ELEVATION**


"CVN" denotes Charpy-V-Notch impact energy requirements, zone 2.

\*\*\* Transverse Stiffener 1/2" x 6 1/2" Interior Face




**CONNECTION PLATE**


(No. plates required = 180)




**SECTION A-A**




**DETAIL B**



**DETAIL C**




**TYP. END OF BEAM ELEVATION**



**TRANSVERSE STIFFENER**

(No. plates required = 14)


FILE NAME = 0101050-70897-023-Structural Steel.dgn <b>BFW</b> BACON   FARMER   WORKMAN ENGINEERING & TESTING, INC. 433 NORTH COURT STREET MAHOMET, ILLINOIS 62450 PHONE: 618.937.9100	USER NAME = PLOT SCALE = PLOT DATE = 4/16/2019	DESIGNED - AAH CHECKED - BWP DRAWN - BJV CHECKED - BWP	REVISED - REVISED - REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>STRUCTURAL STEEL STRUCTURE NO. 010-1050</b> SHEET NO. 23 OF 36 SHEETS	F.A.P. R.T.E. = 719 SECTION = (10-34H)BR-1 COUNTY = CHAMPAIGN TOTAL SHEETS = 147 SHEET NO. = 93 CONTRACT NO. 70B98	ILLINOIS FED. AID PROJECT



**INTERIOR CROSS FRAME CF**

(No. Req'd. = 96)


\* Fillet weld angles along 3 sides on one face of gusset plate




**TEMPORARY ARTICULATED BRACING**

(No. Req'd. = 16)


See CF for details not shown above.  
After closure pour is complete, temporary braces shall be replaced by cross frames CF as shown on framing plan.




**TOP & BOTTOM FLANGE**



**TOP & BOTTOM FLANGE**




**FIELD SPLICE 1 DETAIL**



**FIELD SPLICE 2 DETAIL**

**Notes:**

- Use 7/8"  $\phi$  H.S. bolts with 15/16"  $\phi$  holes for all splice connections.
- "CVN" denotes Charpy-V-Notch impact energy requirements, zone 2.
- All splice plates shall be AASHTO M 270 Grade 50.
- Use 3/4"  $\phi$  H.S. bolts with 15/16"  $\phi$  holes for all cross frame connections.
- Two hardened washers required for each set of oversized holes.




**CAMBER DIAGRAM**

**\*TOP OF WEB ELEVATIONS**


Location	☉ Brg. W. Abut.	☉ Splice 1	☉ Brg. Pier 1	☉ Splice 2	☉ Brg. E. Abut.
Girder 1	793.81	795.09	794.78	794.64	793.43
Girder 2	793.96	795.24	794.93	794.79	793.58
Girder 3	794.11	795.39	795.08	794.94	793.73
Girder 4	794.22	795.50	795.19	795.05	793.84
Girder 5	794.20	795.48	795.17	795.03	793.82
Girder 6	794.08	795.36	795.05	794.91	793.70
Girder 7	793.93	795.21	794.90	794.76	793.55

\*For fabrication use only.




ELEVATION AT PIER


FIXED BEARING



SECTION B-B




PINTLE



ELEVATION AT ABUTMENT

FIXED BEARING



SECTION A-A

INTERIOR GIRDER MOMENT TABLE				
		0.4 Sp. 1	Pier	0.6 Sp. 2
$I_s$	(in <sup>4</sup> )	53,423	127,454	41,192
$I_c(n)$	(in <sup>4</sup> )	121,039	213,591	97,046
$I_c(3n)$	(in <sup>4</sup> )	88,669	166,518	71,477
$I_c(cr)$	(in <sup>4</sup> )	-----	138,972	-----
$S_s$	(in <sup>3</sup> )	1,625	3,516	1,185
$S_c(n)$	(in <sup>3</sup> )	2,197	4,083	1,695
$S_c(3n)$	(in <sup>3</sup> )	1,993	3,824	1,521
$S_c(cr)$	(in <sup>3</sup> )	-----	3,620	-----
DC1	(k/')	1.065	1.294	1.024
M <sub>DC1</sub>	(k)	2,244	4,605	1,104
DC2	(k/')	0.275	0.275	0.275
M <sub>DC2</sub>	(k)	593	1,121	321
DW	(k/')	0.327	0.327	0.327
M <sub>DW</sub>	(k)	705	1,334	381
LLDF		0.546	0.555	0.564
$M_L + IM$	(k)	2,752	3,093	2,217
$M_u$ (Strength I)	(k)	9,420	14,571	6,233
$\phi_r M_n$	(k)	10,378	15,733	8,265
$f_s$ DC1	(ksi)	16.6	15.7	11.2
$f_s$ DC2	(ksi)	3.6	3.7	2.5
$f_s$ DW	(ksi)	4.2	4.4	3.0
$f_s$ ( $\zeta + IM$ )	(ksi)	15.0	10.3	15.7
$f_s$ (Service II)	(ksi)	43.9	37.2	37.1
$0.95R_n F_y f$	(ksi)	47.5	47.5	47.5
$f_s$ (Total)(Strength I)	(ksi)	-----	-----	-----
$\phi_r F_n$	(ksi)	-----	-----	-----
$V_r$	(k)	31.1	31.1	32.7

GIRDER REACTION TABLE						
	West Abut.		Pier		East Abut.	
	Interior	Exterior	Interior	Exterior	Interior	Exterior
LLDF	0.767	0.537	0.767	0.537	0.767	0.537
OCF	-----	1.000	---	---	---	1.000
R <sub>DC1</sub> (k)	70.4	65.6	243.8	228.1	50.3	46.7
R <sub>DC2</sub> (k)	18.1	18.1	59.1	59.1	13.7	13.7
R <sub>DW</sub> (k)	21.5	21.5	70.3	70.3	16.2	16.2
R <sub>LL</sub> (k)	88.7	62.1	186.9	130.9	82.9	58.0
R <sub>IM</sub> (k)	16.9	11.8	30.5	21.4	16.8	11.8
R <sub>Total</sub> (k)	215.6	179.1	590.6	509.8	179.9	146.4

Notes:

Anchor bolts shall be ASTM F1554 all-thread (or an Engineer-approved alternate material) of the grade(s) and diameter(s) specified. The corresponding specified grade of AASHTO M314 anchor bolts may be used in lieu of ASTM F1554.

Beams shall be braced for stability during erection and remain braced until deck is poured and cured.

Anchor bolts at all supports shall be installed as each member is erected unless an equivalent temporary means of lateral restraint is used.

Two 1/8 in. adjusting shims shall be provided for each bearing in addition to all other plates or shims and placed as shown on bearing details.

All bearing plates and pintles shall be AASHTO M270 Grade 50.

FILL PLATE THICKNESS




	W. Abut.	Pier	E. Abut.
Girder 4	1/4"	1/4"	1/4"

- $I_s, S_s$ : Non-composite moment of inertia and section modulus of the steel section used for computing  $f_s$  (Total-Strength I, and Service II) due to non-composite dead loads (in<sup>4</sup> and in<sup>3</sup>).
- $I_c(n), S_c(n)$ : Composite moment of inertia and section modulus of the steel and deck based upon the modular ratio, "n", used for computing  $f_s$  (Total-Strength I, and Service II) in uncracked sections due to short-term composite live loads (in<sup>4</sup> and in<sup>3</sup>).
- $I_c(3n), S_c(3n)$ : Composite moment of inertia and section modulus of the steel and deck based upon 3 times the modular ratio, "3n", used for computing  $f_s$  (Total-Strength I, and Service II) in uncracked sections, due to long-term composite (superimposed) dead loads (in<sup>4</sup> and in<sup>3</sup>).
- $I_c(cr), S_c(cr)$ : Composite moment of inertia and section modulus of the steel and longitudinal deck reinforcement, used for computing  $f_s$  (Total-Strength I and Service II) in cracked sections, due to both short-term composite live loads and long-term composite (superimposed) dead loads (in<sup>4</sup> and in<sup>3</sup>).
- DC1: Un-factored non-composite dead load (kips/ft.).
- M<sub>DC1</sub>: Un-factored moment due to non-composite dead load (kip-ft.).
- DC2: Un-factored long-term composite (superimposed excluding future wearing surface) dead load (kips/ft.).
- M<sub>DC2</sub>: Un-factored moment due to long-term composite (superimposed excluding future wearing surface) dead load (kip-ft.).
- DW: Un-factored long-term composite (superimposed future wearing surface only) dead load (kips/ft.).
- M<sub>DW</sub>: Un-factored moment due to long-term composite (superimposed future wearing surface only) dead load (kip-ft.).
- $M_L + IM$ : Un-factored live load moment plus dynamic load allowance (impact) (kip-ft.).
- $M_u$  (Strength I): Factored design moment (kip-ft.).  
1.25 (M<sub>DC1</sub> + M<sub>DC2</sub>) + 1.5 M<sub>DW</sub> + 1.75  $M_L + IM$
- $\phi_r M_n$ : Compact composite positive moment capacity computed according to Article 6.10.7.1 or non-slender negative moment capacity according to Article A6.1.1 or A6.1.2 (kip-ft.).
- $f_s$  DC1: Un-factored stress at edge of flange for controlling steel flange due to vertical non-composite dead loads as calculated below (ksi).  
M<sub>DC1</sub> /  $S_{nc}$
- $f_s$  DC2: Un-factored stress at edge of flange for controlling steel flange due to vertical composite dead loads as calculated below (ksi).  
M<sub>DC2</sub> /  $S_c(3n)$  or M<sub>DC2</sub> /  $S_c(cr)$  as applicable.
- $f_s$  DW: Un-factored stress at edge of flange for controlling steel flange due to vertical composite future wearing surface loads as calculated below (ksi).  
M<sub>DW</sub> /  $S_c(3n)$  or M<sub>DW</sub> /  $S_c(cr)$  as applicable.
- $f_s$  ( $\zeta + IM$ ): Un-factored stress at edge of flange for controlling steel flange due to vertical composite live load plus impact loads as calculated below (ksi).  
 $M_L + IM$  /  $S_c(n)$  or  $M_L + IM$  /  $S_c(cr)$  as applicable.
- $f_s$  (Service II): Sum of stresses as computed below (ksi).  
 $f_{sDC1} + f_{sDC2} + f_{sDW} + 1.3 f_s(\zeta + IM)$
- $0.95R_n F_y f$ : Composite stress capacity for Service II loading according to Article 6.10.4.2 (ksi).
- $f_s$  (Total)(Strength I): Sum of stresses as computed below on non-compact section (ksi).  
1.25 ( $f_{sDC1} + f_{sDC2}$ ) + 1.5  $f_{sDW} + 1.75 f_s(\zeta + IM)$
- $\phi_r F_n$ : Non-Compact composite positive or negative stress capacity for Strength I loading according to Article 6.10.7 or 6.10.8 (ksi).
- $V_r$ : Maximum factored shear range in span computed according to Article 6.10.10.

BILL OF MATERIAL

Item	Unit	Total
Anchor Bolts, 1" $\phi$	Each	28
Anchor Bolts, 1 1/2" $\phi$	Each	14

Notes:  
 Space reinforcement in cap to miss anchor bolts.  
 Pour steps monolithically with cap.




**SEC. THRU ABUT.**  
**BILL OF MATERIAL**

Bar No.	Size	Length	Shape
h(E)	#5	12'-9"	—
h1(E)	#6	18'-4"	—
h2(E)	#5	10'-6"	—
p(E)	#7	18'-6"	—
p1(E)	#7	29'-10"	—
p2(E)	#5	5'-1"	—
p3(E)	#5	8'-11"	—
s2(E)	#5	13'-3"	□
s3(E)	#5	4'-0"	┌
s4(E)	#5	7'-0"	┌
* sp(E)	#4	2'-0"	⋈
u(E)	#6	10'-6"	□
v1(E)	#8	5'-11"	—
v2(E)	#5	9'-10"	—
v3(E)	#5	14'-11"	—
Structure Excavation	Cu. Yd.	138	
Concrete Structures	Cu. Yd.	28.7	
Reinforcement Bars, Epoxy Coated	Pound	5,210	
Furnishing Steel Piles, HP 14x102	Foot	600	
Driving Piles	Foot	600	
Test Pile, HP 14x102	Each	1	

For details of piles see sheet 30 of 36.  
 \* Length is height of spiral.


**PILE DATA**

Type: HP 14x102  
 Nominal Required Bearing: 535K  
 Factored Resistance Available: 294K  
 Est. Length: 75'  
 No. Production Piles: 8  
 No. Test Piles: 1




Order h1(E) and v3(E) full length. Cut as shown and use remainder of bars in opposite face.

**PLAN**






**ANCHOR BOLT LAYOUT**





Notes:  
 Space reinforcement in cap to miss anchor bolts.  
 Pour steps monolithically with cap.




**BILL OF MATERIAL**


Bar	No.	Size	Length	Shape
h(E)	48	#5	12'-9"	—
h1(E)	12	#6	18'-4"	—
h2(E)	4	#5	10'-6"	—
p(E)	10	#7	18'-6"	—
p1(E)	10	#7	29'-10"	—
p2(E)	4	#5	5'-1"	—
p3(E)	4	#5	8'-11"	—
s2(E)	45	#5	13'-3"	□
s3(E)	18	#5	4'-0"	┌
s4(E)	15	#5	7'-0"	┌
* sp(E)	9	#4	2'-0"	⋈
u(E)	8	#6	10'-6"	□
v1(E)	91	#8	5'-11"	—
v2(E)	8	#5	9'-10"	—
v3(E)	18	#5	14'-11"	—
Structure Excavation	Cu. Yd.		138	
Concrete Structures	Cu. Yd.		28.7	
Reinforcement Bars, Epoxy Coated	Pound		5,210	
Furnishing Steel Piles, HP 14x102	Foot		1,048	
Driving Piles	Foot		1,048	
Test Pile, HP 14x102	Each		1	


\* Length is height of spiral.  
 For details of piles see sheet 30 of 36.

**PILE DATA**  
 Type: HP 14x102  
 Nominal Required Bearing: 620 Kips  
 Factored Resistance Available: 341 Kips  
 Est. Length: 131'  
 No. Production Piles: 8  
 No. Test Piles: 1




Order h1(E) and v3(E) full length. Cut as shown and use remainder of bars in opposite face.






**ELEVATION**




**SECTION A-A**

Maximum Applied Service Bearing Pressure,  $Q_{max} = 2,100$  psf




**EXPANSION JOINT DETAIL**




**PLAN**

**RETAINING WALL DIMENSIONS**

Dimension	West Abut.		East Abut.	
	North	South	North	South
X	2'-10 <sup>7</sup> / <sub>8</sub> "	3'-2 <sup>1</sup> / <sub>8</sub> "	2'-10 <sup>5</sup> / <sub>8</sub> "	3'-1 <sup>3</sup> / <sub>4</sub> "
Y	4'-10 <sup>7</sup> / <sub>8</sub> "	5'-2 <sup>1</sup> / <sub>8</sub> "	4'-10 <sup>5</sup> / <sub>8</sub> "	5'-1 <sup>3</sup> / <sub>4</sub> "
Z	7'-10 <sup>7</sup> / <sub>8</sub> "	8'-2 <sup>1</sup> / <sub>8</sub> "	7'-10 <sup>5</sup> / <sub>8</sub> "	8'-1 <sup>3</sup> / <sub>4</sub> "



**BAR z(E)**



**FIELD CUTTING DIAGRAM**

Order bars shown full length. Cut as shown and use remainder of bars in opposite face.


**BILL OF MATERIAL  
4 WINGWALL EXTENSIONS**

Bar	No.	Size	Length	Shape	
h20(E)	80	#4	3'-8"	—	
v20(E)	20	#4	13'-2"	—	
z(E)	20	#4	6'-4"	┌	
Concrete Structures				Cu. Yd.	5.6
Reinforcement Bars, Epoxy Coated				Pound	460


Notes:  
 Space reinforcement in cap to miss anchor bolts.  
 Pour steps monolithically with cap.  
 For details of piles, see sheets 31 of 36.

**PILE DATA**

Type: Metal Shell Piles 14" x 0.250" Walls  
 Nominal Required Bearing: 413k  
 Factored Resistance Available: 227k  
 Est. Length: 67 ft.  
 No. Production Piles: 26  
 No. Test Piles: 1




**TOP PLAN**




**SEC. A-A**

**SEC. C-C**




**END VIEW**




**ELEVATION**  
(Looking East)



**BAR t1(E)**



**BAR n2(E)**  
**BARS n(E) & n1(E)**



**SEC. B-B**



\* In pairs top and bottom  
 \*\* Length is height of spiral  
 \*\*\* Splicing of reinforcement will not be allowed in this region

**BILL OF MATERIAL**


Bar	No.	Size	Length	Shape
h3(E)	12	#5	25'-9"	—
h4(E)	12	#5	19'-1"	—
h5(E)	4	#5	7'-4"	—
h6(E)	4	#5	6'-8"	—
h7(E)	5	#8	14'-9"	—
h8(E)	5	#8	21'-5"	—
h9(E)	24	#6	16'-3"	—
h10(E)	24	#6	11'-7"	—
n(E)	28	#8	6'-9"	U
n1(E)	28	#8	8'-9"	U
n2(E)	14	#6	9'-3"	U
p4(E)	16	#9	19'-1"	—
p5(E)	16	#9	25'-9"	—
p6(E)	6	#9	14'-6"	—
p7(E)	6	#9	21'-2"	—
p8(E)	12	#9	6'-2"	—
s5(E)	98	#5	14'-7"	□
s6(E)	72	#5	10'-0"	□
s7(E)	15	#5	7'-2"	□
s8(E)	49	#5	9'-10"	□
s9(E)	49	#6	19'-6"	□
s10(E)	325	#4	3'-11"	□
sp1(E)	4	#5	13'-9"	MM
t(E)	44	#8	14'-6"	L
t1(E)	50	#5	9'-6"	L
u1(E)	16	#6	11'-11"	L
u2(E)	24	#6	13'-5"	L
v4(E)	28	#8	10'-6"	U
v5(E)	28	#8	8'-6"	U
w(E)	20	#5	23'-5"	—
w1(E)	20	#5	16'-9"	—
Structure Excavation			Cu. Yd.	143
Concrete Structures			Cu. Yd.	120.2
Reinforcement Bars, Epoxy Coated			Pound	18,510
Furnishing Metal Shell Piles, 14" x .250"			Foot	1742
Driving Piles			Foot	1742
Test Pile, Metal Shells			Each	1

**A&B DIMENSIONS**


Bar	A	B
S6(E)	2'-2"	3'-11"
S7(E)	3'-2"	2'-0"
S8(E)	3'-2"	3'-4"
S9(E)	3'-2"	8'-2"




**BAR s10(E)**  
(alternate end for end)



**FOOTING PLAN**




**ANCHOR BOLT LAYOUT**




**BAR v4(E) & v5(E)**  
**BAR s5(E)**

**BARS u1(E) & u2(E)**




**STEEL PILE TABLE**

Designation	Depth d	Flange width br	Web and Flange thickness t	Encasement diameter A
HP 14x117	14 1/4"	14 7/8"	1 3/16"	30"
x102	14"	14 3/4"	1 1/16"	30"
x89	13 7/8"	14 3/4"	5/8"	30"
x73	13 5/8"	14 5/8"	1/2"	30"
HP 12x84	12 1/4"	12 1/4"	1 1/16"	24"
x74	12 1/8"	12 1/4"	5/8"	24"
x63	12"	12 1/8"	1/2"	24"
x53	11 3/4"	12"	7/16"	24"
HP 10x57	10"	10 1/4"	9/16"	24"
x42	9 3/4"	10 1/8"	7/16"	24"
HP 8x36	8"	8 1/8"	7/16"	18"




**ELEVATION**




**DETAIL "B"**

**WELDED COMMERCIAL SPLICE**




**ISOMETRIC VIEW**




**ELEVATION**

**PILE ENCASEMENT**




**ELEVATION**

**DETAIL D**




**WELDED PLATE FIELD SPLICE**




**SECTION A-A**

Note:  
Forms for encasement may be omitted when soil conditions permit.




**END VIEW**

Designation	F	F <sub>t</sub>	F <sub>w</sub>	W	W <sub>t</sub>	W <sub>w</sub>
HP 14x117	12 1/2"	1"	7/8"	7 3/4"	5/8"	1/2"
x102	12 1/2"	7/8"	3/4"	7 3/4"	5/8"	1/2"
x89	12 1/2"	3/4"	1 1/16"	7 3/4"	5/8"	1/2"
x73	12 1/2"	5/8"	9/16"	7 3/4"	5/8"	1/2"
HP 12x84	10"	7/8"	1 1/16"	6 1/2"	5/8"	1/2"
x74	10"	7/8"	1 1/16"	6 1/2"	5/8"	1/2"
x63	10"	5/8"	1/2"	6 1/2"	1/2"	3/8"
x53	10"	5/8"	1/2"	6 1/2"	1/2"	3/8"
HP 10x57	8"	3/4"	9/16"	5 1/4"	1/2"	3/8"
x42	8"	5/8"	9/16"	5 1/4"	1/2"	3/8"
HP 8x36	7"	5/8"	7/16"	4 1/4"	1/2"	3/8"




**ELEVATION**



**DETAIL A**

**H-PILE SHOE ATTACHMENT**



**ISOMETRIC VIEW**

**WELDED COMMERCIAL SPLICE ALTERNATE**

- \* Interrupt welds 1/4" from end of web and/or each flange.
- \*\* Remove portions of backup plates that extend outside the flanges.
- \*\*\* Weld size per pile shoe manufacturer (5/16" min.).

Note:  
The steel H-piles shall be according to AASHTO M270 Grade 50.

F-HP 1-27-12