

INDEX OF SHEETS

1	TITLE SHEET
2-4	LOCATION MAPS
5	INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES
6	SUMMARY OF QUANTITIES
7-10	STRUCTURAL REPAIRS LOC 1 (SN 016-1000, -1001)
11-16	STRUCTURAL REPAIRS LOC 2 (SN 016-0376, -1121)
17-19	STRUCTURAL REPAIRS LOC 3 (SN 016-0500, -1126)
20-21	STRUCTURAL REPAIRS LOC 4 (SN 016-0617)
22	STRUCTURAL REPAIRS LOC 5 (SN 016-0618)
23-24	STRUCTURAL REPAIRS LOC 6 (SN 022-0026)
25	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS

STATE STANDARDS

701006-02	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 4.5M (15') AWAY
701301-02	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701501-04	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701601-05	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701606-05	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701801-03	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901	TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION) AT (1-800)-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTREIC, TELEPHONE AND GAS UTILITIES, (48 HOUR NOTIFICATION IS REQUIRED).

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS

THE CONTRATOR SHALL CONTRACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORKS.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVE FROM BRIDGE INSPECTORS.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATEIRIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISED BASED UPON THE UNIT PRICE BID FOR THE WORK.

ALL STRUCTURAL STEEL SHALL CONFORM TO AASHTO CLASSIFICATION M-270 GR 36, UNLESS OTHERWISE NOTED.

REINFORCEMENT BARS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A706 GR 60 (IL MODIFIED), SEE SPECIAL PROVISIONS.

ALL STRUCTURAL STEEL SHALL BE PAINTED WITH THE INORGANIC ZINC RICH PRIMER PER AASHTO M300, TYPE 1, COST INCLUDED IN FURNISHING & ERECTING STRUCTURAL STEEL.

FILE NAME = c:\projects\dl20507\1171847.thdgn	USER NAME = mxdjjo	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			VARIOUS	2007-0071	VARIOUS	25	5
	PLOT SCALE = 50.0000 "/ IN.	CHECKED -	REVISED -							
	PLOT DATE = 12/27/2007	DATE -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT
										CONTRACT NO. 60C36