

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE- SFTY-2A					
CODE NO	ITEM	UNIT		COOK COUNTY					DUPAGE COUNTY
				LOC 1 016-1000 016-1001	LOC 2 016-1121 016-0376	LOC 3 016-0500 016-1126	LOC 4 016-0617	LOC 5 016-0618	LOC 6 022-0026
50102400	CONCRETE REMOVAL	CU YD	.3	.3					
50300225	CONCRETE STRUCTURES	CU YD	.3	.3					
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	200	200					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	70	70					
52100520	ANCHOR BOLTS, 1"	EACH	4	4					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	.51	.51	.51	.48	.48	.51
67100100	MOBILIZATION	L SUM	1	0.17	0.17	0.17	0.16	0.16	0.17
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1				0.5	0.5	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.5	0.5				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1			0.5			0.5
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1			1			
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	288	48	48	48	48	48	48
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	1399	58	317	104	105	315	440
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	382	24	96	230	12	20	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1			1			
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	15	11	4				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT							

12/27/2007 5:46:10 PM c:\pcc\120507\120507\120507\120507.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev.