F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	2007-047 I	MCHENRY	20	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO. 60D37

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN 90% FED. 10% STATE SFTY-2A					
20200100	EARTH EXCAVATION	CU YD	8500	8500					
31102100	SUB-BASE GRANULAR MATERIAL, TYPE C 4"	SQ YD	25500	25500					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	955	955					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	25500	25500					
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	300	300					
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, (SPECIAL) TANGENT	EACH	10	10					
63200310	GUARDRAIL REMOVAL	FOOT	800	800					
64200105	SHOULDER RUMBLE STRIP	FOOT	70500	70500					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	910	910					
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	20	20					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	10	10					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	910	910					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 12/26/2007

12/26/2007
c:\pwworking\d1\009088\section_qq.dgn