

SUMMARY OF QUANTITIES

URBAN
90% FED.
10% STATE

PAY ITEM NUMBER	PAY ITEM	UNITS	TOTAL QUANTITY	ROADWAY SFTY-4A
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	44	44
20400800	FURNISHED EXCAVATION	CU YD	117	117
21001000	FABRIC FOR GROUND STABILIZATION GEOTECHNICAL	SQ YD	2,265	2,265
25100630	EROSION CONTROL BLANKET	SQ YD	416	416
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	2,265	2,265
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	27	27
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	413	413
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	3
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	50	50
63200310	GUARDRAIL REMOVAL	FOOT	2,774	2,774
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
78200410	GUARDRAIL MARKERS, TYPE A	EACH	153	153
78201000	TERMINAL MARKERS - DIRECT APPLIED	EACH	50	50
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	106	106
X2503100	MOWING AND	UNIT	241	241
X6330100	REMOVE / RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL	EACH	1	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
X0325917	TURF ESTABLISHMENT	SQ YD	416	416

⊙ 100% STATE
X SPECIALTY ITEMS



GRAEF, ANHALT, SCHLOEMER & ASSOCIATES, INC.
CHICAGO, ILLINOIS

FILE NAME =	USER NAME = USER	DESIGNED - MW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - EUB	REVISED -			303	2007-050 GRR	LAKE	13	3	
		CHECKED - RJS	REVISED -			CONTRACT NO. 60D40					
		DATE - 12/03/2007	REVISED -			SCALE: N.T.S.	SHEET NO. 3 OF 13 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS

1/6/08