


SCHEDULE OF QUANTITIES

LOCATION	EXCAV. GRADING SHOULDER	AGG. SHLDRS, TYPE B, 6"	AGG. WEDGE, TYPE B	GUARDRAIL, TYPE A	TBT, TYPE 2	TBT, TYPE 1, SPL (TANGENT)	GUARDRAIL REMOVAL	REMOVE & RE-ERECT TBT TY 1 SP	EARTH EXCAVATION	EMBANKMENT	FURNISHED EXCAVATION	MOWING	TURF ESTABLISHMENT	EROSION CONTROL BLANKET	FABRIC FOR GROUND STABILIZATION
	UNIT=100'	SQ. YD.	TON	FOOT	EACH	EACH	FOOT	EACH	CU YD	CU YD	CU YD	UNIT	SQ YD	SQ YD	SQ YD
1 N	1.35	76	2.4			2	86			15.7	15.7	12	52	52	76
1 S	2.15	118	3.1	50		2	121			12.1	12.1	16	63	63	118
2				37.5	1		50								
3 N	2.05	77		37.5		2	113			6.7	6.7	9	24	24	77
3 S	2.05	112	3.0	37.5		2	106		0.4	5.2	4.9	11	9	9	112
4	2.29	126	5.7	112.5	1		76	1	3.2	12.4	9.7	17	59	59	126
5	0.84	49				1	50					4			49
6	0.84	33				1	50			1.7	1.7	4	13	13	33
7	0.79	42				1	50			1.7	1.7	5	8	8	42
8	0.77	58		25	1	1	75			16.1	16.1	10	56	56	58
9	0.84	35				1	50			2.6	2.6	4	5	5	35
10 N	0.84	58				1	50					5			58
10 S	1.70	62		50		2	151			9.7	9.7	7	13	13	62
11	0.84	30				1	50					3			30
12	0.84	36				1	50					3			36
13	0.63	31				1	50					3			31
14 N	0.79	31				1	50			3	3	3	5	5	31
14 S	1.68	61				2	102					5			61
15 N	1.89	83		50		2	144					7			83
15 S	0.93	46				1	50					4			46
16	0.84	45				1	50					4			45
17	0.60	38				1	50			8	8	8	56	56	38
18	0.50	23				1	50					2			23
19	0.50	26				1	50					2			26
20	1.04	61				2	88					5			61
21	2.16	138				2	94					12			138
22	0.60	38				1	39					3			38
23	0.67	40				1	50					4			40
24	0.84	35				1	50					3			35
25	0.94	47				1	50					4			47
26 N	1.44	60	2.1	12.5		1	81					5			60
26 S	1.86	89	2.9			2	101					8			89
27 N	0.90	40	1.4			1	50					4			40
27 S	0.96	49	1.4			1	50					4			49
28	0.84	33				1	50					3			33
29	0.96	48				1	50					4			48
30	1.68	91				2	97					8			91
31	0.76	59	1.0			1	50					5			59
32	0.56	54				1	50			24.9	24.9	10	53	53	54
33	0.90	45	2.6			1	50					4			45
34	0.62	42	1.5			1	50					4			42
TOTAL:	44	2,265	27	413	3	50	2,774	1	4	120	117	241	416	416	2,265

P:\Jobs\2006\20063028-38\CAD\DOT Trans\dgn\00\ILL-173\Schedule of Quantities.dgn
 1/7/2008 10:53:37 AM



FILE NAME =	USER NAME = _USER_	DESIGNED -	REVISED -
ht:\Jobs\2006\20063028-38\CAD\DOT Trans\dgn\00\ILL-173\Schedule of Quantities.dgn		DRAWN -	REVISED -
PLOT SCALE = 10.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 1/7/2008		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 4 OF 13 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	2007-050 GRR	LAKE	13	4
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		CONTRACT NO. 60D40		

1/8/08