

GENERAL NOTES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
JOB	10810-1.0610-2R	ROCK ISLAND	210	4
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS	FED. AID PROJECT	

UTILITIES

38. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING LISTED UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS ARE MEMBERS OF JULIE:

SBC AMERITECH TELEPHONE CO.
 CITY OF ROCK ISLAND
 MIDAMERICAN ENERGY CO.
 MEDIACOM
 MCI WORLD COM

39. FOLLOWING ARE THE KNOWN UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS WHICH ARE NOT MEMBERS OF JULIE AND SHOULD BE NOTIFIED INDIVIDUALLY BY THE CONTRACTOR:

KYLE LORENZ
 IDOT - DISTRICT 2
 819 DEPOT AVENUE
 DIXON, IL 21021
 (815) 284-5469

40. CADD DATA WILL BE AVAILABLE TO CONTRACTORS AND CONSULTANTS WORKING ON THIS PROJECT. THIS INFORMATION WILL BE PROVIDED UPON REQUEST AS MICROSTATION CADD FILES AND GEOPAK COORDINATE GEOMETRY FILES ONLY. IF DATA IS REQUIRED IN OTHER FORMATS IT WILL BE THE CONTRACTOR OR CONSULTANT'S RESPONSIBILITY TO MAKE THESE CONVERSIONS. IF ANY DISCREPANCY OR INCONSISTENCY ARISES BETWEEN THE ELECTRONIC DATA AND THE INFORMATION ON THE HARD COPY, THE INFORMATION ON THE HARD COPY SHOULD BE USED. CONTACT THE DISTRICT'S PROJECT ENGINEER TO REQUEST THESE FILES.

41. HEIGHT AND WIDTH OF MEDIAN BARRIER SHALL TRANSITION FROM ROADWAY TO BRIDGE SECTIONS OVER A DISTANCE OF 10'. THE TRANSITION SHALL OCCUR ON THE ROADWAY SECTION ADJACENT TO THE APPROACH PAVEMENT AT EACH LOCATION.

42. IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 SHALL BE ABSORB 350

COMMITMENTS

1. NO TREES WILL BE REMOVED DURING THIS PROJECT CONSTRUCTION
2. THERE ARE SEVERAL WETLANDS IN THE PROJECT AREA WHICH ARE SHOWN ON THE CONTRACT PLANS. NO CONSTRUCTION ACTIVITIES, INCLUDING EQUIPMENT AND MATERIAL STORAGE, OR DRIVING OF VEHICLES AND EQUIPMENT SHALL TAKE PLACE BEYOND THE CONSTRUCTION LIMITS SHOWN ON THE CONTRACT PLANS SO AS TO AVOID ANY WETLAND IMPACTS. WETLANDS CAN BE FOUND ON EROSION AND SEDIMENT CONTROL SHEETS 68-75.

PLT DATE * DATE *
 PLOT SCALE * SCALE *
 USER NAME * USER *

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: NONE DATE
DRAWN BY AMK		CHECKED BY MGZ