CONTRACT NO. 64814

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
308	1HB,HB-1,VB,HB-2R	ROCK ISLAND	210	6
STA.		TO STA.		
FED. ROAD DIST. NO. 2	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	URBAN 80% FED. 20% STATE UNITS	TOTAL	BRF ROADWAY BITUMINOUS I000	BRF ROADWAY CONCRETE J000	BRF BRIDGE 31ST SB X271-2A	BHF BRIDGE 31ST NB X271-2A	BHF BRIDGE RR X171-2A	BRF BRIDGE 18TH X271-2A	BRF BRIDGE 7TH X271-2A	BRF GUARDRAIL SFTY-3J	BRF LIGHTING Y030-1E
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	2			1	1					
50102400	CONCRETE REMOVAL	CU YD	62					62				
50104650	SLOPE WALL REMOVAL	SQ YD	1825					1825				
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1					1				
50157300	PROTECTIVE SHIELD	SQ YD	3810			552	552	797	944	965		
50200100	STRUCTURE EXCAVATION	CU YD	920			118	122	348	194	138		
50300100	FLOOR DRAINS	EACH	2					2				
50300225	CONCRETE STRUCTURES	CU YD	1237			205.3	204.6	69.7	309.7	447.7		
50300254	RUBBED FINISH	SQ FT	10488			1699	1701		3132	3956		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1738.8			201.9	201.9	648.7	341	345.3		
50300260	BRIDGE DECK GROOVING	SQ YD	4621			539.5	539.5	1783	875	884		
50300280	CONCRETE ENCASEMENT	CU YD	63.4			15.4	15.4		23.4	9.2		
50300300	PROTECTIVE COAT	SQ YD	5985			674.5	674.5	2267	1179	1190		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			0.15	0.15		0.3	0.4		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	17820					17820				
50500505	STUD SHEAR CONNECTORS	EACH	18558			1872	1872	7872	3471	3471		
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	28					28				
50501110	STRUCTURAL STEEL REMOVAL	POUND	13820					13820				
50600300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1					1				
50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUE	L SUM	1					1				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	489960			60890	61090	160070	96730	111180		
50800515	BAR SPLICERS	EACH	2396			80	80	1013	593	630		
51100100	SLOPE WALL 4 INCH	SQ YD	132					132				
51100500	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	3474					3474				
51201600	FURNISHING STEEL PILES HP12X53	FOOT	4058			976	976		1482	624		
51201900	FURNISHING STEEL PILES HP14X89	FOOT	3318			1152	1152		1014			
51202305	DRIVING PILES	FOOT	7376			2128	2128		2496	624		
51204650	PILE SHOES	EACH	146			34	34		52	26		
51205200	TEMPORARY SHEET PILING	SQ FT	147					147				
51500100	NAME PLATES	EACH	5			1	1	1	1	1		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	255					255				
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	14					14				
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	14					14				
52100520	ANCHOR BOLTS, 1"	EACH	360			48	48	56	104	104		
54215547	METAL END SECTIONS 12"	EACH	10	10								
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	783	783								
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	74	74								

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: NONE

DATE

DRAWN BY AMK

CHECKED BY MGZ

PLOT DATE = $DATE$
FILE NAME = $FILE$
PLOT SCALE = $SCALE$
USER NAME = $USER$