

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
308	10R,10B-1,10B,10B-2R	ROCK ISLAND	210	12
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS	FED. AID PROJECT	

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION	OFFSET	REMARKS
1	1469+65.39	RT	
1	1470+07.28	LT	
1	1471+32.87	RT	
1	1471+75.68	LT	
1	1486+58.45	LT	
1	1487+58.78	LT	
1	1499+05.46	RT	
1	1500+50.06	RT	
1	1501+83.33	RT	
1	1504+32.78	LT	
1	1506+37.28	LT	
1	1508+97.87	LT	
1	1511+38.69	LT	
1	1511+46.86	RT	
1	1513+00.00	RT	
1	1514+17.34	RT	
1	1514+94.42	RT	
1	1515+09.69	RT	
1	1515+71.29	RT	
1	1516+93.92	LT	
1	1518+53.90	LT	
1	1519+50.04	RT	
1	1519+95.19	LT	
1	1520+10.67	RT	
1	1540+57.49	LT	
1	1540+74.96	LT	
1	1541+00.00	LT	
1	1542+55.39	LT	
1	1543+56.67	RT	
1	1544+00.04	LT	
1	1546+41.38	RT	
1	1548+02.77	RT	
1	1552+26.05	LT	
1	1552+98.77	LT	
1	1553+20.08	LT	
1	1553+72.10	LT	
1	1556+53.59	LT	
1	1559+55.70	LT	
1	1560+75.08	LT	
39 TOTAL			

31100300 SUB-BASE GRANULAR MATERIAL, TYPE A 4"

SQ YD	LOCATION	SHEET	REMARKS
0	1451+00.00 TO 1457+00.00	SHEET 1	
0	1457+00.00 TO 1463+00.00	SHEET 2	
0	1463+00.00 TO 1469+00.00	SHEET 3	
0	1469+00.00 TO 1475+00.00	SHEET 4	
0	1475+00.00 TO 1481+00.00	SHEET 5	
215	1481+00.00 TO 1487+00.00	SHEET 6	
474	1487+00.00 TO 1493+00.00	SHEET 7	
439	1493+00.00 TO 1499+00.00	SHEET 8	
355	1499+00.00 TO 1504+00.00	SHEET 9	
363	1504+00.00 TO 1510+00.00	SHEET 10	
357	1510+00.00 TO 1515+00.00	SHEET 11	
455	1515+00.00 TO 1521+00.00	SHEET 12	
474	1521+00.00 TO 1527+00.00	SHEET 13	
508	1527+00.00 TO 1533+00.00	SHEET 14	
485	1533+00.00 TO 1539+00.00	SHEET 15	
469	1539+00.00 TO 1545+00.00	SHEET 16	
570	1545+00.00 TO 1551+00.00	SHEET 17	
455	1551+00.00 TO 1557+00.00	SHEET 18	
341	1557+00.00 TO 1561+63.55	SHEET 19	
5,960 TOTAL			

40600635 LEVELING BINDER (MACHINE METHOD), N70

TON	LOCATION	OFFSET	DIRECTION	REMARKS
16.0	IAIS RR		SB	SOUTH OF IAIS RR
11.6	IAIS RR		NB	SOUTH OF IAIS RR
1.6	IAIS RR		NB	NORTH OF IAIS RR
6.6	18TH AVE BRIDGE		SB	SOUTH OF 18TH
7.2	18TH AVE BRIDGE		NB	SOUTH OF 18TH
20.8	18TH AVE BRIDGE		SB	NORTH OF 18TH
22.8	18TH AVE BRIDGE		NB	NORTH OF 18TH
2.0	7TH AVE BRIDGE		SB	NORTH OF 7TH
1.9	7TH AVE BRIDGE		NB	NORTH OF 7TH
91 TOTAL				

28100125 STONE RIPRAP, CLASS B3

SQ YD	LOCATION	OFFSET	REMARKS
13.33	1547+98.12	82' RT	(10'X12')
13.33	1546+36.39	82' RT	(10'X12')
13.33	1469+58.74	99' RT	(10'X12')
13.33	1470+02.58	122' LT	(10'X12')
13.33	1471+28.33	106' RT	(10'X12')
13.33	1471+72.61	112' LT	(10'X12')
13.33	1506+30.48	107' LT	(10'X12')
13.33	1508+94.96	108' LT	(10'X12')
13.33	1516+87.71	99' LT	(10'X12')
13.33	1518+48.53	99' LT	(10'X12')
134 TOTAL			

40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50

TON	LOCATION	SHEET	REMARKS
0	1451+00.00 TO 1457+00.00	SHEET 1	
0	1457+00.00 TO 1463+00.00	SHEET 2	
95	1463+00.00 TO 1469+00.00	SHEET 3	
99	1469+00.00 TO 1475+00.00	SHEET 4	
78	1475+00.00 TO 1481+00.00	SHEET 5	
77	1481+00.00 TO 1487+00.00	SHEET 6	
74	1487+00.00 TO 1493+00.00	SHEET 7	
83	1493+00.00 TO 1499+00.00	SHEET 8	
124	1499+00.00 TO 1504+00.00	SHEET 9	
63	1504+00.00 TO 1510+00.00	SHEET 10	
112	1510+00.00 TO 1515+00.00	SHEET 11	
82	1515+00.00 TO 1521+00.00	SHEET 12	
31	1521+00.00 TO 1527+00.00	SHEET 13	
0	1527+00.00 TO 1533+00.00	SHEET 14	
0	1533+00.00 TO 1539+00.00	SHEET 15	
23	1539+00.00 TO 1545+00.00	SHEET 16	
69	1545+00.00 TO 1551+00.00	SHEET 17	
5	1551+00.00 TO 1557+00.00	SHEET 18	
0	1557+00.00 TO 1561+63.55	SHEET 19	
1,015 TOTAL			

PLOT DATE * * * * *
 FILE NAME * * * * *
 USER NAME * * * * *

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: NONE DRAWN BY JW CHECKED BY MGZ

SCHEDULE OF QUANTITIES