

SCHEDULE OF QUANTITIES

20100110	<u>TREE REMOVAL (6 TO 15 UNITS DIAMETER)</u>			
	UNIT	LOCATION		OFFSET
		<u>IL 65</u>		
	11	LT	100+66	52
	12	LT	100+99	52
	14	LT	100+99	52
	<u>7</u>	LT	100+99	40
TOTAL	44			

20100500	<u>TREE REMOVAL ACRES</u>		
	ACRE	LOCATION	
		<u>IL 64</u>	
	<u>0.25</u>	RT	97+00 - 105+59
TOTAL	0.25		

21301052	<u>EXPLORATION TRENCH 52" DEPTH</u>			
	FOOT	LOCATION		
		<u>IL 64</u>		
	50	LT	101+49	FIELD TILE LOCATION
	<u>50</u>	LT	104+95	FIELD TILE LOCATION
TOTAL	100			

25000210	<u>SEEDING, CLASS 2A</u>		
	ACRE	LOCATION	
		<u>IL 64</u>	
	<u>0.7</u>	LT&RT	97+00 - 105+80
TOTAL	0.7		

25000310	<u>SEEDING, CLASS 4</u>		
	ACRE	LOCATION	
		<u>IL 64</u>	
	<u>0.8</u>	LT&RT	97+00 - 105+80
TOTAL	0.8		

25000750	<u>MOWING</u>		
	ACRE	LOCATION	
		<u>IL 64</u>	
	<u>1.5</u>	LT&RT	97+00 - 105+80
TOTAL	1.5		

25100115	<u>MULCH, METHOD 2</u>		
	ACRE	LOCATION	
		<u>IL 64</u>	
	<u>1.5</u>	LT&RT	97+00 - 105+80
TOTAL	1.5		

25100630	<u>EROSION CONTROL BLANKET</u>		
	SQ. YD.	LOCATION	
		<u>IL 64</u>	
	424	LT	98+97 - 105+33
	<u>57</u>	RT	101+75 - 102+50
TOTAL	481		

28000250	<u>TEMPORARY EROSION CONTROL SEEDING (THREE APPLICATIONS)</u>		
	POUND	LOCATION	
		<u>IL 64</u>	
	<u>450</u>	LT&RT	97+00 - 105+80
TOTAL	450		