

# SCHEDULE OF QUANTITIES

28000300 TEMPORARY DITCH CHECKS

28000500 INLET AND PIPE PROTECTION

EACH LOCATION

IL 64

1	LT	97+11
1	LT	97+22
1	LT	97+58
1	LT	99+17
1	LT	99+66
1	LT	100+14
1	LT	100+64
1	LT	101+13
1	LT	101+61
1	LT	102+04
1	LT	102+46
1	LT	102+85
1	LT	103+23
1	LT	103+60
1	LT	103+97
1	LT	104+33
1	LT	104+69
1	LT	105+03
1	RT	97+15
1	RT	97+36
1	RT	97+65
1	RT	97+95
1	RT	98+42
1	RT	98+91
1	RT	99+41
1	RT	99+91
1	RT	100+40
1	RT	100+88
1	RT	101+37
1	RT	101+77
1	RT	101+91
1	RT	103+14
1	RT	104+13
1	RT	104+49
1	RT	104+84
1	RT	105+12

TOTAL 36

28000400 PERIMETER EROSION BARRIER

FOOT LOCATION

IL 64

<u>129</u>	RT	102+00 - 103+00
------------	----	-----------------

TOTAL 129

EACH LOCATION

IL 64

1	LT	97+74
1	RT	103+27
1	LT	105+27

TOTAL 3

28100107 STONE RIPRAP, CLASS A4

SQ YD LOCATION

IL 64

<u>13</u>	RT	105+30	(8' X 15')
-----------	----	--------	------------

TOTAL 13

28200200 FILTER FABRIC

SQ YD LOCATION

IL 64

<u>13</u>	RT	105+30	(8' X 15')
-----------	----	--------	------------

TOTAL 13

35101400 AGGREGATE BASE COURSE TYPE B

TON LOCATION

IL 64

65	LT	98+00	FE	(8" DEPTH)
63	LT	98+64	FE	(8" DEPTH)
61	RT	103+50	FE	(8" DEPTH)
<u>68</u>	LT&RT	105+30 - 105+80	SIDEROAD RETURNS	(12" DEPTH)

TOTAL 257

40600990 TEMPORARY RAMP

SQ YD LOCATION

IL 64

29	LT&RT	105+20 - 105+30
<u>29</u>	LT&RT	105+65 - 105+75

TOTAL 58