

# SCHEDULE OF QUANTITIES

40603315	<u>HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N70</u>				
	TON	LOCATION			
		<u>IL 64</u>			
	10	LT	105+30 - 105+80	SIDEROAD RETURN	(PLACED IN 2 LIFTS)
	6	RT	105+30 - 105+80	SIDEROAD RETURN	(PLACED IN 2 LIFTS)
	<u>31</u>	LT&RT	105+20 - 105+75	PATCH AREA	(PLACED IN 2 LIFTS)
TOTAL	47				

44201383	<u>CLASS C PATCHES, TYPE IV, 12"</u>				
	SQ YD	LOCATION			
		<u>IL 64</u>			
	<u>160</u>	LT&RT	105+20 - 105+75		
TOTAL	160				

48100100	<u>AGGREGATE SHOULDERS, TYPE A</u>				
	TON	LOCATION			
		<u>IL 64</u>			
	287	LT	97+00 - 105+80	(6" DEPTH)	
	<u>321</u>	RT	97+01 - 105+81	(6" DEPTH)	
TOTAL	608				

50100300	<u>REMOVAL OF EXISTING STRUCTURES NO. 1</u>				
	EACH	LOCATION			
		<u>IL 64</u>			
	<u>1</u>	LT&RT	105+66		
TOTAL	1				

50105200	<u>REMOVE EXISTING CULVERTS</u>				
	EACH	LOCATION			
		<u>IL 64</u>			
	1	LT	105+19		
	<u>1</u>	RT	105+51		
TOTAL	2				

54207165	<u>PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL EQUIVALENT ROUND - SIZE 30"</u>				
	FOOT	LOCATION			
		<u>IL 64</u>			
	<u>58</u>	LT&RT	105+30		
TOTAL	58				

542D0220	<u>PIPE CULVERTS, CLASS D, TYPE 1, 15"</u>		
	FOOT	LOCATION	
		<u>IL 64</u>	
	<u>120</u>	LT	98+35
TOTAL	120		

54213450	<u>END SECTION, 15"</u>		
	EACH	LOCATION	
		<u>IL 64</u>	
	<u>2</u>	LT	98+35
TOTAL	2		

54214725	<u>PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL EQUIVALENT ROUND - SIZE 30"</u>		
	EACH	LOCATION	
		<u>IL 64</u>	
	<u>2</u>	LT&RT	105+30
TOTAL	2		

61100605	<u>MISCELLANEOUS CONCRETE</u>		
	CU YD	LOCATION	
		<u>IL 64</u>	
	<u>1</u>	AT FIELD TILE OUTLET LOCATIONS (APPROXIMATE LOCATIONS 101+/-50 & 105+/-00)	
TOTAL	1		

61101009	<u>STORM SEWERS PROTECTED, CLASS A 8"</u>		
	FOOT	LOCATION	
		<u>IL 64</u>	
	<u>50</u>	AT FIELD TILE OUTLET LOCATIONS (APPROXIMATE LOCATIONS 101+/-50 & 105+/-00)	
TOTAL	50		

61133100	<u>FIELD TILE JUNCTION VAULTS, 2' DIAMETER</u>		
	EACH	LOCATION	
		<u>IL 64</u>	
	<u>2</u>	AT FIELD TILE OUTLET LOCATIONS (APPROXIMATE LOCATIONS 101+/-50 & 105+/-00)	
TOTAL	2		