

EARTH WORK SCHEDULE

LOCATION	20200100 EARTH EXC (CUT) CU YD	EARTH EXC ADJ SHRINK 25% CU YD	EMBANK (FILL) CU YD	EARTH WORK BALANCE WASTE (+) SHORTAGE (-) CU YD
97 + 00 - 100 + 00	2338	1753	68	1685
100 + 00 - 105 + 80	4045	3034	418	2616
TOTAL	6383	4787	486	4301