

63100087 TRAFFIC BARRIER TERMINAL, TYPE 6A

Location	Sta.	EACH	Remarks
<b>US 6</b>			
665+57.5	- 666+03.2	RT	1
665+57.5	- 666+03.2	LT	1
667+35.2	- 667+80.9	RT	1
667+35.2	- 667+80.9	LT	1
		<b>US 6 Total =</b>	<b>4</b>
<b>IL 78</b>			
881+27.6	- 881+73.3	RT	1
881+27.6	- 881+73.3	LT	1
883+62.4	- 884+08.1	RT	1
883+62.4	- 884+08.1	LT	1
		<b>IL 78 Total =</b>	<b>4</b>
		<b>Grand Total =</b>	<b>8</b>

63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

Location	Sta.	EACH	Remarks
<b>US 6</b>			
664+70.0	- 665+20.0	LT	1
669+05.9	- 669+55.9	LT	1
		<b>US 6 Total =</b>	<b>2</b>
		<b>Grand Total =</b>	<b>2</b>

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

Location	Sta.	EACH	Remarks
<b>US 6</b>			
663+95.0	- 664+45.0	RT	1
668+18.4	- 668+68.4	RT	1
		<b>US 6 Total =</b>	<b>2</b>
<b>IL 78</b>			
880+40.1	- 880+90.1	RT	1
880+77.6	- 881+27.6	LT	1
884+08.1	- 884+58.1	RT	1
884+45.6	- 884+95.6	LT	1
		<b>IL 78 Total =</b>	<b>4</b>
		<b>Grand Total =</b>	<b>6</b>

63200310 GUARDRAIL REMOVAL

Location	Sta.	EQUI	Remarks
<b>US 6</b>			
664+19.5	- 666+03.2	RT	183.7
664+94.4	- 666+03.2	LT	108.1
667+35.3	- 668+43.4	RT	108.4
667+35.3	- 669+42.4	LT	207.6
		<b>US 6 Total =</b>	<b>607.7</b>
<b>IL 78</b>			
880+32.9	- 881+73.3	RT	139.5
880+71.2	- 881+73.3	LT	101.8
883+62.3	- 884+39.5	RT	76.7
883+62.3	- 885+02.3	LT	139.4
		<b>IL 78 Total =</b>	<b>457.3</b>
		<b>Grand Total =</b>	<b>1065.1</b>

63500105 DELINEATORS

Location	Sta.	EACH	Remarks
<b>US 6</b>			
663+95.0		RT	1
664+70.0		LT	1
668+70.2		RT	1
669+57.7		LT	1
		<b>US 6 Total =</b>	<b>4</b>
<b>IL 78</b>			
880+40.1		RT	1
880+77.6		LT	1
884+58.1		RT	1
884+95.6		LT	1
		<b>IL 78 Total =</b>	<b>4</b>
		<b>Grand Total =</b>	<b>8</b>

66700305 PERMANENT SURVEY MARKERS, TYPE II

Location	Sta.	Offset	EACH	Remarks
<b>US 6 &amp; IL 78 Total =</b>				<b>4</b>
<b>Grand Total =</b>				<b>4</b>

70106700 TEMPORARY RUMBLE STRIP

Location	Sta.	EACH	Remarks
<b>US 6</b>			
644+35.6			1
649+35.6			1
654+35.6			1
679+13.0			1
684+13.0			1
689+13.0			1
		<b>US 6 Total =</b>	<b>6</b>
<b>IL 78</b>			
860+11.6			1
865+11.6			1
870+11.6			1
895+00.7			1
900+00.7			1
905+00.7			1
		<b>IL 78 Total =</b>	<b>6</b>
		<b>Grand Total =</b>	<b>12</b>

70300100 SHORT-TERM PAVEMENT MARKING

Location	Sta.	to	Sta.	EQUI	Remarks
<b>US 6</b>					
661+22.9	-	672+50.0	LT	338.1	CL skip dash - Yellow (3 applications)
661+22.9	-	672+50.0	LT	338.1	White Edge Line (3 applications)
661+22.9	-	672+50.0	RT	338.1	White Edge Line (3 applications)
				<b>US 6 Total =</b>	<b>1014.4</b>
<b>IL 78</b>					
881+01.1	-	884+34.5	LT	100.0	CL solid stripe - Yellow (3 applications)
881+01.1	-	884+34.5	LT	100.0	White Edge Line (3 applications)
881+01.1	-	884+34.5	RT	100.0	White Edge Line (3 applications)
				<b>IL 78 Total =</b>	<b>300.1</b>
				<b>Grand Total =</b>	<b>1314.5</b>

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

Location	Sta.	EQUI	Remarks
<b>US 6</b>			
662+99.1	- 670+59.1		760.0
		<b>US 6 Total =</b>	<b>760.0</b>
<b>IL 78</b>			
878+91.3	- 886+20.0		728.8
878+92.5	- 886+15.0		722.5
		<b>IL 78 Total =</b>	<b>1451.3</b>
		<b>Grand Total =</b>	<b>2211.2</b>

70300570 PAVEMENT MARKING TAPE, TYPE III 24"

Location	Sta.	EQUI	Remarks
<b>US 6</b>			
661+35.6			12.0
672+12.0			12.0
		<b>US 6 Total =</b>	<b>24.0</b>
<b>IL 78</b>			
877+11.6			12.0
888+00.7			12.0
		<b>IL 78 Total =</b>	<b>24.0</b>
		<b>Grand Total =</b>	<b>48.0</b>

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

Location	Sta.	EQUI	Remarks
<b>US 6</b>			
661+33.0	- 672+14.0		450.4
661+46.0	- 671+52.0		336.0
662+99.1	- 670+59.1		253.3
661+96.0	- 672+02.0		336.0
661+35.6			24.0
672+12.0			24.0
661+22.9	- 672+50.0	LT	37.6
661+22.9	- 672+50.0	LT	37.6
661+22.9	- 672+50.0	RT	37.6
		<b>US 6 Total =</b>	<b>1536.5</b>
<b>IL 78</b>			
877+10.0	- 888+03.0		455.4
878+91.3	- 886+20.0		242.9
878+92.5	- 886+15.0		240.8
877+76.8	- 887+90.6		338.7
877+21.7	- 887+34.9		338.7
877+11.6			24.0
888+00.7			24.0
881+01.1	- 884+34.5	LT	11.1
881+01.1	- 884+34.5	LT	11.1
881+01.1	- 884+34.5	RT	11.1
		<b>IL 78 Total =</b>	<b>1697.8</b>
		<b>Grand Total =</b>	<b>3234.3</b>

\* FAP 22 (IL 78) & FAS 1247 (US 6) \*\* (125BR-1)D & (6BR)D

FILE NAME =	USER NAME = grantpin	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\projects\p205207\d05007.dgn		DRAWN -	REVISED -					*	**	HENRY	80	13
		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 64D10				
		DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							