

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: Y007

CODE NO.	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITY
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	10.4
20400800	FURNISHED EXCAVATION	CU YD	372
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	80
48203033	HOT-MIX ASPHALT SHOULDERS, 9"	SQ YD	520
50102400	CONCRETE REMOVAL	CU YD	38
50200100	STRUCTURE EXCAVATION	CU YD	372
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7350
54003000	CONCRETE BOX CULVERTS	CU YD	44
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	150
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	30
63200310	GUARDRAIL REMOVAL	FOOT	180
67100100	MOBILIZATION	L SUM	1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	120
X0323115	REFLECTOR MARKERS, TYPE A	EACH	8
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1368
X0321781	MECHANICAL SPLICE	EACH	68
Z0073400	TEMPORARY SUPPORT SYSTEM	EACH	2

*SPECIALTY ITEMS