CONTRACT NO. 70389

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
749	(9BR)BR	EDGAR	31	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY HBBRP TWO-LANE RURAL ROADWAY 80% FEDERAL 20% STATE X080-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	14
20200100	EARTH EXCAVATION	CU YD	415
20400800	FURNISHED EXCAVATION	CU YD	634
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	750
25000200	SEEDING, CLASS 2	ACRE	1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90
25100115	MULCH, METHOD 2	ACRE	1
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100
28000300	TEMPORARY DITCH CHECKS	EACH	6
28000400	PERIMETER EROSION BARRIER	FOOT	305
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	60
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	231
4060331O	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	93
48101200	AGGREGATE SHOULDERS, TYPE B	TON	60
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	0.7
50300225	CONCRETE STRUCTURES	CU YD	0.8
50300260	BRIDGE DECK GROOVING	SQ YD	520
50300300	PROTECTIVE COAT	SQ YD	520
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	2840
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	1817
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6600
* 50901050	STEEL RAILING, TYPE SM	FOOT	294
* 51500100	NAME PLATES	EACH	1
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	375
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	505
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	956

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY HBBRP TWO-LANE RURAL ROADWAY 80% FEDERAL 20% STATE X080-2A
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	319
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	956
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2
* 78200400	GUARDRAIL REFLECTORS	EACH	12
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	48
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	12
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	520

* DENOTES SPECIALTY ITEM

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 1 OF 1

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 12/14/2007
FILE NAME = c:\pwcgeis\d562304 (c8)\final plans 04.05.2007\drawings\quantitiesummary.dgn
PLOT SCALE = 1 / 1 in.
USER NAME = calliavo

BLANK, WESSELINK, COOK & ASSOCIATES ENGINEERS - CONSULTANTS DECATUR, ILLINOIS

F.A.P. 749 (IL RTE. 133) SECTION (9BR)BR

EDGAR COUNTY