CONTRACT NO. 72B42

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| * | ** | *** | 20 | 3 |

STA. _____ TO STA. _____

FED. ROAD DIST. NO. _ | ILLINOIS | FED. AID PROJECT

* - VARIOUS
** - D-6 SIGNING & STRIPING 2008
*** - ADAMS, BROWN, CASS, CHRISTIAN, HANCOCK, LOGAN, MACOUPIN, MASON, MONTGOMERY, MORGAN, PIKE, SANGAMON, SCHUYLER & SCOTT.

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

| CODE NO. | ITEM | UNIT | VARIOUS ROUTES VARIOUS COUNTIES Y002-1C 90% FED/10% STATE | VARIOUS ROUTES VARIOUS COUNTIES SFTY-1D 90% FED/10% STATE | TOTAL 90% FED/10% STATE |
|---|---|---|---|---|---|
| 67100100 | MOBILIZATION | L SUM | 0.9 | 0.1 | 1.0 |
| 72000100 | SIGN PANEL - TYPE 1 | SQ FT | 1236.8 | | 1236.8 |
| 72000200 | SIGN PANEL - TYPE 2 | SQ FT | 298.0 | | 298.0 |
| 72400310 | REMOVE SIGN PANEL - TYPE 1 | SQ FT | 62.0 | | 62.0 |
| 72400320 | REMOVE SIGN PANEL - TYPE 2 | SQ FT | 66.0 | | 66.0 |
| 72400710 | RELOCATE SIGN PANEL - TYPE 1 | SQ FT | 62.8 | | 62.8 |
| 72500100 | OBJECT MARKER - TYPE 1 | EACH | 2.0 | | 2.0 |
| 72500300 | OBJECT MARKER - TYPE 3 | EACH | 58.0 | | 58.0 |
| 72800100 | TELESCOPING STEEL SIGN SUPPORT | FOOT | 4636.8 | | 4636.8 |
| 73000100 | WOOD SIGN SUPPORT | FOOT | 68.0 | | 68.0 |
| 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | | 30.6 | 30.6 |
| 78000300 | THERMOPLASTIC PAVEMENT MARKING - LINE 5" | FOOT | | 5100.0 | 5100.0 |
| 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | | 100.0 | 100.0 |
| 78200405 | GUARDRAIL MARKERS | EACH | 50.0 | | 50.0 |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | | 248.9 | 248.9 |
| XX005938 | SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE) | EACH | 2.0 | | 2.0 |

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

VARIOUS ROUTES
SECTION D-6 SIGNING & STRIPING
VARIOUS COUNTIES

PLOT DATE = Aug-22-2007 01:41:06PM
FILE NAME = c:\projects\d612107\shtsoq.dgn
PLOT SCALE = 107.0321 ' / IN.
USER NAME = gallowsjbj

D6 PROJECT: d612107 FILE: shtsoq.dgn