

SUMMARY OF QUANTITIES

CODE NO	PAY ITEM	UNIT	100% STATE SFTY -2A QUANTITY
X0320047	REMOVAL OF EXISTING <i>PRECAST PRESTRESSED CONCRETE</i> DECK BEAMS	SQ FT	679
X0321781	MECHANICAL SPLICE	EACH	154
42001300	PROTECTIVE COAT	SQ YD	83.6
50102400	CONCRETE REMOVAL	CU YD	1.3
50301200	CONCRETE WEARING SURFACE	SQ YD	83.6
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	673
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	56620
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1860
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	525
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	525
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	3397
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1464
*78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	3054
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	3
Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
X7200201	<i>WIDTH RESTRICTION SIGNING</i>	<i>L SUM</i>	<i>1</i>
70100405	<i>TRAFFIC CONTROL AND PROTECTION, STANDARD 701321</i>	<i>L SUM</i>	<i>1</i>

* SPECIALTY ITEMS