

STATE
100%
1000
TOTAL

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL	TOTAL
67100100	MOBILIZATION	LSUM	1.0	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LSUM	1.0	1.0
78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	2,580.0	2,580.0
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	944.0	944.0
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	510.0	510.0
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	906.0	906.0
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS ^{AND} SYMBOLS	SQ FT	156.0	156.0
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	89.0	89.0
* 78100100	RAISED REFLECTOR PAVEMENT MARKER	EACH	65.0	65.0
78300200	RAISED REFLECTOR PAVEMENT MARKER REMOVAL	EACH	27.0	27.0
78300400	THERMOPLASTIC PAVEMENT MARKING REMOVAL	SQ FT	1,957.0	1,957.0
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	10	10



* SPECIALTY ITEMS

Rev. 2-27-08

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
cr:\projects\683468\shitsog.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(23, 29, 30)1	HANCOCK	9	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 72B74	