

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		X031-2A		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	5592	5592		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	775	775		
50102400	CONCRETE REMOVAL	CU YD	45	45		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	122.9	122.9		
50300260	BRIDGE DECK GROOVING	SQ YD	131	131		
50300300	PROTECTIVE COAT	SQ YD	146	146		
50606401	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1		
50606402	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1	1		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16040	16040		
50800515	BAR SPLICERS	EACH	52	52		
60260100	INLETS TO BE ADJUSTED	EACH	7	7		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7		
67100100	MOBILIZATION	L SUM	1	1		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1145	1145		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24793	24793		
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	1850	1850		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8264	8264		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	950	950		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	900	900		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	8667	8667		
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	124	124		
* 78100300	REPLACEMENT REFLECTOR	EACH	248	248		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2889	2889		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	248	248		
20030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
20030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1		
50600700	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1	1		

GENERAL NOTES:

1. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AMERENIP (GAS & ELECTRIC)
 - AT&T CORPORATION (COMMUNICATIONS)
 - CHARTER COMMUNICATIONS, INC. (CABLE TV)
 - ILLINOIS AMERICAN WATER COMPANY (WATER)
 - AT&T ILLINOIS (COMMUNICATIONS)
 MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY*. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
4. THE CONTRACTOR SHALL FURNISH AND INSTALL WOOD SIGN SUPPORTS IN ACCORDANCE WITH SECTION 730 OF THE STANDARD SPECIFICATIONS; HOWEVER, INSTALLATION BY METHOD 'A' (ARTICLE 730.04(a)) SHALL BE THE ONLY METHOD PERMITTED.
5. FOR STAGE I, THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER SHALL BE PAINTED YELLOW, FOR STAGE II, THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER SHALL BE PAINTED WHITE. THE COST SHALL BE PAID FOR AS "TEMPORARY PAINT PAVEMENT MARKING - LINE 6" "
6. PAVEMENT MARKING REMOVAL SHALL BE BY WATER BLAST METHOD.
7. TWO LANE TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES.
8. 'ROAD CONSTRUCTION AHEAD' AND 'WORK ZONE SPEED LIMIT' SIGNS SHALL BE INSTALLED AS DIRECTED BY THE RESIDENT ENGINEER ON THE SOUTHBOUND RAMP AT IL 162.

COMMITMENTS

NONE

* SPECIALTY ITEMS

FILE NAME =	USER NAME = harbaughrd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES, GENERAL NOTES & COMMITMENTS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\projects\ed86386\plan\pin86386a.dgn	PLOT SCALE = 50.0000' / IN.	DRAWN -	REVISED -			255	60-8B-II	MADISON	42	2
PLOT DATE = 12/19/2007	DATE -	CHECKED -	REVISED -			CONTRACT NO. 76A25		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		

SCALE: NA SHEET NO. 2 OF 42 SHEETS STA. TO STA.