

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	30	5
STA.		TO STA.		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FAS 919	FAP 331
				100% STATE JACKSON COUNTY 1000 QUANTITY	100% STATE SALINE COUNTY 1000 QUANTITY
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	1.0		1.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	1.0	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,404.0	2,404.0	
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,240.7		1,240.7
40600300	AGGREGATE (PRIME COAT)	TON	60.8	40.1	20.7
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	TON	239.0		239.0
40600990	TEMPORARY RAMP	SQ YD	272.0	74.0	198.0
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE C, N90	TON	2,241.0	2,241.0	
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N105	TON	1,158.0		1,158.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	37,631.0	26,694.0	10,937.0
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2,848.0		2,848.0
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	13.0	13.0	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	162.0	162.0	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	35.0	35.0	
44201823	CLASS D PATCHES, TYPE I, 15 INCH	SQ YD	54.1		54.1
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	95.3		95.3
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	71.0		71.0
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	202.0		202.0
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	1,546.0		1,546.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	516.0	516.0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3.0	1.5	1.5
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.5	0.5
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1.0	0.5	0.5
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1.0		1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0		1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,272.0	2,364.0	1,908.0
70300210	TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	586.3	122.4	463.9
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	49,739.0	42,218.0	7,521.0
70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	598.0		598.0
70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	40.0		40.0
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	134.0	72.0	62.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	17,824.0	14,712.0	3,112.0
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	586.3	122.4	463.9
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,521.0		7,521.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	598.0		598.0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	40.0		40.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	62.0		62.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	42,218.0	42,218.0	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	72.0	72.0	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	312.0	152.0	160.0
* 88600100	DETECTOR LOOP, TYPE I	FOOT	427		427

\* VARIOUS  
 \*\* D9 CONT. MAINT. BIT. RES. FY 08-1  
 \*\*\* SALINE & JACKSON

\* SPECIALTY ITEMS

PLOT DATE = 12/12/2007  
 FILE NAME = c:\pva\pva\18012\18012.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = mcorcor