

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	30	12
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				

- * VARIOUS
- ** D9 CONT. MAINT. BIT. RES. FY 08-1
- *** SALINE & JACKSON

PAVEMENT MARKING SCHEDULE AT MAKANDA

STATION TO STATION	PAINT PAVEMENT MARKING				THPL PAVEMENT MARKING	TEMPORARY			NOTES		
	4 INCH WHITE (EDGELINE)	4 INCH YELLOW	4 INCH YELLOW (SKIP-DASH)	24 INCH WHITE	LTRS & SYMB WHITE	4 INCH	24 INCH	LTRS & SYMB WHITE			
	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	SQ FT			
FAS 919 (Makanda Rd.)											
LEFT	1+00.0	TO	85+09.2	8409		8409			Edgeline		
LEFT	1+00.0	TO	83+50.0			8250			Dbi. Yellow		
LEFT	83+50.0	TO	85+09.2		40	40			Skip-Dash		
Eq. Sta. 85+09.23 (Bk.) = Sta. -(0+44.77) (Ah.)											
LEFT	(0+44.77)	TO	(0+00)	45		90			Edgeline & Dbi. Yellow		
Eq. Sta. -(0+00) (Bk.) = Sta. 0+00 (Ah.)											
LEFT	0+00	TO	3+27.4	328		656			Edgeline & Dbi. Yellow		
Eq. Sta. 3+27.4 (Bk.) = Sta. 2+28 (Ah.)											
LEFT	2+28.0	TO	2+81.0	53		106			Edgeline & Dbi. Yellow		
Sta. 2+81 To Sta. 4+15 (S.N. 039-0055 Omission)											
LEFT	4+15.0	TO	5+40.0	125		250			Edgeline & Dbi. Yellow		
Sta. 5+40 to Sta. 5+52 (Railroad Crossing)											
LEFT	5+52.0	TO	34+00.0	2,848		2,848			Edgeline		
LEFT	5+52.0	TO	8+25.0			273	12		Dbi. Yellow & Stop Bar		
LEFT	6+67.0	TO	7+17.0			24	24	61.2	RR Symb's. (X and 2-R's)		
RIGHT	1+00.0	TO	78+23.0	7723		15446			Edgeline & Dbi. Yellow		
RIGHT	78+23.0	TO	83+50.0	527	132	659			Edgeline & Skip-Dash		
RIGHT	83+50.0	TO	85+09.0	159		318			Dbi. Yellow		
Eq. Sta. 85+09.23 (Bk.) = Sta. -(0+44.77) (Ah.)											
RIGHT	(0+44.77)	TO	(0+00)	45		90			Edgeline & Dbi. Yellow		
Eq. Sta. -(0+00) (Bk.) = Sta. 0+00 (Ah.)											
RIGHT	0+00	TO	3+27.4	328		656			Edgeline & Dbi. Yellow		
Eq. Sta. 3+27.4 (Bk.) = Sta. 2+28 (Ah.)											
RIGHT	2+28.0	TO	2+81.0	53		106			Edgeline & Dbi. Yellow		
Sta. 2+81 To Sta. 4+15 (S.N. 039-0055 Omission)											
RIGHT	4+15.0	TO	5+40.0	125		250	36	61.2	Edge., Dbi. Yell. & RR Symb's.		
Sta. 5+40 to Sta. 5+50 (Railroad Crossing)											
RIGHT	5+52.0	TO	35+00.0	2,948		2,948			Edgeline		
RIGHT	5+52.0	TO	6+67.0		115	115			Dbi. Yellow		
RIGHT	6+67.0	TO	8+00.0		33	33			Skip-Dash		
RIGHT	8+00.0	TO	35+00.0		675	675			Skip-Dash		
SUB-TOTALS				23,716	17,622	880	72	122.4	42,218	72	122.4
FAS 919 TOTALS					42,218		72	122.4	42,218	72	122.4

PLOT DATE = 12/7/2007
 FILE NAME = c:\pave\maka\0390055\p983787.mxd
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = mwoodr