

SUMMARY OF QUANTITIES

F. A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2611	03-00148-00-PV	DUPAGE	58	3
SUMMARY OF QUANTITIES				
FED. ROAD DISTRICT NO. 7 ILLINOIS FED. AID PROJECT M-6003(521)				
CONTRACT NO. 83952				

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	I000-2A	Y030-1E	Y031-1F	Y060
				ROADWAY	LIGHTING	TRAFFIC SIGNAL	100% VILLAGE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	126	126			
20101000	TEMPORARY FENCE	FOOT	643	643			
* 20101200	TREE ROOT PRUNING	EACH	10	5			5
* 20101300	TREE PRUNING (1 to 10 INCH DIAMETER)	EACH	5	5			
* 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	5			
20200100	EARTH EXCAVATION	CUYD	1426	1426			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CUYD	429	429			
20400800	FURNISHED EXCAVATION	CUYD	683	683			
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CUYD	429	429			
20800250	TRENCH BACKFILL, SPECIAL	CUYD	2850	2850			
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQYD	3791	3791			
* 25000400	NITROGEN FERTILIZER	POUND	47	47			
* 25000500	PHOSPHOROUS FERTILIZER	POUND	47	47			
* 25000600	POTASSIUM FERTILIZER	POUND	47	47			
* 25200110	SODDING, SALT TOLERANT	SQYD	3791	3791			
25200200	SUPPLEMENTAL WATERING	UNIT	56	56			
28000510	INLET FILTER	EACH	29	29			
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQYD	684	684			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2492	2492			
40600300	AGGREGATE (PRIME COAT)	TON	28	28			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL -- BUTT JOINT	SQYD	150	150			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	3490	3490			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	971	971			
42001300	PROTECTIVE COAT	SQYD	2530	2398			132
42300710	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH, SPECIAL	SQYD	9	9			
42300800	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH, SPECIAL	SQYD	485	485			
42400500	PORTLAND CEMENT CONCRETE SIDEWALK, SPECIAL	SQFT	11124	10224			900
42400800	DETECTABLE WARNINGS	SQFT	420	420			
44000100	PAVEMENT REMOVAL	SQYD	141	141			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1-1/2"	SQYD	11301	11301			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQYD	250	250			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	1134	1134			
44000300	CURB REMOVAL	FOOT	285	285			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4091	3911			180
44000600	SIDEWALK REMOVAL	SQFT	11461	10561			900

* INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

MAIN STREET

DATE: 11/26/07
DESIGNED BY: SJC
CHECKED BY: JRV