

SUMMARY OF QUANTITIES

F. A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
261103-00148-00-PV	DUPAGE	58	4	
SUMMARY OF QUANTITIES				
FED. ROAD DISTRICT NO. 7 ILLINOIS FED. AID PROJECT M-8003(521)				
CONTRACT NO. 83952				

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	Y030-1E	Y031-1F	Y060
				ROADWAY	LIGHTING	TRAFFIC SIGNAL	100% VILLAGE
44003100	MEDIAN REMOVAL	SQFT	285	285			
44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQYD	32				32
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQYD	306				306
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQYD	911	911			
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQYD	300	300			
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQYD	1417	565			852
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1480	1480			
54216180	REINFORCED CONCRETE PIPE TEE, 12" PIPE WITH 12" RISER	EACH	3	3			
54248100	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 15"	EACH	1				1
550A0020	STORM SEWERS, CLASS A, TYPE 1 6"	FOOT	35	35			
550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	16				16
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	626	626			
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	24	24			
55100200	STORM SEWER REMOVAL 6"	FOOT	70	70			
55100400	STORM SEWER REMOVAL 10"	FOOT	146	146			
55100500	STORM SEWER REMOVAL 12"	FOOT	118	118			
55100700	STORM SEWER REMOVAL 15"	FOOT	36	36			
55101200	STORM SEWER REMOVAL 24"	FOOT	34	24			10
55101600	STORM SEWER REMOVAL 36"	FOOT	10				10
* 56102900	DUCTILE IRON WATER MAIN 4"	FOOT	64				64
* 56103000	DUCTILE IRON WATER MAIN 6"	FOOT	450				450
* 56103100	DUCTILE IRON WATER MAIN 8"	FOOT	210				210
* 56103200	DUCTILE IRON WATER MAIN 10"	FOOT	180				180
* 56103300	DUCTILE IRON WATER MAIN 12"	FOOT	2699				2699
* 56104800	WATER VALVES 4"	EACH	1				1
* 56104900	WATER VALVES 6"	EACH	2				2
* 56105000	WATER VALVES 8"	EACH	6				6
* 56105100	WATER VALVES 10"	EACH	2				2
* 56105200	WATER VALVES 12"	EACH	11				11
* 56200300	WATER SERVICE LINE 1"	FOOT	1116				1116
* 56200500	WATER SERVICE LINE 1 1/2"	FOOT	125				125
* 56200700	WATER SERVICE LINE 2"	FOOT	187				187
* 56201400	CORPORATION STOPS 1"	EACH	25				25
* 56201600	CORPORATION STOPS 1 1/2"	EACH	2				2
* 56201800	CORPORATION STOPS 2"	EACH	3				3

* INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

MAIN STREET

DATE: 11/26/07
DESIGNED BY: SJC
CHECKED BY: JRJ