

## SUMMARY OF QUANTITIES

F. A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
261103-00148-00-PV	DUPAGE	58	7	
SUMMARY OF QUANTITIES				
FED. ROAD DISTRICT NO. 7 ILLINOIS FED. AID PROJECT M-8003(521)				
CONTRACT NO. 83952				

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	Y030-1E	Y031-1F	Y060
				ROADWAY	LIGHTING	TRAFFIC SIGNAL	100% VILLAGE
* 85700305	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1			1	
* 86000105	MASTER CONTROLLER (SPECIAL)	EACH	1			1	
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	2019			2019	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	2638			2638	
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	2260			2260	
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	1976			1976	
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	92			92	
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	4			4	
* 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	2			2	
* 87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1			1	
* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1			1	
* 87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	3			3	
* 87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1			1	
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16			16	
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8			8	
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	45			45	
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	75			75	
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	10			10	
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2	
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4			4	
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	6			6	
* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2			2	
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	6			6	
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	5			5	
* 88200310	TRAFFIC SIGNAL BACKPLATE, LOUVERED, PLASTIC	EACH	16			16	
* 88700200	LIGHT DETECTOR	EACH	4				4
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	2				2
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	16			16	
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2			2	
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2			2	
* 89502380	REMOVE EXISTING HANDHOLE	EACH	7			7	
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	17			17	
Z0001050	AGGREGATE SUBGRADE 12"	SQYD	2171	2171			
Z0017400	DRAINAGE & UTILITY STRUCTURE TO BE ADJUSTED	EACH	5	5			

\* INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SUMMARY OF QUANTITIES

#### MAIN STREET

DATE: 11/26/07  
DESIGNED BY: SJC  
CHECKED BY: JRV