

CONSTRUCTION TYPE CODE : Y047

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	06-00042-00-BT	JO DAVNESS	30	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

85417

SUMMARY OF QUANTITIES			
PAY CODE	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	890
20201000	GRADING AND SHAPING ROADWAY	UNIT	5
20201006	GRADING AND SHAPING SHOULDERS	UNIT	5
20800150	TRENCH BACKFILL	CU YD	190
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,335
21400100	GRADING AND SHAPING DITCHES	FOOT	859
25000210	SEEDING, CLASS 2A	ACRE	166
25000400	NITROGEN FERTILIZER NUTRIENT	LB	145
25000500	PHOSPHORUS FERTILIZER NUTRIENT	LB	145
25000600	POTASSIUM FERTILIZER NUTRIENT	LB	145
25100105	MULCH METHOD 1	ACRE	166
28000300	TEMP. DITCH CHECKS	EACH	7
28000400	PERIMETER EROSION BARRIER	FT	470
28000510	INLET FILTERS	EACH	7
28100107	STONE RIPRAP, CLASS A4	SY	110
28200200	FILTER FABRIC	SY	110
XX007291	AGGREGATE BASE COURSE, TYPE A 6"	TON	1,387
XX007292	AGGREGATE BASE COURSE, TYPE A 8"	TON	380
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	658
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	177
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	177
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4-INCH	SF	21,453
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6-INCH	SF	2,288
42400800	DETECTABLE WARNINGS	SO FT	60
44000200	DRIVEWAY PAVEMENT REMOVAL	SY	117
44000500	COMBINATION CURB AND GUTTER REMOVAL	FT	94
44000600	SIDEWALK REMOVAL	SF	521
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SY	274
44000173	HOT-MIX ASPHALT SURFACE REMOVAL, 6"	SY	585
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SY	20
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SY	76
44213200*	SAW CUTS	FT	1,498
50105220	PIPE CULVERT REMOVAL	FT	56
542C0213	PIPE CULVERTS, CLASS C, TYPE 18"	FT	213
542C0217	PIPE CULVERTS, CLASS C, TYPE 112"	FT	175
542C0220	PIPE CULVERTS, CLASS C, TYPE 115"	FT	59
542C0235	PIPE CULVERTS, CLASS C, TYPE 130"	FT	64
54215550*	METAL END SECTIONS 15"	EACH	1
54215565	METAL END SECTIONS 30"	EACH	1
54248510	CONCRETE COLLAR	CU YD	1.43
56400800 Δ	FIRE HYDRANT AND VALVE TO BE MOVED	EACH	4
60200105	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE I FRAME, OPEN LID	EACH	2
60213300*	CATCH BASINS, SPECIAL	EACH	1
60242400*	INLETS, SPECIAL	EACH	5
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FT	1,385
63300205* Δ	REMOVE AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, TYPE A	FT	20
67100100*	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
72000100 Δ	SIGN PANEL - TYPE 1	SF	150
73000100 Δ	WOOD SIGN SUPPORT	FT	
78000200 Δ	THERMOPLASTIC PAVEMENT MARKING - LINE 4" (YELLOW)	FT	3,734
Z0013738*	CONSTRUCTION LAYOUT	L SUM	1
Z0077900*	WOOD POST AND RAIL FENCE	FT	609
XX000610*	RELOCATE EXISTING MAILBOX	EACH	5
XX003424	CONNECT TO EXISTING STRUCTURE	EACH	2
XX006402*	REMOVE AND RE-BRECT STONE WALL	L SUM	1
X4402200*	PAVEMENT REMOVAL (CONCRETE)	SO YD	49

Revised 2-29-08

Δ SPECIALTY ITEMS



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY

PLAN: SURVEYED, PLANNED, CHECKED, REVISIONS, DATE, FILE NAME, SCALE, DATE, DRAWN BY, CHECKED BY
 PROFILE: SURVEYED, GRADES, CHECKED, E.M. NOTED, STRUCTURE, NOTATIONS, CIP/FO