

SUMMARY OF QUANTITIES

CODED PAY ITEM NUMBER	ITEM	UNIT	TOTAL QUANTITY	FUND CODE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	38	X020-2A
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	24	X020-2A
20200100	EARTH EXCAVATION	CU YD	2117	X020-2A
* 20400800	FURNISHED EXCAVATION	CU YD	589	X020-2A
* 20700400	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	135	X020-2A
20800150	TRENCH BACKFILL	CU YD	87	X020-2A
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2996	X020-2A
25000200	SEEDING, CLASS 2	ACRE	0.6	X020-2A
25000312	SEEDING, CLASS 4A	ACRE	0.3	X020-2A
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	102	X020-2A
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	102	X020-2A
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	102	X020-2A
25000775	SELECTIVE MOWING STAKES	EACH	4	X020-2A
25100630	EROSION CONTROL BLANKET	SQ YD	2015	X020-2A
25200100	SODDING	SQ YD	1635	X020-2A
28000400	PERIMETER EROSION BARRIER	FOOT	1606	X020-2A
28000500	INLET AND PIPE PROTECTION	EACH	2	X020-2A
28100107	STONE RIPRAP, CLASS A4	SQ YD	736	X020-2A
28200200	FILTER FABRIC	SQ YD	850	X020-2A
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	2948	X020-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.5	X020-2A
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1514	X020-2A
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	303	X020-2A
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	20	X020-2A
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	424	X020-2A
44000100	PAVEMENT REMOVAL	SQ YD	2552	X020-2A
* 44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	153	X020-2A
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	1160	X020-2A
* 50100200	REMOVAL OF EXISTING STRUCTURE	L SUM	1	X020-2A
* 50105220	PIPE CULVERT REMOVAL	FOOT	66	X020-2A
50200100	STRUCTURE EXCAVATION	CU YD	296	X020-2A
* 50203000	STRUCTURE EXCAVATION PROTECTION FOR PILE BENTS	EACH	2	X020-2A
50300100	FLOOR DRAINS	EACH	4	X020-2A
50300225	CONCRETE STRUCTURES	CU YD	246.8	X020-2A
50300255	CONCRETE SUPERSTRUCTURE	CU YD	418.0	X020-2A
50300260	BRIDGE DECK GROOVING	SQ YD	579	X020-2A
50300300	PROTECTIVE COAT	SQ YD	1,411	X020-2A
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	99,090	X020-2A
50800515	BAR SPLICERS	EACH	128	X020-2A
50901750	PARAPET RAILING	FOOT	161	X020-2A
51201005	FURNISHING METAL SHELL PILES 12"	FOOT	1,980	X020-2A
51201105	FURNISHING METAL SHELL PILES 14"	FOOT	945	X020-2A
* 51202305	DRIVING PILES	FOOT	2,925	X020-2A
51203200	TEST PILE METAL SHELLS	EACH	4	X020-2A

CODED PAY ITEM NUMBER	ITEM	UNIT	TOTAL QUANTITY	FUND CODE
51500100	NAME PLATES	EACH	1	X020-2A
54209487	PIPE CULVERT, TYPE 2, REINFORCED CONCRETE, EQUIVALENT ROUND-SIZE 42"	FOOT	228	X020-2A
54214527	PRECAST REINFORCED CONCRETE FLARED END SECTIONS EQUIVALENT ROUND-SIZE 42"	EACH	2	X020-2A
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	15	X020-2A
Δ * 56103300	DUCTILE IRON WATER MAIN 12"	FOOT	460	X020-2A
Δ * 56103400	DUCTILE IRON WATER MAIN 16"	FOOT	280	X020-2A
Δ * 56400600	FIRE HYDRANTS	EACH	1	X020-2A
* 60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	226	X020-2A
* 60213300	CATCH BASINS, SPECIAL	EACH	1	X020-2A
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	X020-2A
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	X020-2A
* 60404805	FRAMES AND GRATES, TYPE 11V	EACH	1	X020-2A
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	148	X020-2A
Δ 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	50	X020-2A
Δ 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	X020-2A
Δ * 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	X020-2A
* 63200307	STEEL PLATE BEAM GUARDRAIL REMOVAL, ATTACHED TO STRUCTURE	FOOT	155	X020-2A
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	1	X020-2A
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	X020-2A
67100100	MOBILIZATION	L SUM	1	X020-2A
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	X020-2A
72000100	SIGN PANEL - TYPE 1	SQ FT	9	X020-2A
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	21	X020-2A
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	18	X020-2A
72900100	METAL POST - TYPE A	FOOT	84	X020-2A
Δ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	46.5	X020-2A
Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1799	X020-2A
Δ 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	65	X020-2A
Δ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	102	X020-2A
Δ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	369	X020-2A
Δ 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	328	X020-2A
Δ * 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	X020-2A
* XX006623	MULCH, METHOD 3, SPECIAL	ACRE	0.5	X020-2A
* XX006821	CONCRETE TRUCK WASHOUT	L SUM	1	X020-2A
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	X020-2A
* Z0022800	FENCE REMOVAL	FOOT	90	X020-2A
* Z0076600	TRAINEES	HOUR	500	X020-2A
* X0325862	CONCRETE BRIDGE RAILING	FOOT	104	X020-2A
* XX007255	MODIFIED CONCRETE BRIDGE RAILING	FOOT	104	X020-2A
Δ * XX007256	DUCTILE IRON WATERMAIN, BALL & SOCKET, 12"	FOOT	100	X020-2A
Δ * XX007257	DUCTILE IRON WATERMAIN, BALL & SOCKET, 16"	FOOT	100	X020-2A
Δ * XX007258	REMOVE EXISTING WATERMAIN AND CASING	L SUM	1	X020-2A
* XX007259	SIGN AND POST REMOVAL	EACH	1	X020-2A
* XX007260	SLOPED METAL END SECTION WITH GRATE, ARCH EQUIVALENT ROUND SIZE 36"	EACH	1	X020-2A

\* INDICATES PAY ITEM COVERED BY SPECIAL PROVISION  
Δ INDICATES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SECTION 04-00166-00-BR DEKALB COUNTY FAIRVIEW DRIVE BRIDGE
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: AS SHOWN      DRAWN BY: MWH  
DATE: 11/05/07      CHECKED BY: CPS



LAYOUT: MWH 11/15/06  
DRAWN: MWH 10/13/07  
REVISED: CPS 10/13/07