F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5345	04-00166-00-BR	DEKALB	39	3
STA. 14+00		TO STA. 23+00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 87339

EARTHWORK

STATION	END AREAS CUT (SQ FT)	END AREAS FILL (SQ FT)	VOLUME CUT (CU YD)	VOLUME FILL (CU YD)
14+00.00	49.8	0.6	---	---
14+50.00	53.5	1.7	95.6	2.1
15+00.00	53.3	0.2	98.9	1.8
15+50.00	51.4	0.7	96.9	0.8
16+00.00	42.3	3.7	86.8	4.1
16+50.00	34.3	53.7	70.9	53.1
17+00.00	53.1	154.8	80.9	193.1
17+50.00	54.2	276.4	99.4	399.3
17+71.02	31.8	377.5	33.5	254.5
BRIDGE	---	---	567.9	82.8
19+03.06	11.0	410.9	---	---
19+50.00	11.1	240.4	19.2	566.1
20+00.00	41.0	137.7	48.2	350.1
20+50.00	67.3	50.9	100.3	174.6
20+73.94	86.6	7.3	68.2	25.8
21+00.00	74.1	0.4	77.6	3.7
21+50.00	85.3	13.4	147.6	12.8
22+00.00	81.8	12.0	154.7	23.5
22+50.00	73.2	8.2	143.5	18.7
23+00.00	64.0	1.8	127.0	9.3
TOTALS	---	---	2117.2	2176.2

STORM SEWER

FROM STATION	FROM OFFSET	TO STATION	TO OFFSET	LENGTH (FT)	SIZE (INCH)
21+25.00	43.50' RT	20+92.96	40.26' RT	30	42
20+92.96	40.26' RT	20+33.72	40.37' RT	58	42
20+36.81	26.58' RT	20+33.72	40.37' RT	15	12
20+33.72	40.37' RT	18+92.83	53.62' RT	140	42

STATION	OFFSET	STRUCTURE
18+92.83	53.62' RT	42" PRC EQUIV F.E.S.
20+33.72	40.37' RT	6'Ø MH TYPE A
20+36.81	26.58' RT	CATCH BASIN SPECIAL
20+92.96	40.26' RT	6'Ø MH TYPE A
21+25.00	43.50' RT	42" PRC EQUIV F.E.S.
22+72.65	36.65' RT	SLOPED METAL END SECTION WITH GRATE

TREE REMOVAL

STATION	OFFSET	UNITS
19+06	40' RT	8
19+08	58' RT	8
19+11	63' RT	8
19+14	55' RT	8
19+17	73' RT	6
21+48	53' RT	24
TOTALS		62

SCHEDULES

56103300 DUCTILE IRON WATER MAIN 12"
STA. 17+00 TO STA. 20+70 — 459 FT

56103400 DUCTILE IRON WATER MAIN 16"
STA. 16+13 TO STA. 21+53 — 203 FT

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24
STA. 19+29 TO STA. 20+62 — 148 FT

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A
STA. 19+18 TO STA. 19+68 — 50 FT

63100089 TRAFFIC BARRIER TERMINAL, TYPE 6
STA. 17+21 TO STA. 17+64 — 1 EACH
STA. 18+75 TO STA. 19+18 — 1 EACH

63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)
STA. 16+71 TO STA. 17+21 (RT) — 1 EACH
STA. 19+68 TO STA. 20+18 (LT) — 1 EACH

63200307 STEEL PLATE BEAM GUARD RAIL REMOVAL, ATTACHED TO STRUCTURE
STA. 17+55 TO STA. 17+95 (LT) — 39.5 FT
STA. 18+63 TO STA. 19+00 (LT) — 37.5 FT
STA. 17+69 TO STA. 18+07 (RT) — 38.5 FT
STA. 18+75 TO STA. 19+14 (RT) — 39.5 FT
155 FT

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS
STA. 22+50 — 15.5 SQ FT
STA. 22+90 — 15.5 SQ FT
STA. 23+30 — 15.5 SQ FT
46.5 SQ FT

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"
STA. 14+00 TO STA. 17+58, STA. 19+11 TO STA. 23+00 — 1669 FT
STA. 22+35 TO STA. 23+00 — 130 FT
1799 FT

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"
STA. 22+35 TO STA. 23+00 — 65 FT

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"
STA. 19+11 TO STA. 19+95 (LT - DIAG.) — 51 FT
STA. 16+74 TO STA 17+58 (RT - DIAG.) — 51 FT
102 FT

78001110 PAINT PAVEMENT MARKING - LINE 4"
STA. 17+52 TO STA. 19+17 — 40 FT
STA. 17+47 TO STA. 19+11 (LT) — 164.5 FT
STA. 17+58 TO STA. 19+22 (RT) — 164.5 FT
369 FT

78001150 PAINT PAVEMENT MARKING - LINE 12"
STA. 17+51 TO STA. 19+05 (LT - DIAG.) — 164 FT
STA. 17+64 TO STA 19+18 (RT - DIAG.) — 164 FT
328 FT

NOTE

SEE BRIDGE PLANS FOR ADDITIONAL SCHEDULES.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SECTION 04-00166-00-BR
DEKALB COUNTY
FAIRVIEW DRIVE BRIDGE

SCHEDULES

SCALE: AS SHOWN — DRAWN BY MWH
DATE 11/05/07 — CHECKED BY CPS

HANSON
Hanson Professional Services Inc.
© Copyright Hanson Professional Services Inc. 2006

LAYOUT MWH 10/05/07
DRAWN MWH 10/19/07
REVIEWED CPS 10/19/07