

DRAINAGE SCHEDULE																		
LOCATION (STA TO STA)		LENGTH (FT)	WIDTH (FT)	PIPE CULVERT CL C1 12" (LF)	PRECAST FLAR END SEC 18" (EA)	PRECAST FLAR END SEC 30" (EA)	STEEL END SECTION 12" (EA)	STORM SEWER CL A TY 1 10" (LF)	STORM SEWER CL A TY 1 18" (LF)	MANHOLE TY A 4' DIA T 1 C.L. (EA)	INLETS TA T10 F&G (EA)	CONC MEDIAN SPL (SF)	CONC GUTTER TA (LF)	CONC GUTTER TB (LF)	GUTTER OUTLET (EA)	INLET & PIPE PROTECT (EA)	BROKEN CONC RIPRAP (SY)	
ROSE HILL DR	0+00 LT														1			
	0+00 TO 0+50 LT	83						85										
	0+00 TO 4+83 LT	523										523						
	0+50 LT										1						1	
	0+50 TO 1+20 LT	62						74										
	1+20 LT								1									
	1+20 TO 2+00 LT	72						80										
	2+00 LT										1						1	
	2+00 TO 3+50 LT	145						156										
	3+50 LT										1						1	
	9+50 RT	20	5														11.1	
	10+88 TO 11+12 RT	20											20					
	11+00 RT										1						1	
	11+15 TO 11+40 RT	20											20					
	11+27 RT										1						1	
	15+80 LT																	
	15+70 LT																	
ROSE HILL SUBTOTALS					0	2	0	0	0	395	1	5	0	523	40	1	5	11.1
MEMORIAL LANE	10+35 RT										1						1	
	10+55 RT										1						1	
	10+70 RT										1						1	
	11+90 TO 13+60 LT	180											180					
	13+45 RT										1						1	
	13+80 LT													1				
	14+50 TO 16+15 RT	165											165					
	14+80 RT										1						1	
	15+95 TO 16+10 LT	15											15					
	16+30 RT													1				
	16+50 LT														1			
	16+60 RT																	
	16+70 LT	18	10														20	
	16+80 RT	10	10														11.1	
	17+40 RT																	
	17+50 LT	10	10														11.1	
MEMORIAL SUBTOTALS					0	2	0	0	0	0	0	5	0	0	360	3	5	42.2
HERVEY LIGHTNER DR	6+10 LT										1							
	8+75 RT										1							
	9+05 RT										1							
	11+60 LT														1			
	11+60 TO 19+30 LT	770											770					
	12+80 LT	20																
	12+80 LT							12			1						1	
	12+80 RT																	
	13+75 LT										1						1	
	14+80 RT											12						
	15+00 LT	5	5														2.8	
	15+00 RT																	
	15+50 LT										1						1	
	17+00 LT	5	5														2.8	
	17+00 RT																	
	17+25 LT										1						1	
	17+33 LT	22																
	17+45 LT	4	4														1.8	
	17+45 RT																	
	19+16 LT																	
	19+70 LT																20.5	
	19+70 RT	5	5														2.8	
HERVEY LIGHTNER SUBTOTALS					42	2	2	2	12	0	0	7	12	0	770	2	4	30.6
DRAINAGE TOTALS					42	6	2	2	12	395	1	17	12	523	1170	6	14	83.9

SEEDING SCHEDULE											
LOCATION (STA TO STA)		LENGTH (FT)	WIDTH (FT)	SEEDING CLASS 3 (ACRE)	NITROGEN FERT NUTR (LBS)	PHOPHOROUS FERT NUTR (LBS)	POTASSIUM FERT NUTR (LBS)	MULCH METHOD 2 (ACRE)	EROSION CONTR BLANKET (SY)	F & P TOP SOIL (CY)	
ROSE HILL DR	0+00 TO 18+90	1890	5	0.2	19.5	19.5	19.5	0.2	189.0	115.5	
MEMORIAL LANE	12+00 TO 18+00	600	5	0.1	6.2	6.2	6.2	0.1		36.7	
HERVEY LIGHTNER DR	11+60 TO 19+30	770	5	0.1	8.0	8.0	8.0	0.1		47.1	
SEEDING TOTALS				0.4	33.7	33.7	33.7	0.4	189.0	199.2	

P:\3160070016\DWG\Final Set\QUANTITY SCHEDULES_2.dwg, 1/4/2008 11:22:48 AM, \\peoria-m\Peoria-P5

REVISIONS			
NO.	DATE	DESCRIPTION	APPROVED

DESIGNED AJS
DRAWN AJS, KSB, JLA
CHECKED EEA
DATE 01/04/03



SCHEDULES-DRAINAGE & SEEDING

SPRINGDALE CEMETERY
3014 N. PROSPECT RD.
PEORIA, ILLINOIS
FOUNDED 1854
REBORN 2003