

CSI CONSOLIDATED SERVICES INC.
of Coles County

ENGINEERING - SURVEYING - CONSTRUCTION MANAGEMENT
520 Jackson Avenue - P.O. Box 644 - Charleston, Illinois - 61920 - (217) 345-9511

CSI File # 05378-06-06

DRAWN	DCR
DATE	
CHECKED	
DATE	
APPROVED	
DATE	
REVISED	
DATE	

SCALES	N/A
--------	-----

4th Street
Plan and Profile

Sheet No.
16
of 57 Sheets

Trench Backfill

13.50' Rt.64+00.00 to 13.50' Rt.64+66.25 7.70 CY
20.00' Rt.64+66.25 to 13.50' Rt.64+66.25 4.40 CY
13.50' Rt.64+66.25 to 23.54' Rt.65+10.02 12.10 CY
13.85' Lt.69+00.00 to 14.50' Lt.67+35.00 250.50 CY
Total 274.7 CY

Sub-Base Granular Material, Type B 4"

13.25' Lt.64+00.00 to 15.36' Lt.65+25.62 36.94 SY
11.07' Rt.64+00.00 to 14.54' Rt.65+25.75 70.53 SY
13.75' Lt.66+54.68 to 13.10' Lt.69+00.00 133.12 SY
11.75' Rt.66+87.76 to 11.30' Rt.69+00.00 95.26 SY
Total 335.85 SY

Portland Cement Concrete Base Course Widening 7"

9.82' Rt.64+00.00 to 13.29' Rt.65+25.69 35.53 SY
13.01' Lt.64+77.52 to 14.11' Lt.65+26.16 1.82 SY
12.50' Lt.66+54.68 to 12.00' Lt.69+00.00 56.39 SY
10.50' Rt.66+87.76 to 10.00' Rt.69+00.00 46.26 SY
Total 140 SY

Hot-Mix Asphalt Surface Removal - Butt Joint

0.00' Lt.65+06.17 to 0.00' Lt.65+26.16 55.67 SY
0.00' Lt.66+54.68 to 0.00' Lt.66+74.68 51.21 SY
Total 106.88 SY

Portland Cement Concrete Driveway Pavement, 6 Inch

13.50' Lt.64+30.46 to 30.50' Lt.64+30.46 25.07 SY
14.23' Rt.64+99.80 to 24.47' Rt.64+99.80 21.43 SY
14.50' Lt.67+05.68 to 24.00' Lt.67+05.68 26.44 SY
14.50' Lt.68+75.49 to 20.50' Lt.68+75.49 13.73 SY
Total 86.67 SY

Portland Cement Concrete Sidewalk 4 Inch

17.50' Lt.64+00.00 to 17.50' Lt.64+22.18 90.79 SF
17.50' Rt.64+00.00 to 17.50' Rt.64+90.15 360.15 SF
18.11' Lt.64+37.74 to 18.11' Lt.65+26.43 369.65 SF
19.70' Lt.64+75.37 to 22.71' Lt.64+75.37 11.63 SF
17.50' Rt.65+11.34 to 17.39' Rt.65+25.93 61.55 SF
18.57' Rt.66+00.30 to 16.50' Rt.69+00.00 1198.76 SF
18.50' Lt.66+35.50 to 18.50' Lt.66+93.03 229.62 SF
18.50' Lt.67+18.32 to 18.50' Lt.68+65.84 589.11 SF
20.50' Lt.68+20.43 to 26.50' Lt.68+20.43 18.00 SF
18.50' Lt.68+85.13 to 18.50' Lt.69+00.00 58.99 SF
Total 2988.25 SF

Driveway Pavement Removal

Lt.64+30.46 13.05 SY
Rt.64+99.80 22.01 SY
Lt.67+05.66 35.43 SY
Lt.68+75.47 7.06 SY
Total 77.55 SY

Combination Curb and Gutter Removal

14.58' Lt.64+00.00 to 13.92' Lt.64+45.85 45.83 FEET
9.14' Rt.64+00.00 to 9.81' Rt.64+42.52 42.53 FEET
9.81' Rt.64+42.52 to 14.79' Rt.65+25.75 83.60 FEET
13.92' Lt.64+45.85 to 15.60' Lt.65+25.59 80.57 FEET
14.00' Lt.66+54.68 to 12.18' Lt.67+33.09 78.42 FEET
12.00' Rt.66+87.76 to 11.40' Rt.67+00.73 12.99 FEET
11.40' Rt.67+00.73 to 10.61' Rt.69+00.00 199.27 FEET
12.18' Lt.67+33.08 to 12.21' Lt.69+00.00 166.92 FEET
Total 710.13 FEET

Sidewalk Removal

19.24' Lt.64+00.00 to 19.40' Lt.65+25.63 492.73 SF
12.80' Rt.64+75.99 to 21.78' Rt.64+75.37 34.80 SF
18.44' Lt.66+35.50 to 17.08' Lt.66+89.73 208.07 SF
16.79' Lt.67+20.60 to 17.05' Lt.69+00.00 698.20 SF
24.60' Lt.68+20.38 to 26.50' Lt.68+20.38 4.96 SF
Total 1438.76 SF

Class C Patches, Type II

9.70' Rt.70+37.82 to 10.68' Lt.70+37.82 6.79 SY
Total 6.79 SY

Concrete Retaining Wall Removal

16.65' Rt.64+00.00 to 17.96' Rt.64+22.65 22.69 FEET
Total 22.69 FEET

Precast Reinforced Concrete Flared End Sections 18"

30.00' Rt.65+39.34 1.00 EACH
Total 1 EACH

Storm Sewers, Class A, Type 1 12"

20.00' Rt.64+66.25 to 13.50' Rt.64+66.25 6.50 FEET
Total 6.5 FEET

Storm Sewers, Class A, Type 1 18"

13.50' Rt.64+00.00 to 13.50' Rt.64+66.25 66.26 FEET
13.50' Rt.64+66.25 to 30.00' Rt.65+39.34 56.94 FEET
Total 123.2 FEET

Storm Sewers, Class A, Type 2 12"

13.85' Lt.69+00.00 to 14.50' Lt.67+35.00 164.99 FEET
Total 164.99 FEET

Water Valves To Be Adjusted

17.27' Lt.66+60.82 1.00 EACH
19.99' Lt.66+63.09 1.00 EACH
Total 2 EACH

Water Service Line 3/4"

14.10' Rt.64+62.45 7.00 FEET
22.01' Lt.68+20.31 6.00 FEET
22.22' Lt.68+27.89 4.00 FEET
21.09' Lt.68+86.14 4.00 FEET
Total 21 FEET

Domestic Meter Vaults To Be Moved

14.10' Rt.64+62.45 1.00 EACH
22.01' Lt.68+20.31 1.00 EACH
22.22' Lt.68+27.89 1.00 EACH
21.09' Lt.68+86.14 1.00 EACH
Total 4 EACH

Manholes, Type A, 4' - Diameter, Type 11 Frame and Grate

13.50' Rt.64+66.25 1.00 EACH
14.50' Lt.67+35.00 1.00 EACH
Total 2 EACH

Inlets, Type A, With Salvaged Grate

20.00' Rt.64+66.25 1.00 EACH
Total 1 EACH

Manholes To Be Adjusted

11.79' Rt.65+08.36 1.00 EACH
6.65' Lt.65+25.03 1.00 EACH
Total 2 EACH

Removing Inlets

17.73' Rt.64+66.30 1.00 EACH
Total 1 EACH

Combination Concrete Curb and Gutter, Type B-6.12

13.00' Rt.64+00.00 to 13.00' Rt.64+81.80 81.80 FEET
13.00' Lt.64+00.00 to 13.01' Lt.64+46.79 46.79 FEET
13.01' Lt.64+46.79 to 15.60' Lt.65+25.57 79.63 FEET
13.00' Rt.64+81.80 to 14.79' Rt.65+25.77 44.20 FEET
14.00' Lt.66+54.68 to 14.00' Lt.69+00.00 245.32 FEET
12.00' Rt.66+87.76 to 12.00' Rt.69+00.00 212.24 FEET
Total 709.98 FEET

Thermoplastic Pavement Marking - Line 4"

11.67' Lt.64+00.00 to 14.27' Lt.65+26.16 126.40 FEET
11.67' Rt.64+00.00 to 13.46' Rt.65+26.16 126.02 FEET
0.00' Rt.64+00.00 to 0.00' Rt.65+26.16 31.54 FEET
12.67' Lt.66+54.68 to 12.67' Lt.69+00.00 245.32 FEET
11.68' Rt.66+54.68 to 10.67' Rt.69+00.00 245.39 FEET
0.00' Rt.66+54.69 to 0.00' Rt.69+00.00 61.33 FEET
Total 836 FEET

Segmental Concrete Block Wall

21.00' Rt.64+00.00 to 21.00' Rt.64+27.26 72.00 SF
Total 72 SF