

**CSI CONSOLIDATED SERVICES INC.**  
of Coles County

ENGINEERING - SURVEYING - CONSTRUCTION MANAGEMENT  
520 Jackson Avenue - P.O. Box 644 - Charleston, Illinois - 61920 - (217) 345-9511

**Trench Backfill**  
9.75' Lt.100+68.50 to 1.05' Lt.100+68.50 14.40 CY  
9.75' Rt.100+68.50 to 1.05' Lt.100+68.50 16.00 CY  
Total 30.4 CY

**Sub-Base Granular Material, Type B 4"**  
0.00' Lt.100+33.78 to 0.00' Lt.100+90.12 147.11 SY  
Total 147.11 SY

**Aggregate Base Course, Type B 8"**  
100+90.11 44.88 SY  
Total 44.88 SY

**Portland Cement Concrete Base Course 7"**  
0.00' Lt.100+33.77 to 0.00' Lt.100+90.11 115.81 SY  
Total 115.81 SY

**Bituminous Materials (Prime Coat)**  
100+90.11 22.44 GAL  
Total 22.44 GAL

**Aggregate (Prime Coat)**  
100+90.11 0.13 TONS  
Total 0.13 TONS

**Incidental Hot-Mix Asphalt Surfacing**  
100+90.11 7.54 TONS  
Total 7.54 TONS

**Portland Cement Concrete Driveway Pavement, 6 Inch**  
10.75' Lt.100+82.38 to 14.75' Lt.100+82.38 5.37 SY  
Total 5.37 SY

**Portland Cement Concrete Sidewalk 4 Inch**  
12.78' Lt.100+33.78 to 12.76' Lt.100+76.34 170.27 SF  
12.75' Lt.100+88.42 to 12.45' Lt.100+94.42 22.42 SF  
Total 192.69 SF

**Pavement Removal**  
0.00' Lt.100+33.82 to 0.00' Lt.101+10.19 155.28 SY  
Total 155.28 SY

**Driveway Pavement Removal**  
Lt.100+81.57 6.43 SY  
Total 6.43 SY

**Combination Curb and Gutter Removal**  
10.65' Lt.100+33.78 to 10.26' Lt.100+90.11 56.34 FEET  
Total 56.34 FEET

**Sidewalk Removal**  
12.61' Lt.100+33.78 to 12.65' Lt.100+73.60 127.30 SF  
14.14' Lt.100+39.37 to 19.77' Lt.100+39.97 11.27 SF  
12.81' Lt.100+89.36 to 12.45' Lt.100+94.42 18.94 SF  
Total 157.51 SF

**Storm Sewers, Class A, Type 2 12"**  
9.75' Lt.100+68.50 to 1.05' Lt.100+68.50 8.69 FEET  
9.75' Rt.100+68.50 to 1.05' Lt.100+68.50 10.80 FEET  
Total 19.49 FEET

**Manholes, Type A, 4' - Diameter, Type 1 Frame, Closed Lid**  
1.05' Lt.100+68.50 1.00 EACH  
Total 1 EACH

**Inlets, Type A, Type 11 Frame and Grate**  
9.75' Lt.100+68.50 1.00 EACH  
9.75' Rt.100+68.50 1.00 EACH  
Total 2 EACH

**Manholes To Be Adjusted**  
0.76' Lt.100+87.32 1.00 EACH  
Total 1 EACH

**Removing Inlets**  
10.08' Lt.100+90.92 1.00 EACH  
Total 1 EACH

**Filling Manholes**  
3.11' Rt.100+84.52 1.00 EACH  
Total 1 EACH

**Combination Concrete Curb and Gutter, Type B-6.12**  
10.23' Rt.100+33.81 to 10.25' Rt.101+37.85 104.02 FEET  
10.28' Lt.100+33.82 to 10.25' Lt.100+90.15 56.33 FEET  
Total 160.35 FEET

DCR	
DRAWN	
DATE	
CHECKED	
DATE	
APPROVED	
DATE	
REVISED	
DATE	

SCALES	N/A
--------	-----

**4th Street**  
**Plan and Profile**

Sheet No.  
**22**  
of 57 Sheets