

CSI CONSOLIDATED SERVICES INC.
of Coles County

ENGINEERING - SURVEYING - CONSTRUCTION MANAGEMENT
520 Jackson Avenue - P.O. Box 644 - Charleston, Illinois - 61920 - (217) 345-9511

DCR	DATE	CHECKED	DATE	APPROVED	DATE	REVISED	DATE

SCALES	N/A
--------	-----

4th Street
Plan and Profile

Sheet No.
24
of 57 Sheets

Sub-Base Granular Material, Type B 4"

9.73' Lt.100+61.23 to 7.97' Lt.101+23.05 43.65 SY
12.70' Rt.100+61.23 to 12.04' Rt.101+23.05 18.84 SY
Total 62.49 SY

Portland Cement Concrete Base Course Widening 7"

8.47' Lt.100+61.23 to 6.71' Lt.101+23.05 26.39 SY
11.44' Lt.100+61.23 to 10.79' Rt.101+23.05 1.61 SY
Total 28 SY

Aggregate Surface Course, Type B

18.50' Lt.100+77.23 to 48.50' Lt.100+77.23 14.55 TONS
Total 14.55 TONS

Hot-Mix Asphalt Surface Removal - Butt Joint

0.00' Lt.101+03.05 to 0.00' Lt.101+23.05 37.97 SY
Total 37.97 SY

Portland Cement Concrete Driveway Pavement, 6 Inch

12.50' Lt.100+77.23 to 18.50' Lt.100+77.23 11.06 SY
Total 11.06 SY

Portland Cement Concrete Sidewalk 4 Inch

16.50' Lt.100+61.23 to 16.50' Lt.100+69.58 32.92 SF
17.44' Rt.100+61.23 to 17.78' Rt.101+22.90 245.04 SF
Total 277.96 SF

Combination Curb and Gutter Removal

7.46' Lt.100+61.23 to 7.96' Lt.101+23.05 61.82 FEET
12.49' Rt.100+61.23 to 12.08' Rt.101+23.05 61.82 FEET
Total 123.64 FEET

Sidewalk Removal

20.48' Rt.100+61.23 to 17.78' Rt.101+22.90 241.88 SF
Total 241.88 SF

Combination Concrete Curb and Gutter, Type B-6.12

12.00' Lt.100+61.23 to 12.00' Lt.100+93.20 31.97 FEET
12.90' Rt.100+61.23 to 12.00' Rt.100+74.60 13.41 FEET
12.00' Rt.100+74.60 to 12.00' Rt.101+23.05 48.45 FEET
12.00' Lt.100+93.20 to 7.97' Lt.101+22.98 30.06 FEET
Total 123.89 FEET

Thermoplastic Pavement Marking - Line 4"

10.67' Lt.100+61.23 to 6.61' Lt.101+23.05 62.09 FEET
11.55' Rt.100+61.23 to 10.67' Rt.101+23.05 61.86 FEET
Total 123.95 FEET

Segmental Concrete Block Wall

20.00' Lt.100+61.23 to 26.00' Lt.100+69.98 45.00 SF
Total 45 SF

Concrete Removal (special)

12.81' Rt.100+97.93 to 16.85' Rt.100+97.90 17.56 SF
Total 17.56 SF