

CSI CONSOLIDATED SERVICES INC.
of Coles County

ENGINEERING - SURVEYING - CONSTRUCTION MANAGEMENT
520 Jackson Avenue - P.O. Box 644 - Charleston, Illinois - 61920 - (217) 345-9511

Trench Backfill

38.84' Rt. 78+49.29 to 50.04' Lt. 78+56.25 14.30 CY
50.04' Lt. 78+56.25 to 293.16' Lt. 78+52.41 68.90 CY
Total 83.2 CY

Portland Cement Concrete Driveway Pavement, 6 Inch

76.68' Lt. 78+57.13 to 76.77' Lt. 78+51.70 24.59 SY
231.14' Lt. 78+57.51 to 230.85' Lt. 78+48.22 46.24 SY
Total 70.83 SY

Portland Cement Concrete Sidewalk 4 Inch

251.63' Lt. 78+49.63 to 293.94' Lt. 78+45.41 168.77 SF
50.13' Lt. 78+53.76 to 57.65' Lt. 78+53.95 38.05 SF
98.23' Lt. 78+54.04 to 212.18' Lt. 78+50.76 467.51 SF
Total 674.33 SF

Detectable Warnings

56.65' Lt. 78+53.92 10.21 SF
99.23' Lt. 78+54.01 8.00 SF
Total 18.21 SF

Driveway Pavement Removal

76.72' Lt. 78+54.41 24.45 SY
230.43' Lt. 78+55.01 27.46 SY
Total 51.91 SY

Combination Curb and Gutter Removal

50.03' Lt. 78+56.76 to 104.36' Lt. 78+58.42 54.35 FEET
Total 54.35 FEET

Sidewalk Removal

98.09' Lt. 78+53.68 to 294.02' Lt. 78+48.00 824.38 SF
Total 824.38 SF

Storm Sewers, Class A, Type 1 12"

38.85' Rt. 78+49.29 to 50.04' Lt. 78+56.26 89.16 FEET
50.04' Lt. 78+56.26 to 212.11' Lt. 78+53.70 162.09 FEET
Total 251.25 FEET

Storm Sewers, Class A, Type 2 12"

212.11' Lt. 78+53.70 to 293.16' Lt. 78+52.41 81.05 FEET
Total 81.05 FEET

Manholes, Type A, 4' - Diameter, Type 11 Frame and Grate

50.04' Lt. 78+56.26 1.00 EACH
Total 1 EACH

Inlets, Type A, Type 11 Frame and Grate

38.85' Rt. 78+49.29 1.00 EACH
Total 1 EACH

Combination Concrete Curb and Gutter, Type B-6.24

50.03' Lt. 78+56.76 to 104.36' Lt. 78+58.52 54.36 FEET
Total 54.36 FEET

Connection to Existing Manhole

293.16' Lt. 78+52.41 1.00 EACH
Total 1 EACH

DRAWN	DCR
DATE	
CHECKED	
DATE	
APPROVED	
DATE	
REVISED	
DATE	

SCALES	N/A
--------	-----

4th Street
Plan and Profile

Sheet No.
26
of 57 Sheets