SUMMARY OF QUANTITIES

URBAN

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 80% FED 20% STATE ROADWAY 0004	80% FED 13.3% STATE 6.7% VILLAGE OF PRAIRIE GROVE T.S. SIGNAL 0021	100% CRYSTAL LAKE FIRE DEPT. EVP 0021			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	190.5	190.5					
20101700	SUPPLEMENTAL WATERING	UNIT	2	2					
20200100	EARTH EXCAVATION	CU YD	3795	3795					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1981	1981					
20800150	TRENCH BACKFILL	CU YD	78.5	78.5					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	4934	4934					
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	7175	7175					
* 21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	758	758					
* 25000210	SEEDING, CLASS 2A	ACRE	1.33	1.33					
* 25000312	SEEDING, CLASS 4A	ACRE	0.16	0.16					
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	120	120					
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	120	120					
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	120	120					

SUMMARY OF QUANTITIES

URBAN

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 80% FED 20% STATE ROADWAY 0004	80% FED 13.3% STATE 6.7% VILLAGE OF PRAIRIE GROVE T.S. SIGNAL 0021	100% CRYSTAL LAKE FIRE DEPT. EVP 0021			
25100630	EROSION CONTROL BLANKET	SQ YD	7175	7175					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	148	148					
28000305	TEMPORARY DITCH CHECKS	FOOT	660	660					
28000400	PERIMETER EROSION BARRIER	FOOT	1887	1887					
28000500	INLET AND PIPE PROTECTION	EACH	2	2					
28000510	INLET FILTERS	EACH	17	17					
28100105	STONE RIPRAP, CLASS A3	SQ YD	26.4	26.4					
28200200	FILTER FABRIC	SQ YD	26.4	26.4					
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	184	184					
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	4934	4934					
35501302	HOT-MIX ASPHALT BASE COURSE, 4 1/2"	SQ YD	188	188					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	350	350					
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SQ YD	2246	2246					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.1	4.1					
40600300	AGGREGATE (PRIME COAT)	TON	20.5	20.5					

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pwidot\abreuah\dms99207\P114205-DESIGN.dgn	USER NAME = abreuah	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 12/12/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. RTE. 176 AT SMITH ROAD
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
335	146N-2	MCHENRY	65	3
		CONTRACT NO. 60K20		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT