SUMMARY OF QUANTITIES

URBAN

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 80% FED 20% STATE ROADWAY 0004	80% FED 13.3% STATE 6.7% VILLAGE OF PRAIRIE GROVE T.S. SIGNAL 0021	100% CRYSTAL LAKE FIRE DEPT. EVP 0021			
40600400	MIXTURE FOR CRACKS, JOINTS,	TON	8	8					
	AND FLANGEWAYS								
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT	SQ YD	53	53					
	JOINT								
40603090	HOT-MIX ASPHALT BINDER COURSE,	TON	574	574					
	IL-19.0, N90								
40603335	HOT-MIX ASPHALT SURFACE COURSE,	TON	40	40					
	MIX "D", N50								
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE	TON	1365	1365					
	COURSE, MIX "F", N90								
42001300	PROTECTIVE COAT	SQ YD	545	545					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	4200	4200					
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	415	415					
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	693	693					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	450	450					
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	23	23					

SUMMARY OF QUANTITIES

URBAN

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 80% FED 20% STATE ROADWAY 0004	80% FED 13.3% STATE 6.7% VILLAGE OF PRAIRIE GROVE T.S. SIGNAL 0021	100% CRYSTAL LAKE FIRE DEPT. EVP 0021			
44300200	STRIP REFLECTIVE CRACK CONTROL	FOOT	3893	3893					
	TREATMENT								
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	279	279					
48203015	HOT-MIX ASPHALT SHOULDERS, 4 1/2"	SQ YD	208	208					
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	1801	1801					
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2					
50105220	PIPE CULVERT REMOVAL	FOOT	73.5	73.5					
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2					
54002020	EXPANSION BOLTS 3/4 INCH	EACH	16	16					
54010303	PRECAST CONCRETE BOX CULVERTS 3' X 3'	FOOT	10	10					
54266618	CONCRETE END SECTION, STANDARD 542001, 18" 1:6	EACH	2	2					
~~54247110~~	~~GRATING FOR CONCRETE FLARED END SECTION 18"~~	~~EACH~~	~~2~~	~~2~~					
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	79.2	79.2					
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1370	1370					
55101300	STORM SEWER REMOVAL 27"	FOOT	79	79					

* SPECIALTY ITEMS

Rev.

FILE NAME = c:\pw_work\pwidot\dbrauch\dms99207\P94205-DESIGN.dgn	USER NAME = dbrauch	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 12/12/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. RTE. 176 AT SMITH ROAD
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
335	146N-2	MCHENRY	65	4

CONTRACT NO. 60K20

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT