SUMMARY OF QUANTITIES

URBAN

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 80% FED 20% STATE ROADWAY 0004	80% FED 13.3% STATE 6.7% VILLAGE OF PRAIRIE GROVE T.S. SIGNAL 0021	100% CRYSTAL LAKE FIRE DEPT. EVP 0021			
*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL,	FOOT	229		229				
		4" DIA.								
*	81400100	HANDHOLE	EACH	5		5				
*	81400200	HEAVY-DUTY HANDHOLE	EACH	3		3				
*	81400300	DOUBLE HANDHOLE	EACH	1		1				
*	86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1				
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.	FOOT	274			274			
		14 3C								
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.	FOOT	1234		1234				
		14 5C								
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.	FOOT	738		738				
		14 7C								
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO.	FOOT	932		932				
		14 1 PAIR								
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO.	FOOT	30		30				
		6 2 C								
*	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT	FOOT	415		415				
		GROUNDING CONDUCTOR, NO. 6 1C								

SUMMARY OF QUANTITIES

URBAN

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 80% FED 20% STATE ROADWAY 0004	80% FED 13.3% STATE 6.7% VILLAGE OF PRAIRIE GROVE T.S. SIGNAL 0021	100% CRYSTAL LAKE FIRE DEPT. EVP 0021			
*	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL	EACH	1		1				
		14 FT.								
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL	EACH	1		1				
		16 FT.								
*	87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1		1				
*	87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1		1				
*	87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1		1				
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8		8				
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4				
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH	FOOT	30		30				
		DIAMETER								
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION,	EACH	4		4				
		MAST-ARM MOUNTED								
*	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION,	EACH	2		2				
		BRACKET MOUNTED								
~~*~~	~~X8620200~~	~~UNINTERRUPTIBLE POWER SUPPLY, SPECIAL~~	~~EACH~~	~~1.0~~	~~1.0~~					

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pw1dot\bureauthdms99207*\114205-DESIGN.dgn	USER NAME = cdrauch	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 12/12/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. RTE. 176 AT SMITH ROAD
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
335	146N-2	MCHENRY	65	7

CONTRACT NO. 60K20

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT