

SHEET NO. INDEX OF SHEETS
TITLE

01	COVER SHEET
02	INDEX OF SHEETS AND LIST OF STANDARDS
03-09	SUMMARY OF QUANTITIES
10-16	STANDARD TRAFFIC SIGNAL DESIGN DETAILS (7 SHEETS)
17	TEMPORARY TRAFFIC SIGNAL INSTALLATION AND REMOVAL PLAN ILL. RTE. 64 (NORTH AVE.) AT SWIFT ROAD (SHEET 1 OF 2)
18	TEMPORARY TRAFFIC SIGNAL INSTALLATION AND REMOVAL PLAN ILL. RTE. 64 (NORTH AVE.) AT SWIFT ROAD (SHEET 2 OF 2)
19	TEMPORARY CABLE PLAN AND PHASE DESIGNATION DIAGRAM ILL. RTE. 64 (NORTH AVE.) AT SWIFT ROAD
20	SIDEWALK AND PAVEMENT MARKING REMOVAL PLAN ILL. RTE. 64 (NORTH AVE.) AT SWIFT ROAD
21	TRAFFIC SIGNAL INSTALLATION ILL. RTE. 64 (NORTH AVE.) AT SWIFT ROAD (SHEET 1 OF 2)
22	TRAFFIC SIGNAL INSTALLATION ILL. RTE. 64 (NORTH AVE.) AT SWIFT ROAD (SHEET 2 OF 2)
23	SIDEWALK AND PAVEMENT MARKING PLAN ILL. RTE. 64 (NORTH AVE.) AT SWIFT ROAD (SHEET 1 OF 2)
24	SIDEWALK AND PAVEMENT MARKING PLAN ILL. RTE. 64 (NORTH AVE.) AT SWIFT ROAD (SHEET 2 OF 2)
25	CABLE PLAN ILL. RTE. 64 (NORTH AVE.) AT SWIFT ROAD
26	PHASE DESIGNATION DIAGRAM AND SCHEDULE OF QUANTITIES ILL. RTE. 64 (NORTH AVE.) AT SWIFT ROAD
27	TEMPORARY TRAFFIC SIGNAL INSTALLATION PLAN AND REMOVAL PLAN ILL. RTE. 64 (NORTH AVE.) AT WEST RAMPS (SHEET 1 OF 2)
28	TEMPORARY TRAFFIC SIGNAL INSTALLATION PLAN AND REMOVAL PLAN ILL. RTE. 64 (NORTH AVE.) AT WEST RAMPS (SHEET 2 OF 2)
29	TEMPORARY CABLE PLAN AND TEMPORARY PHASE DESIGNATION DIAGRAM ILL. RTE. 64 (NORTH AVE.) AT WEST RAMPS
30	TRAFFIC SIGNAL INSTALLATION PLAN ILL. RTE. 64 (NORTH AVE.) AT WEST RAMPS (SHEET 1 OF 2)
31	TRAFFIC SIGNAL INSTALLATION PLAN ILL. RTE. 64 (NORTH AVE.) AT WEST RAMPS (SHEET 2 OF 2)
32	PAVEMENT MARKING PLAN ILL. RTE. 64 (NORTH AVE.) AT WEST RAMPS (SHEET 1 OF 2)
33	PAVEMENT MARKING PLAN ILL. RTE. 64 (NORTH AVE.) AT WEST RAMPS (SHEET 2 OF 2)
34	CABLE PLAN ILL. RTE. 64 (NORTH AVE.) AT WEST RAMPS
35	PHASE DESIGNATION DIAGRAM, EMERGENCY VEHICLE PREEMPTION SEQUENCE, AND SCHEDULE OF QUANTITIES ILL. RTE. 64 (NORTH AVE.) AT WEST RAMPS
36	TEMPORARY TRAFFIC SIGNAL INSTALLATION PLAN AND REMOVAL PLAN ILL. RTE. 64 (NORTH AVE.) AT EAST RAMPS (SHEET 1 OF 2)
37	TEMPORARY TRAFFIC SIGNAL INSTALLATION PLAN AND REMOVAL PLAN ILL. RTE. 64 (NORTH AVE.) AT EAST RAMPS (SHEET 2 OF 2)
38	TEMPORARY CABLE PLAN AND TEMPORARY PHASE DESIGNATION DIAGRAM ILL. RTE. 64 (NORTH AVE.) AT EAST RAMPS
39	TRAFFIC SIGNAL INSTALLATION PLAN ILL. RTE. 64 (NORTH AVE.) AT EAST RAMPS (SHEET 1 OF 2)
40	TRAFFIC SIGNAL INSTALLATION PLAN ILL. RTE. 64 (NORTH AVE.) AT EAST RAMPS (SHEET 2 OF 2)
41	PAVEMENT MARKING PLAN ILL. RTE. 64 (NORTH AVE.) AT EAST RAMPS (SHEET 1 OF 2)
42	PAVEMENT MARKING PLAN ILL. RTE. 64 (NORTH AVE.) AT EAST RAMPS (SHEET 2 OF 2)
43	CABLE PLAN ILL. RTE. 64 (NORTH AVE.) AT EAST RAMPS
44	PHASE DESIGNATION DIAGRAM, EMERGENCY VEHICLE PREEMPTION SEQUENCE, AND SCHEDULE OF QUANTITIES ILL. RTE. 64 (NORTH AVE.) AT EAST RAMPS
45	TEMPORARY INTERCONNECT PLAN ILL. RTE. 64 (NORTH AVE.) FROM SWIFT RD. TO ILL. RTE. 53 (ROHLWING RD.) (SHEET 1 OF 2)
46	TEMPORARY INTERCONNECT PLAN ILL. RTE. 64 (NORTH AVE.) FROM SWIFT RD. TO ILL. RTE. 53 (ROHLWING RD.) (SHEET 2 OF 2)
47	TEMPORARY INTERCONNECT SCHEMATIC ILL. RTE. 64 (NORTH AVE.) FROM SWIFT RD. TO ILL. RTE. 53 (ROHLWING RD.)
48	INTERCONNECT PLAN ILL. RTE. 64 (NORTH AVE.) FROM SWIFT RD. TO ILL. RTE. 53 (ROHLWING RD.) (SHEET 1 OF 2)
49	INTERCONNECT PLAN ILL. RTE. 64 (NORTH AVE.) FROM SWIFT RD. TO ILL. RTE. 53 (ROHLWING RD.) (SHEET 2 OF 2)
50	INTERCONNECT SCHEMATIC ILL. RTE. 64 (NORTH AVE.) FROM SWIFT RD. TO ILL. RTE. 53 (ROHLWING RD.)
51	MAST ARM MOUNTED STREET NAME SIGNS
52	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
53	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)
54	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
55	ARTERIAL ROAD INFORMATION SIGN

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.

THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (841) 705-4470 72 HOURS IN ADVANCE OF BEGINNING WORK.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION. THIS SHALL INCLUDE LOCATING THE MAST ARM FOUNDATIONS AND VERIFYING THE MAST ARMS LENGTHS.

THE EXACT LOCATION OF ALL UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR BEFORE ORDERING ANY MATERIALS AND STARTING ANY WORK FOR LOCATIONS OF UTILITIES. LOCALLY OWNED EQUIPMENT, LEASED ENFORCEMENT CAMERA SYSTEM FACILITIES AND IDOT UNDERGROUND FACILITIES, CONTACT THE LOCAL COUNTIES, MUNICIPALITIES AND IDOT FOR LOCATES. THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 OR 811, IN THE CITY OF CHICAGO CONTACT DIGGER AT (12) 744-7000 FOR FIELD LOCATIONS OF BURIED UTILITIES (48 HOURS NOTIFICATION REQUIRED).

IF THIS CONTRACT REQUIRES THE SERVICES OF AN ELECTRICAL CONTRACTOR, THE CONTRACTOR SHALL BE RESPONSIBLE AT HIS/HER OWN EXPENSE FOR LOCATING EXISTING IDOT ELECTRICAL FACILITIES PRIOR TO PERFORMING ANY WORK. IF THIS CONTRACT DOES NOT REQUIRE THE SERVICES OF AN ELECTRICAL CONTRACTOR, THE CONTRACTOR MAY REQUEST ONE FREE LOCATE FOR EXISTING IDOT ELECTRICAL FACILITIES FROM THE DISTRICT ONE ELECTRICAL MAINTENANCE CONTRACTOR PRIOR TO THE START OF ANY WORK. ADDITIONAL REQUESTS MAY BE AT THE EXPENSE OF THE CONTRACTOR. THE LOCATION OF UNDERGROUND TRAFFIC FACILITIES DOES NOT RELIEVE THE CONTRACTOR OF THEIR RESPONSIBILITY TO REPAIR ANY FACILITIES DAMAGED DURING CONSTRUCTION AT THEIR EXPENSE.

THE CONTRACTOR SHALL CHECK THE PROPOSED TRAFFIC SIGNAL EQUIPMENT LOCATIONS FOR OVERHEAD UTILITY CONFLICTS. THE CONTRACTOR SHALL COORDINATE ANY CONFLICTS WITH THE UTILITY COMPANIES AND RESIDENT ENGINEER BEFORE ORDERING MATERIALS.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, LOCAL GOVERNMENT AGENCIES AND IDOT.

RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCLUDED IN THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIAN, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGED TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

STD. NO.	DESCRIPTION
000001 - 06	ABBREVIATIONS, SYMBOLS AND PATTERNS
001001 - 02	REINFORCEMENT BARS, AREAS, WEIGHTS AND SPACING
001006	DECIMAL EQUIVALENTS OF AN INCH AND FOOT
424001 - 07	PERPENDICULAR CURB RAMPS FOR SIDEWALKS
424006 - 01	DIAGONAL CURB RAMPS FOR SIDEWALKS
424021 - 01	DEPRESSED CORNER FOR SIDEWALKS
442201 - 03	PATCHING, CLASS C AND D
606001 - 04	CURB TYPE B AND COMBINATION CURB AND GUTTER, CONCRETE
606301 - 04	MEDIAN, CONCRETE
701006 - 04	OFF-RD OPERATIONS, 2L, 2W, 15' (4.5m) TO 24" (600mm) FROM PAVEMENT EDGE
701011 - 03	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701101 - 03	OFF-RD OPERATIONS, MULTILANE, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
701301 - 04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701421 - 05	LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS ≥ 45 MPH TO 55 MPH
701422 - 05	LANE CLOSURE, MULTILANE, FOR SPEEDS ≥ 45 MPH TO 55 MPH
701458 - 02	PARTIAL EXIT RAMP CLOSURE FREEWAY /EXPRESSWAY
701501 - 06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701601 - 08	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701701 - 08	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701901 - 02	TRAFFIC CONTROL DEVICES
720001 - 01	SIGN PANEL MOUNTING DETAILS
780001 - 03	PAVEMENT MARKINGS
805001 - 01	ELECTRICAL SERVICE INSTALLATION DETAILS
814001 - 02	HANDHOLES
814006 - 02	DOUBLE HANDHOLES
857001 - 01	STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES
862001 - 01	UNINTERRUPTIBLE POWER SUPPLY (UPS)
873001 - 02	TRAFFIC SIGNAL GROUNDING & BONDING
877001 - 05	STEEL MAST ARM ASSEMBLY AND POLE 16" THROUGH 55'
877002 - 02	STEEL MAST ARM ASSEMBLY AND POLE 56" THROUGH 75'
878001 - 09	CONCRETE FOUNDATION DETAILS
880001 - 01	SPAN WIRE MOUNTED SIGNALS AND FLASHING BEACON INSTALLATION
880006 - 01	TRAFFIC SIGNAL MOUNTING DETAILS
886001 - 01	DETECTOR LOOP INSTALLATIONS
886006 - 01	TYPICAL LAYOUTS FOR DETECTION LOOPS

NOTES FOR TEMPORARY TRAFFIC SIGNALS

- ALL CONTROL EQUIPMENT INCLUDING EMERGENCY PRE-EMPTION AND COMMUNICATION DEVICES FOR THE TEMPORARY TRAFFIC SIGNAL(S) SHALL BE FURNISHED BY THE CONTRACTOR.
- ONLY CONTROLLERS SUPPLIED BY ONE OF THE DISTRICT APPROVED CLOSED LOOP EQUIPMENT MANUFACTURERS WILL BE APPROVED FOR USE AT TEMPORARY SIGNAL LOCATIONS. ALL CONTROLLERS USED FOR TEMPORARY TRAFFIC SIGNALS SHALL BE FULLY ACTUATED NEMA MICROPROCESSOR BASED WITH RS232 DATA ENTRY PORTS COMPATIBLE WITH EXISTING MONITORING SOFTWARE APPROVED BY IDOT DISTRICT 1, INSTALLED IN A NEMA TS2 CABINET. ONLY ONE BRAND OF CONTROLLER WILL BE ACCEPTED FOR ANY ONE CONTRACT.
- ALL TRAFFIC SIGNAL SECTIONS AND PEDESTRIAN SIGNAL SECTIONS SHALL BE LED 12" DIAMETER. HEADS SHALL BE PLACED AS INDICATED ON THE TEMPORARY TRAFFIC SIGNAL PLAN OR AS DIRECTED BY THE ENGINEER. PEDESTRIAN SIGNALS SHALL INCLUDE SOLID INTERNATIONAL SYMBOLS. PEDESTRIAN SIGNALS WITH COUNTDOWN TIMERS SHALL BE USED WHEN THE EXISTING INSTALLATION UTILIZES COUNTDOWN TYPE OR AS DIRECTED BY THE ENGINEER. COUNTDOWN TYPE PEDESTRIAN SIGNALS ARE NOT TO BE INSTALLED AT A RAILROAD INTERSECTION. THE CONTRACTOR SHALL FURNISH ENOUGH CABLE SLACK TO RELOCATE HEADS TO ANY POSITION ON THE SPAN WIRE OR AT LOCATIONS ILLUSTRATED ON THE PLANS FOR CONSTRUCTION STAGING. THE TEMPORARY TRAFFIC SIGNAL SHALL REMAIN IN OPERATION DURING ALL SIGNAL HEAD RELOCATIONS. EACH TEMPORARY TRAFFIC SIGNAL HEAD SHALL HAVE ITS OWN CABLE FROM THE CONTROLLER CABINET TO THE SIGNAL HEAD.
- ALL EXISTING STREET NAME AND INTERSECTION REGULATORY SIGNS SHALL BE REMOVED FROM EXISTING POLES, RELOCATED AND SECURELY FASTENED TO THE SPAN WIRE OR WOOD POLE AS DIRECTED BY THE ENGINEER.
- ANY TEMPORARY SIGNAL WITHIN AN EXISTING CLOSED LOOP TRAFFIC SIGNAL SYSTEM SHALL BE INTERCONNECTED TO THAT SYSTEM USING SIMILAR BRAND CONTROL EQUIPMENT AT NO ADDITIONAL COST TO THE CONTRACT.
- THE TEMPORARY TRAFFIC SIGNAL SHALL HAVE THE SIGNAL HEAD DISPLAYS, SIGNAL HEAD PLACEMENTS AND CONTROLLER PHASING MATCH THE EXISTING TRAFFIC SIGNAL, AT THE TIME OF THE TURN ON, IF NO TRAFFIC STAGING IS IN PLACE OR WILL NOT BE STAGED ON THE DAY OF THE TURN ON.
- UNINTERRUPTIBLE POWER SUPPLY (UPS) SYSTEMS SHALL BE INSTALLED AND MADE OPERATIONAL AT TEMPORARY TRAFFIC SIGNAL INSTALLATIONS WHERE UPS IS INSTALLED AT THE EXISTING TRAFFIC SIGNAL. TEMPORARY TRAFFIC SIGNALS AT RAILROAD INTERSECTIONS, AND TEMPORARY TRAFFIC SIGNALS AT INTERSECTIONS WITH FIRE STATION ACTUATED EMERGENCY VEHICLE PRE-EMPTION, OR WHEN INDICATED ON THE PLANS.
- TRAFFIC SIGNAL MANAGEMENT SYSTEMS SHALL BE MAINTAINED IN OPERATION AS INDICATED ON THE PLANS OR AS DIRECTED BY THE ENGINEER. REQUIRED EQUIPMENT SHALL BE AS SHOWN ON THE PLANS AND THE CONTRACTOR SHALL PLACE THE EQUIPMENT IN OPERATION TO THE SATISFACTION OF THE ENGINEER AND THE AGENCY RESPONSIBLE FOR THE TRAFFIC SIGNAL MANAGEMENT SYSTEM.
- DETECTION AT TEMPORARY TRAFFIC SIGNALS SHALL BE INCLUDED FOR ALL APPROACHES OF THE INTERSECTION UNLESS INDICATED OTHERWISE ON THE PLANS. THE DETECTION SYSTEM MUST MEET THE SPECIFICATIONS OF DISTRICT 1 AND THE CONTRACTOR SHALL PLACE THE DETECTORS INTO OPERATION TO THE SATISFACTION OF THE ENGINEER. DETECTION SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN TEMPORARY TRAFFIC SIGNAL INSTALLATION PAY ITEM.
- WHEN PAN, TILT, ZOOM CAMERAS ARE INSTALLED AT THE EXISTING INTERSECTION OR ARE CALLED FOR IN THE PLANS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING AND MAINTAINING THE CAMERAS TO THE SATISFACTION OF THE ENGINEER AND THE AGENCY RESPONSIBLE FOR THE CAMERAS.

FILE NAME * #FILE#	USER NAME * #USER#	DESIGNED - PKG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS AND LIST OF STANDARDS			F.A.P. RTE. 307	SECTION 2012-029-TS	COUNTY DuPAGE	TOTAL SHEETS 55	SHEET NO. 02
		DRAWN - EA, MG	REVISED -		SCALE: NONE	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO. 60T80		
		CHECKED - PKG	REVISED -		FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT							
		DATE - 12/7/2012	REVISED -									