

URBAN

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				ILL. RTE. 64 (NORTH AVE.) AT SWIFT RD.	ILL. RTE. 64 (NORTH AVE.) AT WEST RAMPS	ILL. RTE. 64 (NORTH AVE.) AT EAST RAMPS	INTERCONNECT	EMERGENCY VEHICLE PREEMPTION
				90% FEDERAL 5% STATE 5% COUNTY	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	100% VILLAGE OF LOMBARD
				0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	961	961	-	-	-	-
42400800	DETECTABLE WARNINGS	SO FT	78	78	-	-	-	-
44000100	PAVEMENT REMOVAL	SO YD	14.6	14.6	-	-	-	-
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	230	230	-	-	-	-
44201857	CLASS D PATCHES, TYPE IV, 17 INCH	SO YD	51	51	-	-	-	-
48301000	PROTECTIVE COAT	SO YD	51	51	-	-	-	-
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	125	125	-	-	-	-
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	43	43	-	-	-	-
60608250	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.06	FOOT	5	5	-	-	-	-
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	1.67	1.67	1.66	-	-
67100100	MOBILIZATION	LSUM	1	0.33	0.33	0.34	-	-
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	LSUM	1	0.33	0.33	0.34	-	-
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	LSUM	1	0.33	0.33	0.34	-	-
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LSUM	1	0.33	0.33	0.34	-	-