

URBAN

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				ILL. RTE. 64 (NORTH AVE.) AT SWIFT RD.	ILL. RTE. 64 (NORTH AVE.) AT WEST RAMPS	ILL. RTE. 64 (NORTH AVE.) AT EAST RAMPS	INTERCONNECT	EMERGENCY VEHICLE PREEMPTION
				90% FEDERAL 5% STATE 5% COUNTY	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	100% VILLAGE OF LOMBARD
				0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3372	1928	754	690	-	-
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	11859	4193	3490	4176	-	-
87301790	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 2 2C	FOOT	1119	-	601	518	-	-
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	163	129	-	34	-	-
87501900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	4076	1078	1415	1583	-	-
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	12	2	5	5	-	-
87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	3	-	1	2	-	-
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	3	3	-	-	-	-
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1	-	-	1	-	-
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1	-	1	-	-	-
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	3	1	1	1	-	-
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1	1	-	-	-	-
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1	1	-	-	-	-
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	2	-	1	1	-	-