

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0005 90% FED 10% STATE	TRAFFIC SIGNAL 0021 90% FED 5% STATE 5% CITY OF HARVEY	EVP 0021 100% CITY OF HARVEY	INTER CONNECT 0021 90% FED 10% STATE
20101200	TREE ROOT PRUNING	EACH	1		1		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	28	28			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	105.5	105.5			
25200110	SODDING, SALT TOLERANT	SO YD	105.5	105.5			
28000510	INLET FILTERS	EACH	9	9			
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SO YD	72	72			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.5	4.5			
40600300	AGGREGATE (PRIME COAT)	TON	22	22			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8	8			
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	229	229			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	56.5	56.5			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	543	543			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0005 90% FED 10% STATE	TRAFFIC SIGNAL 0021 90% FED 5% STATE 5% CITY OF HARVEY	EVP 0021 100% CITY OF HARVEY	INTER CONNECT 0021 90% FED 10% STATE
42001300	PROTECTIVE COAT	SO YD	167	167			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	950	950			
42400800	DETECTABLE WARNINGS	SO FT	196.4	196.4			
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	5530	5530			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	200	200			
44000600	SIDEWALK REMOVAL	SO FT	1030	1030			
50400510	FIRE HYDRANTS TO BE REMOVED & REPLACED	EACH	1				1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	50	50			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	150	150			
*66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	500	500			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
*66900450	SPECIAL WASTE PLANS & REPORTS	L SUM	1	1			
67100100	MOBILIZATION	L SUM	1	1			
*66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			

UTILITY
0043
100%
HARVEY

50400510 FIRE HYDRANTS TO BE REMOVED & REPLACED EACH 1 1

*66900200 NON-SPECIAL WASTE DISPOSAL CU YD 500 500

*66900450 SPECIAL WASTE PLANS & REPORTS L SUM 1 1

*66900530 SOIL DISPOSAL ANALYSIS EACH 3 3

Rev. 2-20-13

FILE NAME *	USER NAME * gulluomf	DESIGNED -	REVISED -
DATE * 12/21/2012	PLOT SCALE * 100000' / 1"	DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES		F.A.P. RTE. 397	SECTION 104TS-11(2)	COUNTY COOK	TOTAL SHEETS 38	SHEET NO. 3
SCALE:	SHEET NO. OF SHEETS STA.	TO STA.	CONTRACT NO. 60T92			
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT						