

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		ROADWAY 0005 90% FED 10% STATE	TRAFFIC SIGNAL 0021 90% FED 5% STATE 5% CITY OF HARVEY	EVP 0021 100% CITY OF HARVEY	INTER CONNECT 0021 90% FED 10% STATE		
20101200	TREE ROOT PRUNING	EACH	1		1				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	105.5	105.5					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	105.5	105.5					
25200110	SODDING, SALT TOLERANT	SO YD	5	5					
28000510	INLET FILTERS	EACH	9	9					
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SO YD	72	72					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	45	45					
40600300	AGGREGATE (PRIME COAT)	TON	22	22					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8	8					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	229	229					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	56.5	56.5					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	543	543					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		ROADWAY 0005 90% FED 10% STATE	TRAFFIC SIGNAL 0021 90% FED 5% STATE 5% CITY OF HARVEY	EVP 0021 100% CITY OF HARVEY	INTER CONNECT 0021 90% FED 10% STATE		
42001300	PROTECTIVE COAT	SO YD	167	167					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	950	950					
42400800	DETECTABLE WARNINGS	SO FT	196.4	196.4					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	5530	5530					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	200	200					
44000600	SIDEWALK REMOVAL	SO FT	1030	1030					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	50	50					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	150	150					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					

FILE NAME :	USER NAME : gulloumfp	DESIGNED -	REVISED -
ORIG. WORK: 12/21/2012	DATE: 12/21/2012	DRAWN -	REVISED -
PLOT SCALE : 1000000' / 1"		CHECKED -	REVISED -
PLOT DATE : 12/21/2012		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.P. RTE. 397	SECTION 104TS-1(12)	COUNTY COOK	TOTAL SHEETS 38	SHEET NO. 3
CONTRACT NO. 60T92				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				