

| SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | | | | SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | | | | | |
|-----------------------|---|--------|------------------|--------------------------------|--|------------------------------|--------------------------------------|--|-----------------------|------------|---|------|------------------------|--------------------------------|--|------------------------------|--------------------------------------|--|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | ROADWAY 0005 90% FED 10% STATE | TRAFFIC SIGNAL 0021 90% FED 5% STATE 5% CITY OF HARVEY | EVP 0021 100% CITY OF HARVEY | INTER CONNECT 0021 90% FED 10% STATE | | | CODE NO | ITEM | UNIT | TOTAL QUANTITIES | ROADWAY 0005 90% FED 10% STATE | TRAFFIC SIGNAL 0021 90% FED 5% STATE 5% CITY OF HARVEY | EVP 0021 100% CITY OF HARVEY | INTER CONNECT 0021 90% FED 10% STATE | | |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 | 1 | | | | | | * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 145 | 145 | | | | | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 2 | 2 | | | | | | * 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 500 | 500 | | | | | |
| 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 850 | 850 | | | | | | * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 55 | 55 | | | | | |
| 70300210 | TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS | SO FT | 103 | 103 | | | | | | * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 60 | 60 | | | | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 3450 | 3450 | | | | | | 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 30 | 30 | | | | | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 145 | 145 | | | | | | 80500020 | SERVICE INSTALLATION - POLE MOUNTED | EACH | 1 | | 1 | | | | |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 500 | 500 | | | | | | 81028200 | UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA. | FOOT | 977 | | 657 | | 320 | | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 55 | 55 | | | | | | 81028210 | UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA. | FOOT | 104.5 | | 104.5 | | | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SO FT | 95 | 95 | | | | | | 81028220 | UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA. | FOOT | 78 | | 78 | | | | |
| * 72000100 | SIGN PANEL - TYPE 1 | SO FT | 15 | | 15 | | | | | 81028230 | UNDERGROUND CONDUIT, GALVANIZED STEEL, 3 1/2" DIA. | FOOT | 42 | | 42 | | | | |
| * 72000200 | SIGN PANEL - TYPE 2 | SO FT | 13.75 | | 13.75 | | | | | 81028240 | UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA. | FOOT | 235 | | 235 | | | | |
| * 72400310 | REMOVE SIGN PANEL - TYPE 1 | SO FT | 8.3 | | 8.3 | | | | | | | | | | | | | | |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SO FT | 103 | 103 | | | | | | | | | | | | | | | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 3450 | 3450 | | | | | | | | | | | | | | | |

* Specialty Items