

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				IL 53 AT LARAWAY RD	100% CITY OF JOLIET
				90% FED 10% STATE	EVP
				TRAFFIC SIGNALS	0021
				0021	0021
				URBAN	URBAN
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	213	213	
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1	1	
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1	1	
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1	1	
87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1	1	
87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1	1	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8	8	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	41	41	
87900200	DRILL EXISTING HANDHOLE	EACH	5	5	
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8	8	
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2	2	
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2	2	
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2	2	
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10	10	
88200510	TRAFFIC SIGNAL BACKPLATE, RETROREFLECTIVE	EACH	10	10	

FILE NAME *	USER NAME * blumbergpo	DESIGNED - PB / LP	REVISED -
ct:\pwork\pwork\blumbergpo\08323734\011713-SHT-TS.dgn		DRAWN - PB / LP	REVISED -
PLOT SCALE * 1/8"=1'-0"		CHECKED - SM	REVISED -
PLOT DATE * 12/4/2012		DATE - 11/30/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
(SHEET 2 OF 3)**

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
B46 A	2-TS (12)	WILL	15	4
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60Y95	

Rev.