

URBAN
100% STATE

SUMMARY OF QUANTITIES

CONSTRUCTION
TYPE CODE

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 0004	STRUCTURE 016-1292 0040
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	922	273	649
20101000	TEMPORARY FENCE	FOOT	300	300	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	761	224	537
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	348	348	
25200110	SODDING, SALT TOLERANT	SO YD	348	348	
28000305	TEMPORARY DITCH CHECKS	FOOT	32	32	
25000310	SEEDING, CLASS 4	ACRE	0.25	0.25	
28000400	PERIMETER EROSION BARRIER	FOOT	450	450	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25	25	
28000510	INLET FILTERS	EACH	12	12	
25100630	EROSION CONTROL BLANKET				
28100107	STONE RIPRAP, CLASS A4	SO YD	70.1	70.1	
28200200	FILTER FABRIC	SO YD	70.1	70.1	
31100500	SUBBASE GRANULAR MATERIAL, TYPE A 6"	SO YD	413.7	413.7	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2	
40600300	AGGREGATE (PRIME COAT)	TON	0.2	0.2	
40600635	LEVELING BINDER MACHINE METHOD, N70	TON	17.4	17.4	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	40.5	40.5	
42001200	PAVEMENT FABRIC	SO YD	413.7	413.7	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	136.1	136.1	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	748	748	
44000100	PAVEMENT REMOVAL	SO YD	1493.7	1493.7	
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	136.1	136.1	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2339	2339	
44000600	SIDEWALK REMOVAL	SO FT	748	748	
44003100	MEDIAN REMOVAL	SO FT	10483	10483	
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SO YD	413.7	413.7	
44201297	DOWEL BARS 1"	EACH	186	186	
44213200	SAW CUTS	FOOT	166	166	
44213204	TIE BARS 3/4"	EACH	186	186	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1	

URBAN
100% STATE

SUMMARY OF QUANTITIES

CONSTRUCTION
TYPE CODE

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 0004	STRUCTURE 016-1292 0040
50300300	PROTECTIVE COAT	SO FT	11179.8	11179.8	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	33,500	9810	23,690
50800515	BAR SPLICERS	EACH	70	30	40
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERTS	CU YD	138.5	40.4	98.1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	25	25	
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	1	1	
60500060	REMOVING INLETS	EACH	1	1	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	8637.9	8637.9	
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SO FT	891	891	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	665.5	665.5	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	836	836	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	307.9	307.9	
60623800	CONCRETE BARRIER MEDIAN	SO FT	353.1	353.1	
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	162.5	162.5	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	22122	22122	
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	576	576	
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	157	157	
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	103	103	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	6959	6959	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	400	400	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	400	400	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	73	73	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4080	4080	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	431	431	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	99.4	99.4	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	84	84	

• SPECIALTY ITEM

Rev. 2-20-13

Rev.

FILE NAME: P:\2011\111887_Fed-Var-PH\111887-WB-Willow-Road\Sheet104-0160604-ht-500.dgn
 PLOT SCALE: 1/8"=1'-0"
 USER NAME: KILLIAN, Professional Services



200 225D Street, Suite 216, Lombard, IL 60148
 630.785.0110 voice, 630.839.1566 fax
 www.mps-ll.com
MILLENNIA PROFESSIONAL SERVICES

DESIGNED	TVN	REVISED	
DRAWN	MJW	REVISED	
CHECKED	TVN	REVISED	
DATE	12/27/2012	REVISED	

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

WILLOW ROAD

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	1920.01-B-R	COOK	60	3
CONTRACT NO.			60W04	
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT				

P:\2011\111887_Fed-Var-PH\111887-WB-Willow-Road\Sheet104-0160604-ht-500.dgn